



TYPE S POLE BOLT KIT (SN1790S)		
ITEM	QUANTITY	DESCRIPTION
A	4	5/8"φ x 3" LONG BOLT, 2 NUTS AND 2 WASHERS.
B	6	1"φ x 4 1/2" LONG BOLT, NUT AND 2 WASHERS.
C	4	NUT AND WASHER FOR 1" BOLT.
D	2	LARGE HANDHOLE COVER WITH 2-3/8"φ x 1" LONG BOLTS AND 2 WASHERS.
E	1	3/8"φ x 1 1/4" LONG BONDING BOLT WITH 1 NUT AND 2 WASHERS.
G	1	PLASTIC END CAP
H	4	LEVELLING SHIMS

NOTES

- SEE STANDARD SPECIFICATIONS & SPECIAL PROVISIONS FOR ADDITIONAL INFORMATION.
- POLE SHAFT SHALL BE INSTALLED PLUMB.
- ALL SHAFTS, ARMS AND EXTENSIONS SHALL BE SUPPLIED WITH A GALVANIZED FINISH.
- APPLY GREASE TO ANCHOR BOLTS.
- TOUCH UP ANY SCRATCHES IN GALVANIZED SURFACES WITH COLD GALVANIZING COMPOUND.

NOT TO SCALE

POLE ASSEMBLY DETAIL

No.	Description	Date
J		
I		
H		
G		
F		
E		
D		
C		
B		
A	NEW DRAWING	DEC03
REVISION		

TYPE S SHAFT, ARMS AND EXTENSIONS ASSEMBLY AND BOLT KIT

GENERAL ASSEMBLY



BRITISH COLUMBIA

Ministry of Transportation and Highways

Drawing No.

MS321.3