



BOREHOLE LOG 06-MW-23

Borehole Number: 06-MW-23

Client: ICL Holdings Ltd.

Levelton Project ID: 806-0131

Project: Detailed Site Investigation Site Location: 10091, 10111, 10131, 10151 River Dr. Richmond, BC

Depth (m)	Description	Symbol	Depth/Elev. (m)	Well and Backfill Details	SAMPLE		HEADSPACE VAPOUR CONC. ppmV (0-300) 50 150 250	COMMENTS
					Number	Type		
0	Ground Surface		0.0					
0-1	Asphalt							
1-1.2	Sand medium, moist - wet, brown, no odour		1.2		06-MW-23@0.6	7		Analyzed for metals
1.2-1.6	- brown-grey, moist - wet below 1.22m		1.6		MW-23@1.4-1.5m	10		Analyzed for metals
1.6-3.0	Clay trace silt, trace sand, damp - moist, dark grey, slight decomposing odour		3.0		MW-23@1.5-1.6m	10		Analyzed for styrene
3.0-4.6	Silt sandy, some clay, wet, dark grey, slight decomposing odour		4.6		06-MW-23@2.4m	10		Not analyzed
4.6-6.1	Sand medium, wet, dark grey - black, slight chemical - like odour		6.1		06-MW-23@3.6m	8		Analyzed for VOC, DUP 4 collected
6.1-6.1	Sand medium, wet, dark grey - black, slight chemical - like odour				MW-23@4.8-5m	6		Analyzed for VOC, EPH, PAH
6.1-6.1	End of Drill Hole							Shallow well backfill: concrete (0-0.3m) bentonite (0.3 - 0.6m) filter sand (0.6 -1.8m) with screen from 0.75-1.5m backfill: concrete (0-0.3m) bentonite (0.3-0.6m, 1.8-4.6m) filter sand (0.6-1.8m, 4.6-6.1m) with screen from 4.8-6.1m

Logged By: Jay Rao

Drilled by: Beck Drilling & Env. Services Ltd.

Datum: Local

Date Drilled: May 3, 2006

Water Level Recorded on:

Sheet No: 1 of 1