



PGL

LOG OF BORING BH12M

(Page 1 of 1)

Client: Vancouver Lotus Pacific Holdings
 Site Address: 845 Marine Drive,
 North Vancouver, BC

Installation Date : Dec. 27-28/07
 Contractor : Beck
 Drill Type : Solid Stem Auger
 Logged By : Michelle Stockwell
 Well Installed : Yes

Well Type : PVC (2" diameter)

Project# 3116-01.02

| Depth in Meters | USCS | GRAPHIC | Water Level | | SAMPLES | SAMPLE NAME | Vapour ppm | REMARKS |
|-----------------|----------------------|---------|--|--------------------------|---------|---------------|------------|---------|
| | | | ▼ 3.070m December 27, 2007 | ▽ 3.105m January 8, 2008 | | | | |
| | | | DESCRIPTION | | | | | |
| 0 | SP | | Concrete slab with rebar. | | | | | |
| 0.5 | SP | | Light brown medium to coarse SAND. (Fill) | | ☒ | BH12M-1 | 150 | |
| 1.0 | GP | | Grey coarse SAND and fine to coarse sub-angular GRAVEL. Trace cobbles, dry and compact. (Fill) | | ☒ | BH12M-2 | 125 | |
| 2.0 | SM | | Dark brown fine sandy SILT with trace round and sub-angular fine gravel. Trace wood debris (roots), moist. Mild hydrocarbon odour. Soil moist at 2.29m | | ☒ | BH12M-3 | 2%LEL | |
| 3.0 | SP | | Light brown medium to fine SAND with trace wood chunks (roots). Moist and compact. | | ☒ | BH12M-4/GR108 | 400 | |
| 4.0 | SM | | Brown fine sandy SILT with trace wood debris (roots). Moist and compact. | | ☒ | BH12M-6 | 1%LEL | |
| 5.0 | SM | | | | ☒ | BH12M-7 | 450 | |
| 5.5 | SM | | | | ☒ | BH12M-8 | 375 | |
| 6.0 | End of Hole @ 6.10m. | | | | | | | |

Well: BH12M

