



LEVELTON Levelton

0875410 BC Ltd.
675 Marine Drive, West Vancouver

12-BH/MW17

Pg 1 of 1

Project No: RI11-0999-10

Depth (ft) (m)	Description	Symbol	Depth (m)	Sample		Well and Backfill Details	Headspace Vapour Concentration ▲ (ppm.) ▲			Laboratory Analysis /Comments
				Number/ID	Type		10	100	1000	
5 2 10 4 15 6 25 8 30 10 35 12 40	Fill: Grey medium to coarse SAND, trace gravel, damp, no odour - more gravel below 0.9 m		1.2	BH17-1 @ 0.3 m			19.2			BTEX/VPHs
				BH17-2 @ 0.9 m			<<			
	Fill: Grey silty SAND & GRAVEL, damp, no odour - more silt between 1.5 m and 1.8 m		1.8	BH17-3 @ 1.5 m			1.3			
	Grey SAND & GRAVEL, damp, no odour		3.0	BH17-4 @ 2.3 m			1.9			
	Grey GRAVEL, some coarse sand, damp, no odour		4.0	BH17-5 @ 3.4 m			2.6			
	Brown SILT & GRAVEL, some sand, cobbles, damp, no odour		4.6	BH17-6 @ 4 m			1.8			
	No recovery between 4.6 m and 6.1 m		6.1	BH17-7 @ 4.6 m			1.7			
	Grey SAND, some gravel and wood, wet, no odour Low recovery		7.6	BH17-8 @ 7 m/QAQC14			2.7			
	Grey coarse SAND & GRAVEL, cobbles, slight hydrocarbon odour Low recovery		9.1	BH17-9 @ 9 m			<<			
	Low recovery		10.7	BH17-10 @ 10.7 m			<<			
	Bottom of hole at 12.20 meters			12.2	BH17-11 @ 12.2 m					

HAZMAT 2012-09 BH-SV LOGS.GPJ LEVELTON DATA TEMPLATE.GDT 14/11/13

Sample Symbols	Backfill Symbols	Soil Symbols	Notes	Logged By	MM
	Filter Sand	SAND		Drilled/ Excavated By	MM
	Bentonite	Sand and Gravel		Date Drilled or Excavated	Downrite Drilling
	Solid Pipe	Gravel		Elevation (grade)	18/09/2012
	Slotted Pipe	Disturbed Sample		Water Level Recorded On	Elev. 8.67 m
	Slough/Cuttings			Drill Method	20/09/2012
	Concrete				Sonic Core
<p>This log is for environmental purposes only. This log is the sole property of Levelton Consultants Ltd. and cannot be used or duplicated in anyway without express written permission.</p>					