



GEOTACTICS MEDIA ENGINEERING (2007) LTD.

P.O. Box 624, Sechelt B.C. V0N 3A0 T. 604.740.0920
 #4-1877 Field Road, Sechelt B.C. F. 604.740.0932

BORING NUMBER BH11-1

PAGE 1 OF 1

CLIENT Leeon Projects Ltd.
 PROJECT NUMBER SC-0756
 DATE STARTED 11/1/28 COMPLETED 11/1/28
 DRILLING CONTRACTOR Uniwide Drilling Ltd.
 DRILLING METHOD Auger: Solid Stem
 LOGGED BY CD CHECKED BY MY
 NOTES See Figure 2 for BH Locations

PROJECT NAME 3- or 4-level Mixed Commercial-Residential Building
 PROJECT LOCATION Lot Q DL 1328 Gibsons Way
 GROUND ELEVATION 0 m E.G.S. HOLE SIZE 150mm Diameter
 GROUND WATER LEVELS:
 AT TIME OF DRILLING ---
 AT END OF DRILLING ---
 AFTER DRILLING ---

GEOTACTICS MEDIA ENGINEERING BH PLOTS SC-0756_BHLOGS_2011.01.28.GPJ GINT STD CANADA.GDT 11/3/3

DEPTH (m)	GRAPHIC LOG	MATERIAL DESCRIPTION	SAMPLE TYPE NUMBER	RECOVERY % (RQD)	POCKET PEN. (kPa)	DRY UNIT WT. (Mg/m ³)	DCPT BLOW COUNT			
							20	40	60	80
0.0 - 0.5		TOPSOIL, sand and gravel, some silt, loose, dark brown, moist to wet					▲			
0.5 - 1.0		SAND, trace gravel, trace silt, loose, brown, moist					▲			
1.0 - 2.0		SILTY SAND & GRAVEL, trace cobbles, compact to medium dense, brown, moist					▲			
2.0 - 7.0		SILT, trace sand and gravel, trace clay, firm to stiff, grey, mottled, moist					▲			
7.0 - 7.62		SANDY SILT with GRAVEL, till-like, very stiff to hard, grey, mottled, moist					▲			>>

Bottom of hole at 7.62 m.