

Depth (m)	OVA	Blows / 6"	Sample #	Symbols	Date Drilled: Feb 21, 1996	LOCATION: 340 Ewen Avenue	Piezometer Installation	PIEZOMETER CONSTRUCTION DETAILS	ANALYSIS		
					Rig: B61	ELEVATION: 2.52 m (T. O. P.)					
					Contractor: ENVIROTECH	CO-ORDINATES:					
					Sampling: solid stem	SOIL DESCRIPTION					
					NOTES:						
0.0					PAVEMENT			WELL PROTECTOR CONCRETE			
0.0 - 0.2	22 ppm		19		SAND - GREY, COARSE GRAINED, LOOSE, MOIST			BENTONITE			
0.2 - 0.5					SILTY SAND - GREY, FINE GRAINED SAND AND SILT, MOIST, COMPACT			FEBRUARY 27, 1996			
0.5 - 1.5					SAND - GREY, COARSE GRAINED, LOOSE, MOIST - SLIGHT HYDROCARBON ODOUR			FILTER SAND			
1.5 - 2.5					SAND - GREY, COARSE GRAINED, LOOSE, MOIST - SLIGHT HYDROCARBON ODOUR			CUTTINGS			
2.5 - 3.0	27 ppm		19B		SAND - GREY, COARSE GRAINED, LOOSE, MOIST - SLIGHT HYDROCARBON ODOUR						
3.0 - 3.5					SAND - GREY, COARSE GRAINED, LOOSE, MOIST - SLIGHT HYDROCARBON ODOUR						
3.5 - 4.0					SAND - GREY, COARSE GRAINED, LOOSE, MOIST - SLIGHT HYDROCARBON ODOUR						
4.0 - 4.5					SAND - GREY, COARSE GRAINED, LOOSE, MOIST - SLIGHT HYDROCARBON ODOUR						
4.5 - 4.7					SAND - GREY, COARSE GRAINED, LOOSE, MOIST - SLIGHT HYDROCARBON ODOUR						
4.7 - 4.9					SAND - GREY, COARSE GRAINED, LOOSE, MOIST - SLIGHT HYDROCARBON ODOUR						
4.9 - 5.0					PEAT - LITTLE SILT AND CLAY, BROWN, MOIST, SOFT						
5.0 - 5.5					EOH @ 4.57 M			NOTE: SOIL SAMPLES COLLECTED BUT NOT ANALYSED			
5.5 - 6.0											
6.0 - 6.5											
6.5 - 7.0											
7.0 - 7.5											
7.5 - 8.0											
8.0 - 8.5											
8.5 - 9.0											
9.0 - 9.5											
9.5 - 10.0											