

BOREHOLE LOG

CLIENT: Davis & Company
 JOB NO: 5-069-03.02
 SITE LOCATION: 32700 Mission Way, Mission, B.C.

WELL NO: OW1
 DATE: 92 02 10
 DATUM: Surface

NORECOL SUPERVISOR: Robert Bulger
 CONTRACTOR: Sonic Drilling
 DRILLING TYPE: Sonic

INSTALLATION DETAILS
 Screen Type - 5 cm diameter PVC, 0.25 mm slot
 Sand Type - Silica 16B
 Flush mounted well protector Bentonite - Chips

DEPTH metres	SOIL DESCRIPTION		SAMPLE		BLOWS	OTHER
			INT	NAME		
0.0	Surface Conditions: Gravel Fill to a depth of 0.05 m					
1.0	Loose, grey, SAND, dry near surface, becoming wet with depth		30101			
				Bentonite Seal		water
				30102		
				Silica Sand		
3.0	Grey, wet, Sandy, GRAVEL					
4.0	Wet, Grey, SILT					
5.0	E.O.H.					
6.0	Screen interval 2.0 - 5.0 m					