

CLIENT : Brook Development Planning Inc.
 PROJECT: Shellmont Plaza
 JOB#: 43378-001

BOREHOLE LOG

BOREHOLE NO: NDM99-5

LOCATION: n/a

ELEVATION: Top of Casing 0.87m
 Ground 0.96m

HEADSPACE VAPOUR CONCENTRATION	BLOW COUNT	CLASS CODE	USCS	SAMPLE TYPE	SAMPLE I.D.	DEPTH (m)	DEPTH (ft)	LITHOGRAPHY	WELL CONSTRUCTION DETAILS	WELL INSTALLATION & WATER LEVEL	DEPTH (m)
3.6ppm		SP			NDM99-5/ 01 <i>JOC</i>	1	1	CONCRETE SAND (FILL) , brown, fine with some medium grained, wet at 0.6m, grey below 1.0m	0 - 0.1m Concrete		1
6.5ppm					NDM99-5/ 02 <i>JOC</i>	2	2		0.1 - 0.4m Bentonite Seal		
4.2ppm					NDM99-5/ 03	3	3		0.4 - 3.0m Filter Sand Pack		
4.1ppm		MH			NDM99-5/ 04	4	4	SILT , grey-light brown, some clay, trace sand, saturated	0.6 - 3.0m PVC Screen		2
						5	5				
						6	6				
						7	7				
						8	8				
						9	9				9
						10	10	EOH at 3.0m			10
						11	11				11
						12	12				12
						13	13				13
						14	14				14
						15	15				15
						16	16				16
						17	17				17
						18	18				18

Borehole Dia. 5 1/4"

DRILLING CONTRACTOR: Uniwide Drilling Ltd.
 DRILLING METHOD: Solid Stem Auger
 DATE: July 20, 1999
 LOGGED BY: Calin Nan

SAMPLE TYPE: CORE SAMPLE
 GRAB SAMPLE
 SPLIT SPOON SAMPLE
 NO RECOVERY