

Borehole/Well No.: MW11-02

Client: Coastland Wood Industries Ltd.

Project: Detailed Site Investigation

Location: 942 Haliburton Street, Nanaimo, BC

Target: Adjacent to Veneer Plant Fabricating Shop

Date: April 22 & May 9, 2011

Logged by: AM & EB

TerraWest File No.: CWHS11-02

PO Box 46003, 2642 Quadra St.

Victoria, BC, V8T 5G7

1.866.500.1553

www.terrawest.ca

SUBSURFACE PROFILE				SAMPLE			VOC Concentration	Well Completion Details
Depth	Symbol	Description	Elev.	Number	Lab Analysis	Type	ppm 750 1500 2250 %LEL 10 30 50 70 90	
0		Ground Surface	0					
0		Asphalt						
1		Gravel, silty sandy clay, sticky moist, soft, slight plasticity, brown same throughout.						
2								
3	1	becoming less moist with depth						
4								
5								
6				MW11-02	HC, CP	G		
7								
8			-8					
9		Till, sandy grey, damp, trace gravel, dense not hard, fine silt.						
10	3		-10					
11		Clay, sandy silty, with trace gravel, brown, moist, soft some grey sand lenses.						
12								
13	4	wet, trace free water at 13-15'						
14				MW11-02	HC, CP	G		
15								
16	5							
17								
18		refusal						
19								
20	6	End of Borehole	-20	MW11-02	HC, CP	G		

Drilled by: Beck Drilling and Environmental Services Ltd.

Drill Method: Solid Stem Auger

Hole Size: 4"

Datum: Ground Surface

Total Depth: 19.5

Sheet: 1 of 1