



MORROW ENVIRONMENTAL CONSULTANTS INC.

Client :
Imperial Oil Limited

Borehole No. : PW00-2

Location :
1811 Island Highway Campbell River, BC

(Page 1 of 1)

Drilling Contractor : Drillwell Enterprises Ltd.
Drilling Method : Cable Tool
Borehole Dia. (m) : 0.25
Pipe/Slotted Pipe Dia. (m): 0.20, 0.20

Ground Surf Elev. (m) : 9.554
Top of Casing Elev. (m) : 10.418

Project Number : V5255
Borehole Logged By : NC
Date Drilled : 2000 08 31
Log Typed By : JJC

Depth in Metres	Sample Type	Water/LPH Levels ▽ Water Level 1 ▽ Water Level 2 ◆ LPH Level 1 ◆ LPH Level 2	Stratigraphy Plot	Sample Type	Sample Number	Blow Count	% Recovery	Soil Vapour (% LEL)	Well Name 1 : PW00-2	
									0	20
0	SAND (FILL), medium to coarse grained sand, some rounded to subrounded gravel, grey, loose, moist.								Bentonite	
1										
2	SAND and GRAVEL, coarse grained, rounded gravel, grey, dense, wet.									
3										
4	GRAVEL, rounded coarse grained, cobbles, trace sand and silt, grey, wet.									
5										
6										
7										
8	GRAVEL, coarse grained, some cobbles, trace silt and sand, rounded to subrounded gravel and cobbles, grey, wet.									
9										
10	CLAY, soft, medium plastic, some subrounded to rounded gravel, grey, wet.								Slough	
11	End of borehole at 10.1 m.									
12										

Notes:

Print Date: 2001 03 30. Approved by: Peters, Mike