

BOREHOLE RECORD

BH1

CLIENT Beutel Goodman Real Estate Group

PROJECT No. BCV60671.5

LOCATION Capilano Mall, 935 Marine Drive, North Vancouver

DATUM Local

DATES: BORING December 16, 1998

WATER LEVEL December 18, 1998

TPC ELEV. 99.21

DEPTH (m)	ELEVATION (m)	SOIL DESCRIPTION	SOIL SYMBOL	WATER LEVEL	DEPTH (ft)	VAPOUR CONCENTRATIONS				SAMPLES			WELL CONSTRUCTION	
						● %LEL	▲ ppm	TYPE	NUMBER	N-VALUE				
0	99.26					● 20	▲ 100	40	60	80				
	99.2	75 mm ASPHALT	[Cross-hatch symbol]											
	98.9	Brown, compact, SAND and GRAVEL (FILL), trace silt, damp	[Wavy symbol]											
		Brown, firm to very soft, ORGANIC SILT, some sand and clay, moist	[Wavy symbol]		2		▲				SS	1	15	
			[Wavy symbol]		4		▲				SS	2	7	
			[Wavy symbol]		6		▲				SS	3	4	
		- trace sand	[Wavy symbol]		8		▲				SS	4	2	
		- sand seam, wet	[Wavy symbol]		10									
	95.7		[Wavy symbol]		12			▲			SS	5	1	
		Brown, very loose, SILT, sandy, some clay, wet	[Vertical lines symbol]		14		▲				SS	6	1	
			[Vertical lines symbol]		16		▲				SS	7	1	
	94.0	END OF BOREHOLE at 5.2 m	[Vertical lines symbol]		18									
			[Vertical lines symbol]		20									
			[Vertical lines symbol]		22									
			[Vertical lines symbol]		24									
			[Vertical lines symbol]		26									

- bentonite seal

- 50 mm ID slotted PVC with geosox and silica sand backfill

LABORATORY ANALYSES: BH1-4 analyzed for EPH and lead.
BH1-3 analyzed for metals.
Groundwater analyzed for LEPH and HEPH.

