

Project No: 507-0150

Borehole No.: TP-1

Project: Stage 2 Preliminary Site Investigation

Client: Magellan Holdings Ltd.

Date: 11 June 2007

Location: 613 Herald Street, Victoria, BC

Logged By: Wendy Beairsto, B.Sc.

SUBSURFACE PROFILE			SAMPLE		Maximum Combustible Vapour Level	Well Data	Analytical Chemistry (Soil)
Depth (m)	Symbol	Description	Depth (m)	Sample Number			
0							
1		<p>Sand and Gravel (Fill) Compact, coarse-grained, large angular gravels, small rounded gravels, bricks pieces, wood bits, white specks, dark brown, damp, no hydrocarbon odour or staining.</p>	-0.76	Sa1	G		Metals
2		<p>Sand (Native) Compact, silty, fine to medium-grained sand, damp, moderate hydrocarbon staining, low old hydrocarbon odour. Becomes moist below 1.83m. Increased silt content below 2.29m.</p>	-2.9	Sa2	G		VOCs, VPHs, EPHs
3		<p>Silt and Sand (Native) Soft to firm, fine to medium-grained sand, brown, plastic, moist, moderate hydrocarbon staining, no hydrocarbon odour.</p>	-3.7	Sa3	G		EPHs
4		End of Test Pit at 3.66m		Sa4	G		
5				Sa5	G		
6				Sa6	G		
7				Sa7	G		

Completed By: Don Mann Excavating Ltd.

LEVELTON CONSULTANTS LTD.
 760 Enterprise Crescent
 Victoria, BC
 V8Z 6R4

Method: 310E Backhoe

Ground Elevation (m): N/A

Date: 11 June 2007

Sheet: 1 of 1