



LEVELTON
Engineering Solutions

Project No: 1804-0395-01

BOREHOLE LOG: BH108 / MW103

Project: Detailed Site Investigation

Client: Atlantic Furniture Manufacturing Ltd.

Location: 632 Belgrave Way, Annacis Island

City / Province: Delta, British Columbia

Logged by: Sonny Bernales

SUBSURFACE PROFILE				Type	Recovery	Volatile Organic Concentration ppm 700 2100	Well Data	Lab Analysis/ Comments
Depth	Symbol	Description	Sample Number					
0		Ground Surface						
0-1		Asphalt Pavement Asphalt pavement (Parking Area)	BH108-1		0			BH108-1 analyzed for VOCs, VPH, EPHs and metals
1-3		Sand Loose, well sorted coarse sand; dry; no hydrocarbon odour.	BH108-2		0			
3-4			BH108-3		0			
4-7		Sand Loose, well sorted coarse grained; wet at 3.0 m; no hydrocarbon odour.	BH108-4		0			
7-9			BH108-5		0			BH108-5 analyzed for metals
9-11		Silt Dense/stiff silt, some clay; wet; not hydrocarbon odour.	BH108-6		0			BH108-6 analyzed for VOCs, VPH, EPHs and metals
11-14			BH108-7		0			BH108-7 analyzed for metals
14-18		Silt Loose to dense sandy silt; wet; not hydrocarbon odour.	BH108-8		0			14 May 2004 Groundwater Sample (MW103) analyzed for VOCs, VPH and metals

Drilled by: Beck Drilling & Env. Services Ltd.

Drill Method: hollow stem auger

Drill Date: 12 May 2004

Hole Size: 51 mm

Levelton Consultants Ltd.
#150 - 12791 Clarke Place,
Richmond, British Columbia
V6V 2H9
Phone: (604) 278-1411
Fax: (604) 278-1042

Datum: local

Checked by:

Sheet: 1 of 1