


PLAN




TYPICAL STIRRUP LAYOUT AT GIRDER ENDS

STRINGER IDENTIFICATION	
SKEW ANGLE, RIGHT OR LEFT	
DEPTH OF STRINGER IN mm	
MK. 500 / 10 / E or I / 20° R/L	
LENGTH OF STRINGER IN METERS	
EXTERIOR OR INTERIOR STRINGER	


ESTIMATED MASS	
STRINGER MK. 500/10/E/20°	10 570 kg
STRINGER MK. 500/10/I/20°	10 180 kg

NOTES


- DESIGN SPECIFICATIONS: CAN/CSA-S6-06, BC M&T SUPPLEMENT TO S6-06.
- DESIGN LOAD: LIVE LOAD: CL-625 & BCL-625, DEAD LOAD: DESIGNED FOR 100mm CONCRETE OVERLAY.
- STRINGERS SHALL BE MANUFACTURED IN ACCORDANCE WITH THE M.O.T. STANDARD SPECIFICATION 415: MANUFACTURE OF PRECAST AND PRESTRESSED CONCRETE MEMBERS.
- PRESTRESSING STRANDS SHALL BE 13# (7 WIRE) UNCOATED LOW RELAXATION STRANDS, C.S.A. G279M-1982, 1862 MPa GRADE OR EQUIVALENT. MINIMUM ULTIMATE TENSILE STRENGTH = 184 kN/STRAND. STRAND TENSION IMMEDIATELY BEFORE RELEASE = 136.2 kN/STRAND.
- CONCRETE: MINIMUM COMPRESSIVE STRENGTH OF CONCRETE AT TIME OF RELEASE OF STRANDS = 27MPa, AT 28 DAYS = 35MPa.
- REINFORCING STEEL SHALL CONFORM TO C.S.A. G30.18M GRADE 400R.
- REINFORCING STEEL SHALL HAVE 35mm MINIMUM COVER UNLESS OTHERWISE NOTED.
- ALL REINFORCING MARKED "ME" IS EPOXY COATED.
- LAP OF BARS FOR SPLICES TO BE AS FOLLOWS UNLESS NOTED OTHERWISE:
10M BARS - 450
10ME BARS - 600
SPLICES TO BE STAGGERED.
- BOTTOM EDGES OF STRINGERS SHALL BE CHAMFERED 20mm.
- LIFTING DEVICES SATISFACTORY TO THE ENGINEER SHALL BE PROVIDED OVER THE BEARINGS. ONLY VERTICAL LIFTS WILL BE PERMITTED. CARE SHALL BE TAKEN TO PREVENT SUDDEN IMPACT LOADS ON THE STRINGERS.
- ENDS OF PRESTRESSING STRANDS SHALL BE TREATED AS FOLLOWS:
EMBEDDED IN CONCRETE: PAINTED WITH A GALVANIZING AGENT.
EXPOSED: A MINIMUM 3mm COAT OF THIXOTROPIC EPOXY AS SHOWN. MANUFACTURER'S INSTRUCTIONS TO BE STRICTLY ADHERED TO.
- TOP OF BOXES SHALL HAVE A SAND BLASTED FINISH FOR CONCRETE OVERLAY AND FLOAT FINISH FOR NO OVERLAY OR MEMBRANE AND ASPHALT OVERLAY.
- THE CONCRETE IMMEDIATELY SURROUNDING ALL LIFTING DEVICES SHALL HAVE A FORMED RECESS 65mm DEEP. THE RECESS SHALL BE THOROUGHLY SANDBLASTED IN THE SHOP. AFTER ERECTION, THE LIFTING DEVICE SHALL BE BURNT OFF AT THE BOTTOM OF THE RECESS AND THE RECESS SHALL BE PATCHED WITH AN APPROVED NON-SHRINK GROUT.




LIFTING DEVICE RECESS DETAIL SCALE 1:5



ELEVATION EXTERIOR STRINGER (AS SHOWN) INTERIOR STRINGER (SIMILAR EXCEPT AS NOTED) SCALE 1:20




TYPICAL SECTION THROUGH EXTERIOR STRINGER SCALE 1:10




NOTE: ALL NOT SHOWN SIMILAR TO EXTERIOR STRINGER

TYPICAL SECTION THROUGH INTERIOR STRINGER SCALE 1:10



PRESTRESSING STRAND LAYOUT SCALE 1:10



THIXOTROPIC EPOXY LAYOUT SCALE 1:10

Rev	Date	Description	Init
C	07-06-28	DESIGN CODE REVISIONS	W.H.K.
B	93-02-04	GENERAL	J.E.S.
A	92-11-12	LIFTING DEVICE RECESS & NOTES	K.L.

REVISIONS

BRITISH COLUMBIA Ministry of Transportation & Infrastructure Bridge Engineering

STANDARD TWIN CELL CONCRETE BOX STRINGER MK. 500/10/E/20° & MK. 500/10/I/20°

DESIGNED BY	IM	DATE	07-07-28
CHECKED BY	RM	DATE	07-07-10
DRAWN BY	WHK	DATE	07-06-28
SCALE	AS NOTED		
NEGATIVE No.			

FILE No.	PROJECT No.	REG.	DRAWING No.
			2978-7