

Kamloops
March 12, 2002

Pilot 2

Design and Installation of Embedded Culverts

Part 3: Construction





Part 3: Construction

6 Main Topics

- 1. Planning & preparation**
- 2. Construction layout control**
- 3. Diversion works**
- 4. Culvert installation**
- 5. Construction practices**
- 6. As-built**

1. Planning & Preparation

- Approvals & design in place?
- Timing of construction
 - In-stream window
 - dry period





Deliver all materials and mobilize equipment in advance of when required



- Excavators
- Substrate importation equipment
- Construction survey and layout
- Manpower
- Substrate material
- Riprap
- Water pumps
- Filter fabrics

2. Construction Control Layout




- Lay out the worksite, establishing field references for construction





Horizontal Control





Horizontal Control



3. Diversion Works



- All work should be conducted “in the dry”



Isolate the work area from running water to work in the dry



- Bypass channel





Install diversion well in advance of excavation works



- Site will determine available options

- Gravity systems
- Pump(s)





Install a Cofferd Dam at the Upstream End





Alternatives for Gravity Bypasses



- Alternatives for gravity bypasses
- Plastic Pipes
- Water Sock



Open ditch



- If a lined ditch is used ensure material is rugged and capacity of ditch is adequate to carry all anticipated flow conditions





Salvage Fish from the Isolated work area



- Fish should be salvaged from isolated work zone (permit required from fishery agency)



Fish barriers



- Install barriers to ensure fish cannot migrate into work zone

4. Culvert Installation

- Grade control
- Bed preparation
- Backfilling & compaction
- Construction seepage control
- Substrate installation



Grade Control



- Determine design elevation and slope (as determined from profile) using construction level
- Check elevations frequently as excavation progresses



Bed preparation



- Culvert foundation should be sound native soil or well compacted granular material



Backfilling & Compaction



- Culvert foundation, trench walls and backfill material must be kept free of logs, stumps, limbs or rock that could damage or weaken the pipe
- Avoid entraining snow and ice



Backfilling & Compaction




- Culverts are soil steel structures

- Require soil compaction using mechanical vibratory equipment





Typical Backfill Envelope for Pipe-Arch



- Haunch tamping
- Compact to springline



Erosion Protection



- Riprap should be installed at culvert inlet and outlet as per the design
- Establish vegetation






Construction Seepage Control



Seepage is inevitable into excavation



Construction Seepage Control



- Seepage should be filtered through the forest floor before re-entering a stream

• Seepage should be controlled to maintain a dry worksite



Sump @ outlet



Substrate Installation



- Creativity required for substrate placement



Substrate Installation



- Installation crew



Substrate Installation




- Wheel barrow
- Time consuming, labour intensive, limited working room





Substrate Installation

- Use of a small excavator



- Limited working room, time consuming



Substrate Installation




- Portable conveyor belt system





Substrate Installation



- Level line painted to guide substrate placement



Substrate Installation



- Range of sizes required

- Remember “rule of thumb” to duplicate natural stream substrate sizes





Substrate Installation

- Substrate material must be well mixed and contain enough fines to fill voids to keep water on the surface





Substrate Installation



**Monitor depth of
fill frequently**



Substrate Installation



- Large rock installed for hydraulic roughness
- Large rock should project from streambed




Substrate Installation



- Fines should be “washed-in” to ensure a good seal




Substrate Installation



- Fine tuning - thalweg (low flow channel) should be created within culvert substrate



Weir Construction



- Install as per design
- Ensure gaps between boulders to allow for fish passage



5. Construction Practices



- Use appropriate practices to minimize impacts to the stream and riparian zone



Construction Sediment Control



**Sediment controls
installed during
construction**




Design and Installation of Embedded Culverts




Kamloops, March 12, 2002

Manage drainage during construction



- Permanent runoff/drainage controls installed during construction

6. As-built documentation



- “As-built” drawing should be completed for installed culvert
- Document “as-built” according to design as well as record for monitoring

Summary

- All approvals and design should in place prior to commencement
- Layout construction according to design using precise instruments
- Install embedded culvert “in the dry” by diverting streamflow prior to construction
- Install embedment material according to design specs
- Have a sediment control plan in place
- Document installation with “as-builts”