



Kootenay Business Area Worker Field Handbook









"HOW TO USE THE WORKER HANDBOOK"

□ Be	efore starting work, workers to get familiar contents of handbook
aı	nd specifically worker expectations and responsibilities e.g.
Ei	mergency Response, Environmental Field Procedures, working around
W	ater features, reporting req. etc.
□ Ke	eep it handy and recommended in equipment along with maps and
рі	roject plan information.
□Н	elpful to reference for emergency situations
□Н	elpful reference tool for;
	✓ Emergency situations,
	√ Worker tailgate training sessions,
	✓ Project pre-work & inspection/monitoring activities
	✓ Fuel handling conformance
	✓ Promoting forest stewardship & best practices
	✓ Supports BCTS clients meeting their EMS/SFM obligations
	ontents of Worker Field Handbook is also posted on BC Timber Sales
W	ebsite https://www2.gov.bc.ca/gov/content/industry/forestry/bc-
<u>ti</u>	mber-sales/forest-certification/
For	more information contact the local BCTS staff or contact Paul
Ren	dall, Certification Standards Officer at 1-236-352-8114 or by email at
<u>Pau</u>	.Rendall@gov.bc.ca

March 2020

Worker Field Handbook Table of Contents

Content	Page(s)
How to Use Worker Field Handbook	Inside Front Cover
Environmental Emergency Response Plan (Fire, spills, erosion)	2-7
Water Disruption Emergency Response Plan	8-9
EFP #01 General	10-11
EFP #02 Project Supervision	12-13
EFP #03 Development and Planning	14-15
EFP #04 Roads, Bridges, and Culverts	16-18
EFP #05 Harvesting	19-20
EFP #06 Fuel Handling	21-29
Fuel Handling Pictorial "useful guide"	31-35
Species of Management Concern Guide	34
EFP #09 Invasive Plants	35
Roadside Residue Handling Best Practices	36-37
"To support secondary manufacturing"	30 37
Bird Nest Encounter Operating Procedures	38-39
Wildlife Habitat Feature Order Kootenay Boundary	40-41
TKO Wet Weather Operating Guide	42-44
Construction/Rehab Skid Trails Steep Slope BMP	45-48
Deactivation Guidance	49-50
SFI General Awareness "Sustainable Forestry Practices"	51-52
Working with Indigenous Peoples Summary	53-54
EMS Incident Reporting Requirements	Inside Back Cover
EMS Tailgate Training	Back Cover



For BCTS Client Use

Part A Core Information					
Worksite Details					
Project (TSL or Contract)#					
Physical location of activity:					
Latitude:			Longitude:		
Latitude:			Longitude:		
Latitude:			Longitude:		
Duration of Activities:	Date:	Year	Month	Day	

Company Contact Information

24 hr Contact Name and Phone (s) #:

Company Name/Email:

Other Key Emergency Contact(s) #:

Environmental Emergency Contact Information

Forest Fire Reporting : 1-800-663-5555 or * 5555 on the Cantel and Telus networks

Spill Reporting and other Environmental Emergencies to Land & Water:

1-800-663-3456 Emergency Management BC (EMBC).

Natural Gas Leaks: Contact EMBC and utility company (if known): FortisBC **1-800-663-9911** (Northeast, Fraser Valley, South), Pacific Northern Gas (Northwest and Northeast) **1-800-663-1173**, Enbridge (Northeast and Fraser Valley) **1-800-663-9931**

CANUTEC (Canadian Transport Emergency Centre): **1-613-996-6666** or *666 on cell phone

BC Timber Sales Contact:

Cameron Paterson 250-551-0364, George Edney 250-354-8411, Nelson Office 250-825-1100

Part B Supplemental Information. <u>It is the licensee, permittee and contractor's responsibility to</u> ensure that all the phone numbers are correct.

General Contact Informatio	n
Police: 911	WorkSafeBC: 1-888-621-7233 (24 hrs/day,7 days/week)
Ambulance: 911	Joint Rescue Coordination Centre: 1-800-567-5111 or cell #727
Fire Department: 911	Hospital:
Poison Control Centre: 1-800-567-8911	Water Taxi / Ferry: Arrow Park 250-837-8634 or 778-206- 0384, Needles 250-269-7222, Galena 778-206-0384 all operated by WaterBridge Ferries Inc. Kootenay Lake 250-354-7656 operated by Western Pacific Marine

July 1, 2018



For BCTS Client Use

Helicopter / Aircraft: Wildfire Status Website: Wildfire Status

BC Wildfire Service Phone and Fax # (Circle Fire Centre in which activities are occurring):

Coastal:250 951-4201 Fax:250-954-0819 / **Southeast:250 365-4001 Fax:250-365-9919** / Kamloops:250 554-7701 Fax 250-376-6549 Cariboo:250 989-2600 Fax 250-989-2672 / Prince George:250 960-2300 Fax:250 562-6210 / Northwest:250-847-6633 Fax 250-847-2737

Part C Core Information

FOREST FIRE PREPAREDNESS AND RESPONSE

Initial Fire Response

- 1. Stop operations and notify the rest of the crew.
- 2. Report Forest Fires immediately to the BC Wildfire Service (BCWS) and BCTS.
- **3.** The person reporting the fire shall remain in contact to communicate details of the fire suppression activities taken and what additional activities may be required.
- **4.** The remaining crew shall begin immediate action to control and extinguish the fire, if practicable and safe to do so, to the extent of their training and competence.
- **5.** The person in charge of a crew taking action to control a fire is responsible for continuing fire control activities until relieved by the licensee/contractor representative or BCWS personnel.

If Alone

- Take immediate action on the fire if you believe you can safely control it yourself. Report the fire to BCWS and the licensee/contractor representative as soon as you feel that the fire can be left alone without spreading out of control.
- If the fire is beyond your ability, notify the BCWS immediately and follow their instructions. DO NOT take action on an intense fire yourself.
- ☑ Complete an Incident Report Form (CHK-009 or equivalent) and submit to BCTS.

Fire Roles and Responsibilities

Prior to Start-Up and During Operations

☑ For All Industrial Activities

- Determine fire response equipment for the type of operation and associated fire risk to comply with the Wildfire Regulation: http://www.bclaws.ca/EPLibraries/bclaws_new/document/ID/freeside/11_38_2005
- When conducting an industrial operation, sufficient *firefighting hand tools* must be available on site whenever the area is snow free and there is a risk of a fire starting or spreading.
- Hand tools must be a combination and type to properly equip each person who works at the site
 with a minimum of one firefighting hand tool per person. Tools may include shovels, mattocks,
 pulaskis, fire extinguishers and hand tank pumps. The BCTS general rule for assessing the
 adequacy of firefighting hand tools is:

of workers assigned to the site during normal work hours = # of hand tools on site

☑ For High Risk Industrial Activities

- Determine if your operations are High Risk as defined in Part 1 of the Wildfire Regulation.
- Determine the danger class, follow danger class restrictions and durations, keep sufficient *firefighting hand tools* <u>plus</u> an adequate *fire suppression system* at the activity site, and maintain fire watcher and communication requirements.
- A fire suppression system means a system for suppressing fire by delivering water, a suppressant, a surfactant, or any combination of these substances.
- **☑** Determine Restrictions on High Risk Industrial Activities

1



For BCTS Client Use

Acquire local weather data to comply with the Wildfire Regulation. Weather station information is available from the BCWS website at <a href="https://www2.gov.bc.ca/gov/content/safety/wildfire-status/wildfi

 Danger class ratings for your site may be higher than those calculated by the BCWS. Consider local conditions when determining applicable weather station and when to restrict activities.

Note: Refer to the BCWS "Interpretative Bulletin on the Application of the Wildfire Regulation for the Forest Industry" for further guidance to the above, including a defined wildfire prevention and response system (Appendix A) at http://www.bcwildfire.ca/Industry Stakeholders/Industry/

Fire Roles and Responsibilities continued

- ☑ Provide 24hr Contact information
 - Timber Sale License holders must provide an official with a 24 hour a day contact telephone number if the person proposes to carry out an industrial activity on or after March 1 and before November 1 of that year.
- ☑ Provide copies of your training records as required.
- ☑ Ensure employees are trained and aware of <u>all</u> fire emergency responsibilities.
- Complete environmental Emergency Response Plan (eERP) with worksite details and company contact information.
- ☑ <u>List the minimum fire equipment that will be maintained on site</u> for "Industrial" and "High Risk Industrial" activities during Danger Classes III, IV, and V (i.e., water tank(s), pump(s) hoses, accessories etc.):

During Operations

- ☑ Ensure employees are aware of all fire preparedness responsibilities and trained as to their fire duties in accordance with WorkSafeBC requirements.
- ☑ Conduct test(s) and periodic drill(s) of fire preparedness and response. Tests are to be documented on the BCTS Environmental Emergency Response Test/Drill Report Form CHK-010, records maintained on site and copies of results forwarded to a BCTS representative. Results of drills may be documented on the CHK-010 and maintained on site.

Regularly monitor the appropriate fire weather index information using your representative weather station and determine the appropriate Fire Danger Class for the area. For Danger Class Reports go to https://www2.gov.bc.ca/gov/content/safety/wildfire-status/wildfire-situation/fire-danger

- Restrict activities during Fire Danger Class III, IV, or V situations. Implement fire watch, patrol, early shift, and cease activity, as required (see Schedule 3 of the Wildfire Regulation). Monitor activities and changing site/weather conditions. Do not operate solely by the Schedule 3 of the Wildfire Regulation.
- ☑ Ensure a copy of the environmental Emergency Response Plan (eERP) is onsite.
- Conduct regular fire suppression equipment inspections and maintenance.
- ☑ Take action on a forest fire that is within 1 km of the site of the industrial activity.
- Complete Hazard Assessments and Abatement at prescribed intervals in accordance with the Wildfire Regulation;
 - Keep all debris piles clean, obtain a Burn Registration Number (BRN) by calling 1-888-797-1717, complete hazard abatement and follow requirements including monitoring of burning activities

3



For BCTS Client Use

- For smoke management / venting indices call the Provincial Venting Index Hotline 1-888-281-2992 or visit the BC Environment Venting Index website; http://www.env.gov.bc.ca/epd/epdpa/venting/venting.html
- Extinguish and inspect debris piles by the date specified according to the BRN. Apply to extend the BRN if additional time is required to extinguish burned debris piles.

Part D Core Information

SPILL PREPAREDNESS AND RESPONSE

Initial Spill Response Activity

1. Discovery and Assessment

- ☑ Follow safety procedures and put on appropriate personal protective equipment prior to initiating response plan.
- ☑ If Safe, **STOP THE PRODUCT FLOW!** Halt activities that are causing the spill (e.g. Close valves; elevate leaking hoses, shut off pumps, etc.). **Minimize Impact of Spill.**
- Prior to taking action complete an incident assessment (spill identification /volume, assess potential safety, and environmental issues).
- If you feel that the spill is beyond your level of training and experience to handle, seek assistance from a spill response specialist.

2. Notification and Documentation

☑ Report spills in accordance with spill reporting criteria listed in Table 1 below.

3. Containment and Recovery.

- ☑ Take action within your ability using resources (hand tools, heavy equipment and spill response equipment) at hand to minimize the spread and impact of the spill until additional resources and expertise arrive.
- ☑ Due to the hazardous nature of gasoline, volatile gases should be allowed to dissipate before attempts are made to contain or mop up a gasoline spill.

Spills to Land

- ☑ Determine extent of spill. Contain or redirect spills away from watercourses.
- ☑ Mark the perimeter of the spill, dig recovery ditches around the perimeter and recovery pits (sumps) within the spill area.
- ☑ Monitor ditches and recovery pits to ensure the collection system is effective.
- ☑ Recover the product from the containment area, treat or dispose of appropriately.

Spill to Water

- ☑ In a ditch or stream, contain the spill using whatever surface water containment system possible.
- Divert and corral the spilled product to a spill containment system using absorbent booms or other methods.

For Spills less than 25 litres

- ☑ Soak up all free products with absorbent pads, booms, and other materials.
- ☑ Place used absorbent materials in a suitable container (i.e. heavy-duty plastic bag) for disposal or recycling. Mix stained soil with loose absorbents or commercial bioremediation agents.

4. Follow-up, Disposal and Site Restoration

- $\ oxdot$ Ensure spills have been documented and reported to agencies and BCTS as required.
- Complete clean-up and required mitigation actions. If required, contact a spill response specialist for assistance.
- ☑ Complete an Incident Report Form (CHK-009 or equivalent) and submit to BCTS.

.

July 1, 2018

For BCTS Client Use

Spill Roles and Responsibilities

- Assess risk for potential spills identify additional preventative and control measures
- Ensure all workers understand the environmental emergency response plan and it is available on site at all times.
- Ensure all workers are familiar with potential spill sites, spill kit locations and spill kit requirements.
- ☑ Ensure workers are trained/aware in WHMIS, TDG and Spill response
- ☑ Have available on site appropriate MSDS.
- ☑ Conduct test(s) and periodic drill(s) of spill preparedness and response. Tests are to be documented on the BCTS Environmental Emergency Response Test/Drill Report Form CHK-010, records maintained on site and copies of results forwarded to a BCTS representative. Results of drills may be documented on the CHK-010 and maintained on site.
- ☑ Complete spill kits inspections and maintain spill kits as necessary
 - For Equipment spill kit content requirements see Fuel Handling Environmental Field Procedure EFP-06.
- ☑ Respond to all spills in accordance with the emergency response plan.
 - If you are responsible for a spill of hazardous material, you are then responsible to take appropriate actions to minimize environmental impact.
- ☑ Report all reportable spills to the appropriate agencies and to BCTS.

Spill Reporting Criteria (If in Doubt Report the Spill)

- ☑ All spills that are equal to or greater than the EMBC reportable level must be reported to EMBC as soon as possible and within 24hrs.
- ☑ Any spills of deleterious substance to a watercourse must be reported to EMBC as soon as possible and within 24hrs.
- All spills that are equal to or greater than the BCTS reportable level must be reported to BCTS contact as soon as possible and within 24 hrs.

Table 1: Reportable Levels of Hazardous Materials Spills

Hazardous Material	EMBC Reportable Level (1)	BCTS Reportable Level (2)
Antifreeze	25 litres	25 litres
Diesel fuel	100 litres	25 litres
Gasoline (auto & saw)	100 litres	25 litres
Greases	100 litres	25 litres
Hydraulic Oil	100 litres	25 litres
Lubricating Oils	100 litres	25 litres
Methyl Hydrate	5 litres	5 litres
Paints & Paint Thinners	100 litres	25 litres
Solvents	100 litres	25 litres
Pesticides	1 kilogram or 1 litre	1 kilogram or 1 litre
Explosives	Any	Any

⁽¹⁾ as required by the BC Spill Reporting Regulation

⁽²⁾ or a spill of ANY quantity that enters a surface water body (e.g.: running ditch, stream, lake)



For BCTS Client Use

Part E Core Information

LANDSLIDE & EROSION EVENT RESPONSE

Initial Response Activity

- Evaluate. Follow applicable safety procedures and notify supervisor and other workers. If safe to
 do so, assess situation to determine if activities must be shutdown.
- 2. Immediate Remedial Action. Take steps to control further environmental impacts.
- 3. Notification. Report the erosion event to the BCTS contact within 24 hours or as soon as practical. (Refer to Reporting Criteria). It is also the LPC's responsibility to notify applicable regulatory agencies of an erosion event that may impact resource values such as fish sensitive areas, domestic watersheds, private property etc. (e.g. DFO, EMBC). Notify WorkSafeBC if the slide event relates to a safety incident.
- 4. Before Leaving the Site. Supervisors must account for all workers before leaving the site. If a shutdown is required, park all equipment in an environmentally safe location (i.e. avoid riparian management areas, steep side slopes, steep road sections, areas with excessive soil moisture, areas within reach of standing timber, etc.).
- **5. If Environmental Damage Has Occurred**. The BCTS contact must review the situation with the appropriate personnel.
- 6. Complete an Incident Report Form (CHK-009 or equivalent) and submit to BCTS.

Landslide & Erosion Roles and Responsibilities

- Verify that operations are conducted in a manner that minimizes the risk of a landslide and major erosion event occurring.
- ☑ **Ensure all workers understand and are trained** in response procedures and the environmental emergency response plan is available on site at all times.
- ☑ Supervisor to ensure all employees are familiar with risk areas.
- ☑ Conduct test(s) and periodic drill(s) of Landslide/Erosion Emergency Response. Tests are to be documented on the BCTS Environmental Emergency Response Test/Drill Report Form CHK-010, records maintained on site and copies of results forwarded to a BCTS representative. Results of drills may be documented on the CHK-010 and maintained on site.
- ☑ **Assess** landslides and erosion events, determine reporting requirements, and report to BCTS contact immediately where applicable.
- ☑ **Respond to erosion events** in accordance with this emergency response plan.

Landslide/ Erosion Event Reporting Criteria

Landslides and major erosion events must be reported to BCTS in ANY of the following circumstances:

- Loss or imminent loss of life or property,
- Significant environmental damage,
- Situations which potentially create loss of provincial revenue or funds.
- · Abnormal movement has occurred or is actively occurring at a site,
- Abnormal sedimentation,
- A volume of greater than 250 m³ has moved or is imminent danger of movement,
- A land area greater than 0.25 hectares is disturbed,
- A road or structure is damage and requires structural repairs.

6



Kootenay Business Area WATER DISRUPTION EMERGENCY RESPONSE PLAN FOR

Community and Domestic Consumptive Use Watersheds *for BCTS Client Use*

Scope and Purpose

This ERP applies to BCTS clients (Licensees, Permitees and Contractors) and their workers involved in forest practices within Kootenay BA community and domestic consumptive watersheds. The purpose of this ERP is to prevent and respond to water disruption (from sedimentation, spills, or interrupted flows) resulting from BCTS-authorized activities.

Preparedness Roles and Responsibilities

- ☑ Know the names of and contact information for water users within the area of active operations. Ensure this information is on site and available to workers (refer to attached contact list).
- ☑ Know the field location of applicable points of diversion (PODs) and associated infrastructure as identified on project maps, site plans, and assessments.
- ☑ Be familiar with applicable prescriptions (for example: site plans, road designs, drainage plans, riparian management prescriptions, terrain stability and soil erosion assessments, harvest plans) when working in and around drainage areas connected to PODs including protocols for changing site conditions. Review during office and field pre-work discussions. Minimize soil disturbance.
- Ensure adequate sediment control tool kit (e.g. filter fabric, hay bales, rock for armoring etc.) is available on site and workers are aware of their roles and responsibilities for sediment abatement.
- Conduct periodic emergency response drill(s) and or test(s) related to disruption of water, based on employee knowledge and experience and seasonal and site conditions.
- Monitor activities, site and weather conditions, and water turbidity for possible impacts occurring to water quality and stream conditions associated with PODs.
- ☑ Ensure potentially-affected water users and BCTS are advised of planned water interruptions or potential sediment increases as a result of activities.
- ☑ Report to BCTS <u>any</u> amount of unexpected soil movement or <u>any</u> quantity of material spill or equipment fluid leaks within the watershed area.

Initial Response (Water Disruption Events)

- 1. Evaluate: Assess worker safety, hazards, & determine cause of disruption.
- 2. Take Control: If the disruption is a result of a forest practice, **STOP WORK.**
- 3. <u>Take Action:</u> Consider removal of POD intake and/or bypassing POD. Implement sediment abatement measures (sediment control kit).
- Notification: Contact affected water user(s) and BCTS representatives as soon as possible.
- Document details of the incident and response measures on CHK-009 Incident Report Form and submit to BCTS.
- Work Co-operatively with BCTS, other agencies, and water users to investigate incidents and to implement measures to restore disrupted water supply quickly, thereby minimizing impacts on water users.

April 15, 2010



Kootenay Business Area WATER DISRUPTION EMERGENCY RESPONSE PLAN FOR

Community and Domestic Consumptive Use Watersheds

for BCTS Client Use

Scope and Purpose

This ERP applies to BCTS clients (Licensees, Permitees and Contractors) and their workers involved in forest practices within Kootenay BA community and domestic consumptive watersheds. The purpose of this ERP is to prevent and respond to water disruption (from sedimentation, spills, or interrupted flows) resulting from BCTS-authorized activities.

Preparedness Roles and Responsibilities

- ☑ Know the names of and contact information for water users within the area of active operations. Ensure this information is on site and available to workers (refer to attached contact list).
- ☑ Know the field location of applicable points of diversion (PODs) and associated infrastructure as identified on project maps, site plans, and assessments.
- ☑ Be familiar with applicable prescriptions (for example: site plans, road designs, drainage plans, riparian management prescriptions, terrain stability and soil erosion assessments, harvest plans) when working in and around drainage areas connected to PODs including protocols for changing site conditions. Review during office and field pre-work discussions. Minimize soil disturbance.
- Ensure adequate sediment control tool kit (e.g. filter fabric, hay bales, rock for armoring etc.) is available on site and workers are aware of their roles and responsibilities for sediment abatement.
- Conduct periodic emergency response drill(s) and or test(s) related to disruption of water, based on employee knowledge and experience and seasonal and site conditions.
- Monitor activities, site and weather conditions, and water turbidity for possible impacts occurring to water quality and stream conditions associated with PODs.
- ☑ Ensure potentially-affected water users and BCTS are advised of planned water interruptions or potential sediment increases as a result of activities.
- ☑ Report to BCTS <u>any</u> amount of unexpected soil movement or <u>any</u> quantity of material spill or equipment fluid leaks within the watershed area.

Initial Response (Water Disruption Events)

- 1. Evaluate: Assess worker safety, hazards, & determine cause of disruption.
- 2. Take Control: If the disruption is a result of a forest practice, **STOP WORK.**
- 3. <u>Take Action:</u> Consider removal of POD intake and/or bypassing POD. Implement sediment abatement measures (sediment control kit).
- Notification: Contact affected water user(s) and BCTS representatives as soon as possible.
- Document details of the incident and response measures on CHK-009 Incident Report Form and submit to BCTS.
- Work Co-operatively with BCTS, other agencies, and water users to investigate incidents and to implement measures to restore disrupted water supply quickly, thereby minimizing impacts on water users.

April 15, 2010



ENVIRONMENTAL FIELD PROCEDURE - 01

GENERAL

Purpose and Scope

This Environmental Field Procedure (EFP) applies to all BC Timber Sales (BCTS) licensees, permittees, and contractors (LPC), including their employees, agents and subcontractors involved in field activities within the scope of the BCTS Environmental Management System (EMS). It describes procedures to reduce the risk of negative impacts on the environment. This EFP does not replace the requirements of legislation, licences, permits, and contracts.

General Procedures

- 1. Complete a pre-work with your supervisor and/or the BCTS representative.
 - Obtain and review all project plan documents (e.g., harvest plan, harvest plan map, site plan supporting information, road layout and design and silvicultural treatment plans). Have them readily available during field activities.
 - b. Ensure you understand your role in the project plan prior to commencing work.
 - c. Know the flagging or field marking standards.
- 2. Look ahead and make sure that the Project Plan is workable.
 - a. View the area to familiarize yourself with the project plan, map contents, and site conditions.
 - b. Ensure all resource features, resource values or sensitive areas identified on the project plan documents can be located by you on the ground. Know the associated management strategies.
- 3. Monitor and inspect your work to ensure the work conforms to the project requirements.
 - Conduct operations to minimize potential impacts to hazardous or sensitive areas, resource features, resource values, water quality and site productivity.
 - b. Operate during favourable weather and site conditions. Know the project shutdown criteria.
 - c. Report to the project supervisor any conditions which may adversely affect the environment (e.g., siltation of streams, lakes or other water bodies or deterioration of the road).
- Know the activity shutdown criteria (e.g., rainfall shutdown, fire hazard) including operational site conditions
 and timing windows (fisheries windows, community watersheds, migratory birds, wildlife, blasting,
 stakeholders).
- 5. Have the project plan map available and know your location at all times.
- 6. Keep the site clean and be prepared for emergencies, not limited to the following:
 - a. Inspect equipment regularly. Repair or maintain equipment as required.
 - b. Maintain fire suppression equipment and spill kits. Replace used supplies promptly.
 - c. Safely transport, store, and handle industrial waste (e.g., petroleum and chemical products, grease tubes, filters, batteries, coolant, wire rope, used spill pads).
 - d. Remove industrial waste regularly and dispose only at appropriate disposal facilities.
 - e. Understand the environmental Emergency Response Plan (eERP) and your responsibilities in it.

Incident Reporting

- 1. Document on CHK-009 and report to site supervisor and BCTS in the event of:
 - a. Hazardous material spill, uncontrolled fire or erosion/landslide
 - b. Potential non-compliance and significant non-conformance
 - c. Safety incidents, accidents, close call or previously unidentified safety hazards



Stop Work – Contact Project Supervisor and BCTS Representative if:

- There is a hazardous material spill, uncontrolled fire or erosion/landslide event
- There is uncertainty about the project plan, the responsibilities or the location of hazardous or sensitive areas.
- A previously unidentified resource feature, resource value or sensitive area is found (e.g., species of management concern, bear den, wildlife habitat feature, culturally modified tree).
- Unfavourable weather or site conditions could cause environmental damage.
- Conditions have the potential for immediate environmental damage.
- There is reason to believe the project plan will not work.

June 1, 2022

BC Timber Sales - EFP-01 General

Page 2 of 2



ENVIRONMENTAL FIELD PROCEDURE - 02

PROJECT SUPERVISION

Purpose and Scope

This Environmental Field Procedure (EFP) applies to all BC Timber Sales (BCTS) licensees, permittees and contractors (LPC), including their employees, agents and subcontractors, responsible for supervising field activities within the scope of the BCTS Environmental Management System (EMS). It describes the supervisors' responsibilities to prepare and supervise workers in such a manner as to reduce the risk of negative environmental impacts. This EFP does not replace the requirements of legislation, licences, permits and contracts.

Pre-work

- Complete a pre-work meeting with your supervisor and/or the BCTS representative. Understand the information on the pre-work checklist. Ensure you obtain all relevant project information.
- Prepare, complete and document a pre-work meeting with all workers involved in the project before the work commences:
 - a. Review relevant project information including contract, licence, permit, map, project plan, field marking standards, prescriptions, special conditions, requirements and specifications. Review environmental field procedures, environmental emergency response plans and any resource features, resource values, sensitive areas and stop-work conditions.
 - b. Provide copies of project plans and maps to workers.
 - Emphasize to workers that they must speak with the supervisor before any changes are made to the project plans.
 - d. View the site with workers to familiarize them with resource features, resource values, resource objectives, sensitive areas and special conditions, as relevant to their function and activities.
 - e. Document pre-work meeting with workers and record the names of attendees. A copy of the completed BCTS Prework Report can be used for this purpose.
 - f. Ensure all stakeholders are notified as required (e.g., DFO, affected water licensees or purveyors, trappers, guides, lodges, residents).
 - g. Additional pre-works with workers may be required if high risk sites have been identified, a project plan has changed or following a temporary operational shut down.
- 3. Additional pre-work with a BCTS representative is required after temporary operational shut down (inactive for 90 calendar days or more due to season, fire, operational restrictions, economics, etc.) or as requested.

Supervising and Monitoring Project Plans

- 1. Have a project plan prepared by a qualified professional as appropriate.
- 2. Look ahead to make sure that the Project Plan is workable.
 - a. Ensure resource features, resource values or sensitive areas are identified on the project plan map can be located on the ground. Communicate the associated management strategies to workers.
 - b. Stop work upon discovery of a previously unidentified resource feature, resource value or sensitive area; document and identify the previously unidentified resource feature on the project plan map. Report the discovery to the BCTS representative.
- Assess the need for changes to the project plan. Licensees and permittees must amend the project plan with a qualified professional before conducting primary forest activities in a way that is different from what is described in the plan; report to the BCTS representative.
- 4. Know and monitor adherence to all EFP requirements.

Supervisors Must Ensure All Workers:

- 1. Receive adequate training, orientation, information and instructions;
- 2. Have relevant EFPs available, and follow the requirements of the EFPs;

June 1, 2022 BC Timber Sales - EFP-02 Project Supervision

Page 1of3

- 3. Have relevant project plans available, and understand their associated requirements.
- 4. Understand EFP stop-work procedures and incident reporting requirements (EFP-01, CHK-009).

Monitor and Inspect Work:

- 1. Monitor and inspect current and completed works.
 - a. Review relevant items including:
 - Conformance to the project plan, especially areas with complexity or higher risk e.g., riparian areas or special sites;
 - Conformance to EMS and Sustainable Forest Management requirements (e.g., EMS training completed and documented, pre-work(s) completed and documented, eERP completed, implemented and on-site, EFPs followed and onsite, etc.) and the BCTS Sustainable Forest Management Plan;
 - iii. Licence, permit and/or contract conditions;
 - iv. Compliance with all relevant legislation (e.g., Forest and Range Practices Act, Wildfire Act, Forest Act, Transportation of Dangerous Goods Act, Fisheries Act); and
 - v. Safety requirements.
 - b. Report any potential non-compliances to the appropriate agency and BCTS.
 - Assign corrective and preventative actions to identified non-conformances and potential noncompliances.
 - d. Follow-up on any actions identified by BCTS or the LPC inspections. Supervisor to ensure they have been carried out within the noted timelines.
- Conduct self-inspections of the work at the frequency prescribed by BCTS pre-work or more frequently, if desired. The BCTS Client Self-Inspection Report can be used for this purpose.
- 3. Complete an inspection and notify BCTS prior to demobilization or temporary shutdown (inactive 90 calendar days or more due to seasonal, fire, operational restrictions, economics, etc). Ensure steps have been taken to protect resource features and prevent damage to the environment (e.g., ditches cleaned, culverts installed) prior to the shutdown of operations.

Manage Documentation:

- 1. Keep required documentation onsite:
 - a. BCTS pre-work report, and records of your pre-works with workers,
 - b. Project Plans and other materials provided at the pre-work,
 - c. Environmental Emergency Response Plan (eERP) available to all workers,
 - d. EFPs available to workers as relevant to their activities.
 - e. BCTS inspection reports and LPC self-inspection reports,
 - f. Completed Incident Report forms for any incidents that have occurred during the work,
 - g. Training records
 - h. Completed emergency response test reports.
- 2. Provide records for review upon request by BCTS.

In the Case of an Emergency or Environmental Damage:

- 1. Follow the eERP, including reporting to BCTS and external agencies.
- 2. Complete an Incident Report Form (CHK-009 or equivalent) and submit it to BCTS. Ensure corrective and preventative actions taken to address the incident are documented and completed.



Stop Work – Contact Project Supervisor and BCTS Representative if:

- There is a hazardous material spill, uncontrolled fire or erosion/landslide event.
- There is uncertainty about the project lan, the responsibilities or the location of hazardous or sensitive areas.
- Previously unidentified resource feature, resource value or sensitive area is found (e.g., species of management concern, bear den, wildlife habitat feature, culturally modified tree)
- Unfavourable weather or site conditions could cause environmental damage.
- Conditions have the potential for immediate environmental damage.
- There is reason to believe the project plan will not work.



ENVIRONMENTAL FIELD PROCEDURE - 03

DEVELOPMENT & PLANNING

Purpose and Scope

This Environmental Field Procedure (EFP) applies to all BC Timber Sales (BCTS) contractors including their employees, agents, and subcontractors involved in development and planning activities within the scope of the BCTS Environmental Management System (EMS). It also applies to BCTS licensees and permittees making changes to a project plan. This EFP describes procedures to reduce the risk of negative impacts of these activities on the environment. This EFP does not replace the requirements of legislation, licences, permits, and contracts.

Preparation

- 1. Ensure development and planning activities are carried out by an appropriate qualified professional
- 2. Ensure you have copies of and are familiar with all standards, guidebooks, plans and other information relevant to the scope of work.
- 3. Ensure all required assessments have been identified.
- 4. At the pre-work meeting, discuss details of project approach, designs, layouts, or other project plan requirements including professional qualifications to develop a plan or make changes.

Field Work

- 1. When conducting field work, ensure you:
 - a. Are familiar with relevant constraints and plans; understand how resource objectives relate to the project area;
 - b. Follow field marking standards; and
 - c. Note any discrepancies between the plans or objectives and the conditions in the field; notify the BCTS representative of any discrepancies.
- Consider potential longer-term implications of the planned work such as providing future access. If you are not sure about possible longer-term requirements, ask the BCTS representative for direction.
- Look at all options for timber development including roads, bridges, and culverts to ensure they are placed in the best location. Know when you can vary from specifications provided by BCTS, and when you must request approvals.

Plan Completion

- Ensure the following information and requirements, as applicable, are correctly identified and incorporated into all layout and design work:
 - a. Forest Stewardship Plan information, site plan content and any amendments.
 - b. Applicable engineering, mapping, boundary, and field marking requirements.
 - c. Any key points noted during reconnaissance.
 - d. First Nations, stakeholders and other agencies commitments as communicated via BCTS.
 - e. Location of streams, terrain and other important features including wildlife tree retention areas and reserves and the related retention or buffer requirements.
 - f. Location of adjacent resource values.
 - g. Recommendations from professional assessments (e.g., terrain stability, windthrow, soil, watershed, stream).
 - h. Any measures to ensure stability of the area during extreme weather events; roads or cutblock boundary(s).

June 1, 2022

BC Timber Sales - EFP-03 Development and Planning

Page 1 of 2

- i. Location of end-haul sections, spoil sites and quarry/pits; properly classified soils/rock.
- j. Right-of-way design and markings including landing size and location.
- k. Any necessary trails.
- I. All shut down requirements and timing restrictions.
- m. The harvesting system planned to be used and the retention levels for partial cut harvest prescriptions are identified in the harvest plan.
- n. Appropriate referencing (photo ties, reference points).
- 2. Ensure major crossing site plans are identified for, or completed by, a qualified professional.
- 3. Ensure water and sediment control measures are incorporated into the plan.
- 4. Ensure all work is in conformance with applicable requirements and standards applicable to the BCTS business area.
- 5. If you have any concerns about potential environmental impacts relating to this information and the associated prescriptions, contact your supervisor and the BCTS representative.



Stop Work - Contact Project Supervisor and BCTS Representative if:

- There is a hazardous material spill, uncontrolled fire, or erosion/landslide event.
- There is uncertainty about the project plan, the responsibilities, or the location of hazardous or sensitive areas.
- A previously unidentified resource feature, resource value or sensitive area is found (e.g., species of management concern, bear den, wildlife habitat feature, culturally modified tree).
- Unfavourable weather or site conditions could cause environmental damage.
- Conditions have the potential for immediate environmental damage.
- There is reason to believe the project plan will not work.



ENVIRONMENTAL FIELD PROCEDURE - 04

ROADS, BRIDGES AND CULVERTS

Purpose and Scope

This Environmental Field Procedure (EFP) applies to all BC Timber Sales (BCTS) licensees, permittees, and contractors (LPC), including their employees, agents, and subcontractors, involved in permanent and temporary road, bridge and culvert construction, maintenance, inspection, and deactivation within the scope of the BCTS Environmental Management System (EMS). It describes procedures to reduce the risk of negative impacts of these field activities on the environment. This EFP does not replace the requirements of legislation, licences, permits, and contracts.

Road, Bridge and Major Culvert Inspections

- Understand all applicable inspection and engineering requirements. Know which sites and structures require
 assessments. Assessments must be done by those trained and professionally competent.
- 2. Review all relevant assessments prior to inspection. Understand their management implications.
- Review or walk the project area, as well as the surrounding area of influence, to ensure all relevant field information is collected, complete, reported and mapped.
- 4. Understand and use the appropriate inspection form. Record all inspection results, identifying any deficiencies or additional inspection requirements and submit to the project supervisor.

Road Construction, Maintenance and Deactivation

- 1. Have a project plan (e.g., road layout and design, plans and profiles, deactivation, maintenance).
- Ensure compliance with applicable timing windows and other specifications (e.g., fisheries windows, community watersheds, migratory birds, wildlife, recreation).
- 3. Ensure safety signage is posted on sites as required.
- 4. Construct and maintain the road to ensure the structural integrity of the road prism and clearing width are protected, the drainage systems are functional, and the road is safe for industrial use.
- Report to the project supervisor any road conditions which may adversely affect the environment (e.g., siltation of streams, lakes or other water bodies, or deterioration of the road).
- Incorporate considerations for extreme weather events and climate change to ensure functionality of roads and protection of the environment.
- 7. Have appropriate water control measures on roads at locations where there is a risk of erosion, impacts to water quality, classified stream or fish habitat.
- 8. Before equipment demobilization or prior to temporary or seasonal shutdown, and/or when precipitation is occurring in an amount causing erosion of surface material:
 - a. Install back-up cross ditches at culvert locations.
 - b. Establish water-bars and breach grader berms to disperse runoff.
 - Perform site clean-up to ensure water management features (culverts, ditches) are clean of introduced logging debris and functional.
- Maintain natural surface drainage patterns. Avoid directing water onto unstable slopes or erodible soils; direct water to stable slopes and/or armour outfalls with rock.
- 10. Minimize the impact on water quality and site productivity:
 - a. Operate during favourable weather and site conditions. Know the project shutdown criteria.
 - b. Install culverts and other drainage structures concurrently with subgrade construction.
 - c. Utilize sediment control measures as required (e.g., silt fences, hay bales, rock armouring, swales, water bars or sediment ponds).
 - d. Clean introduced debris from ditches, streams and culverts on an on-going basis before any impact can occur.

June 1, 2022

EFP-04 Roads, Bridges and Major Culverts

Page 1 of 3

- e. Ensure road surface drainage is directed to drainage structures and is not impeded.
- f. Minimize erosion potential of exposed soil surfaces by seeding of disturbed areas.
- g. Seeding must be at appropriate times and with an appropriate mix of seed to ensure effectiveness and avoid the spread of invasive species.
- 11. Control blasting to minimize fly-rock damage and slope instability. Adhere to blasting timing windows.
- 12. Know the locations of end-haul and spoil sites.
- 13. Do not remove gravel or other fill from Riparian Management Areas. Avoid constructing pullouts in Riparian Management Areas.
- 14. When re-establishing natural drainage patterns during road deactivation, the road fill should be removed down to the natural ground level. Cut and fill slopes must be left in a stable condition.
- Prepare professional conformance and assurance statements if required for road design, construction, maintenance and deactivation.

Bridge or Culvert Installation, Maintenance and Removal

- Have a project plan deemed appropriate by a qualified professional (e.g., installation, deactivation, maintenance).
- 2. Bridges and major culverts (greater than or equal to 2000mm) require a coordinating registered professional and professional of record to oversee, design, inspect and sign-off the project.
- Comply with timing windows, legislation and other specifications (e.g., DFO Fisheries Act "projects near water" requirements and guidance, fisheries windows, community watersheds, migratory birds, wildlife, blasting, stakeholders).
- 4. Construct and maintain bridges and culverts in accordance with the project plan. Ensure bridges and culverts are structurally sound, appropriate and safe for industrial use.
- When working on crossings, know the stream classification, management zone and associated prescription. During construction of temporary access trails, minimize the impact to water features.
- 6. Minimize the impact on water quality and site productivity:
 - a. Install culverts and other drainage structures concurrently with subgrade construction.
 - Utilize sediment control measures as required (e.g., silt fences, hay bales, rock armouring, swales, water bars, or sediment ponds).
 - Clean introduced debris from ditches, streams and culverts on an on-going basis, and before any blockages can occur.
 - d. Incorporate considerations for extreme weather events and climate change to ensure functionality of roads and protection of the environment.
 - e. Minimize erosion potential of exposed soil surfaces by seeding of disturbed areas.
 - f. Seeding must be at appropriate times and with an appropriate mix of seed to ensure effectiveness and avoid the spread of invasive species.
- 7. Operate during favourable weather and site conditions. Know the project shutdown criteria.
- 8. Temporary structures such as log bundles must be removed prior to unfavourable conditions.
- Avoid placing erodible materials on bridge decks, in stream channels or on flood plains. Clean bridge decks and remove erodible materials.
- 10. Maintain natural surface drainage patterns. Avoid directing water onto unstable slopes or erodible soils; direct water onto stable slopes and/or armour outfalls with rock.
- 11. Armour culvert inflows, outflows and fill slopes to minimize erosion as required. It is a good practice to premark inlet and outlet culvert locations to ensure appropriate road prism fit. Culvert installation should consider skew, slope and percent of embedment as designed.
- 12. Dispose of wood culvert/bridge debris in designated sites outside riparian management areas.
- 13. Ensure professional conformance and assurance statements are prepared for bridges and major culverts by the professional of record (POR).

June 1, 2022

Fire Hazard Assessment and Abatement

- Complete hazard assessments at prescribed intervals and complete abatement in accordance with the Wildfire
 Act and Regulation. Submit assessment to BCTS upon request.
- If burning is part of the plan for abatement, ensure required notification is made, approvals received and conditions followed. Ensure burn area is safe from escape and clear of hazardous or sensitive areas. Monitor burned sites for extinguishment.



Stop Work - Contact Your Project Supervisor and BCTS Representative if:

- There is a hazardous material spill, uncontrolled fire or erosion/landslide event.
- There is uncertainty about the project plan, the responsibilities or the location of hazardous or sensitive areas.
- A previously unidentified resource feature, resource value or sensitive area is found (e.g., species of management concern, bear den, wildlife habitat feature, culturally modified trees).
- Unfavourable weather or site conditions could cause environmental damage.
- Conditions have the potential for immediate environmental damage.
- There is reason to believe the project plan will not work.



ENVIRONMENTAL FIELD PROCEDURE - 05

HARVESTING

Purpose and Scope

This Environmental Field Procedure (EFP) applies to all BC Timber Sales (BCTS) licensees, permittees, and contractors (LPC), including their employees, agents, and subcontractors, involved in all phases of harvesting within the scope of the BCTS Environmental Management System (EMS). It describes procedures to reduce the risk of negative impacts of these field activities on the environment. This EFP does not replace the requirements of legislation, licences, permits, and contracts.

Project Plans

- 1. Have a project plan prepared by a qualified professional as appropriate. Ensure the project plan is applicable to the phase of operation.
 - a. Choose suitable landing and yarder setting locations that are stable and away from water courses.
 - Pre-mark or at least know existing culvert locations and classified stream locations; ensure they are functional at all times until these structures are removed.
 - c. If a change of plan is needed, stop work, then notify project supervisor. Changes to a project plan must be documented, made by a qualified professional, and meet the intended results and strategies for the project area and protect environmental values.

Falling

- 1. Fall next to boundaries only when boundaries are clearly visible (know where they are).
- Use extra caution when falling adjacent to boundaries and reserves in order to minimize damage to standing trees and protect resource features, resource values (e.g., cultural) and sensitive areas.
- 3. Follow stream prescriptions when falling, limbing and bucking adjacent to watercourses.
- 4. Know which streams and gullies require cleaning of introduced debris.
- 5. Know leave-tree, stubbing and retention requirements, and monitor your progress to ensure the requirements are met.

Yarding, Skidding, Forwarding, Loading, Processing and Hauling

- 1. If yarding or skidding in steep or gullied terrain, ensure you implement yarding/skidding strategies to minimize impacts to soil productivity and water quality.
- Use appropriate methods to minimize damage to reserve trees (e.g., dispersed retention trees, retention tree patches, etc.).
- Know the applicable soil disturbance limits and use appropriate methods to avoid excessive soil disturbance (e.g., temporary access structures, gouges, ruts, scalps and compacted areas).
- 4. Minimize the impact on water quality and site productivity:
 - a. Take actions to mitigate potential erosion and/or sedimentation from temporary access trails.
 - b. Utilize sediment control measures as required (e.g., silt fences, hay bales or sediments ponds).
 - Clean introduced debris from ditches, streams, and culverts on an on-going basis, and before any blockages can occur.
- 5. Operate during favourable weather and site conditions. Know the project shutdown criteria.
- 6. Know the project shutdown criteria including operational site conditions and timing windows (e.g., fisheries windows, community watersheds, migratory birds, wildlife, blasting, recreation).
- Know the stream classifications and implement riparian management area requirements (e.g., machine free zones, riparian reserve zones, stream cleaning, etc.) for the watercourses identified in the project plan.
- 8. Rehabilitate excavated and bladed temporary access trails, temporary roads, landings, etc., as required. Ensure rehabilitation activities maintain natural drainage patterns.
- 9. Temporary structures such as log bundles must be removed prior to unfavourable conditions.

June 1, 2022 BC Timber Sales - EFP-05 Harvesting

- 10. Avoid decking wood, processing wood, and piling wood debris in riparian management areas.
- 11. Minimize decked wood and debris pile impacts to standing timber and reforested areas.
- 12. Report to the project supervisor any road conditions which may adversely affect the environment (e.g., siltation of streams, lakes or other water bodies or deterioration of the road).
- 13. Before equipment demobilization or prior to temporary or seasonal shutdown, perform site clean-up to ensure water management features (culverts, ditches) are clean of introduced logging debris and functional.

Fire Hazard Assessment and Abatement

- Complete hazard assessments at prescribed intervals and complete abatement in accordance with the Wildfire Act and Regulation. Submit assessment to BCTS upon request.
- If burning is part of the plan for abatement, ensure required notification is made, approvals are received, and conditions are followed. Ensure burn area is safe from escape and clear of hazardous or sensitive areas. Monitor burned sites for extinguishment.



Stop Work – Contact Project Supervisor and BCTS Representative if:

- There is a hazardous material spill, uncontrolled fire or erosion/landslide event.
- There is uncertainty about the project plan, the responsibilities, or the location of hazardous or sensitive areas.
- Previously unidentified resource feature, resource value or sensitive area is found (e.g., species of management concern, bear den, wildlife habitat feature, culturally modified tree)
- Unfavourable weather or site conditions could cause environmental damage.
- Conditions have the potential for immediate environmental damage.
- There is reason to believe the project plan will not work.

Purpose and Scope

requirements, industrial standards and best management practices as it relates to fuel handling, storage and transportation. The primary fuel This Environmental Field Procedure (EFP) applies to all BCTS clients (Licensee, Permittee and Contractor workers) and BCTS staff who are used within the forest industry is diesel fuel (UN1202) found under Class 3, Flammable Liquids. This EFP is intended to help promote good Iransportation of Dangerous Goods Act and Regulations, BC Motor Vehicle Act and Regulations, Environmental Management Act and Regulations, Hazardous Products Act and Regulation, Contaminated Sites Act and Regulations, Workers' Compensation Act and OHS esponsible for fuel handling within the scope of BCTS EMS program. The purpose of this document is to bring together legislative inel management, and is not intended to supersede legislative requirements or criteria. Applicable Acts and Regulations include: Regulations.

I regulations.		
Table	Contents	Page #
-	Small Fuel Containers <230 L Includes drums, pails and canisters typically used to transport, store and dispense	C
	small quantities of fuel, oil, solvents and antifreeze	1
7	Small Mobile (Truck Box) Tanks ≤450L Ancillary tank located in the box of a pickup truck used to transport, store	c
	and dispense fuel	9
က	Large Mobile Tanks >450 L to ≤3000L Ancillary tank typically located in the box of a pickup truck used to transport,	-
	store and dispense fuel	t
4	Highway Tanks & TC Portable Tanks, Generally >3000L Used to transport fuel. Sometimes used to store and	ц
	dispense fuel.	ס
2	Large Stationary Skid Tanks >3000L Used to store and dispense fuel, rarely used to transport fuel	9
9	Definition of Terms	
	In an effort to keep this document short and to the point, some terms and clauses were used that may require further	7 to 9
	explanation or interpretation. The Definition of Terms is also used to provide examples.	
	Transport Canada contact information	0
7	Spill Kit Requirements	10
	This section outlines minimum spill kit content requirements for BCTS clients)

page 1 of 10 April 1, 2018

April 1, 2018



				buenel	
IAE	I ABLE #1 SMALL FUEL CONTAINERS (Volumes <230L) Drums,	NERS (Volumes <230L) Drums	<u> </u>	5.00	
Jerry	Jerry Cans, Pails, Canisters	,	■ Legal Requirement SCTS Requirement		
TYPE	CONDITION, DESIGN & MAINTENANCE	STORING & SECURING	DISPENSING	TRANSPORT (see column 2 for securing details)	PREVENTION & RESPONSE
	Must be designed, constructed, filled,	✓ Do not store small containers in Riparian Management areas or	Maintain current MSDS in a	■ Drums must be properly	Take reasonable measures to
	under normal conditions of handling	Marine Environments wherever	Do not dispense fuel in	Stacking in an unright	Record to all fine coils
	and transport there will be no	_		vertical position	L'écapolita la allinea spilla
	accidental release of dangerous	Do not smoke where fuel is stored	or Marine Environments	 Separating and Protecting 	
	goods that would endanger public or	or dispensed	-	through use of boards,	in higher risk areas consider
		:	Dispense all flammable and	stakes or sides on the	utilizing additional Spill Control and
	☑ Containers must be in good condition	Labeling	combustible substances only	vehicle to protect the load	Prevention Measures (see Table
	 not damaged, rusting or leaking. 	Any container over 30 liters must have	from drums in an upright	from moving	#6).
		appropriate safety marks:		It multiple containers of diesel	i
	Construction Standard	 Label or Placard as required, 	Do not fill containers beyond	and/ or gasoline are transported	Fire Control and Response
S	Containers must be specifically	UN number and	their safe filling level	and the combined capacity	Maintain and self-inspect one
ЕВ	designed for the product.	Shipping Name	(approximate safe level –	exceeds 2000L, the following	suitable B:C-rated fire extinguisher
		•		conditions apply:	ensuring it's:
VT/ 082	Containers less than 30 liters are	 TDG safety marks on the outside of an 	Store the hose above the	 A shipping document must 	 not actuated or tampered with
	exempt from IDG requirements but	enclosed unit must be visible if	primb (and drum) to avoid	be completed for the goods	 shows no obvious physical damage,
	are still governed under WHMIS.	containers are stored within an	siphoning.	nauled	(i.e. corrosion, leakage, or clogged
		enclosed unit.		Ine operator must have	nozzle) to prevent its operation
				IDG training and possess a	pressure gauge reading or indicator
	Inspections	WHIMIS labeling or appropriate		certificate	is in operable range
NS		Product Identification is required		Ine load must have	e safety seal or nin in place.
	∠ Licensees/ Contractors must self	when storing hazardous products		placards on all visible sides	salety seal of pill in place,
	inspect containers on a regular basis.			 Empty drum transport are exempt 	 product id/WHMIS label in place
	(plastic containers usually every 5	Securing		from TDG Regs provided:	 located in appropriate location, and
	years). Immediately replace	As per manufacture's		 Drum residue <10% 	 document self-inspections
	containers that are leaking.	recommendations, containers must		 If more than 10 drums then 	
		be secured and kept level to		DANGER Placards are required on	✓ Maintain a soill kit of suitable size
		prevent shifting, swaying, damage,		all four sides and include a	
		escape from the vehicle and		shipping document outlining: the	
		accidental release of product.		primary class, 'residue drums' and	
		 Tie down straps must have safe 		number of drums.	
		combined working load ratings			
		greater than the secured load.			



				Legend	
TAE	TABLE #2 SMALL MOBILE (TRUCK BOX) TANKS (Volumes: ≤450L)	ICK BOX) TANKS (Volumes: 3	≤450L) ■ Legal Requirement ☑ BCTS Requirement		
TYPE	CONDITION, DESIGN, & MAINTENANCE	STORING & SECURING	DISPENSING	TRANSPORT (see column 2 for securing details)	PREVENTION & RESPONSE
SMALL MOBILE (TRUCK BOX) TANKS (450L)	Must be designed, constructed, filled, closed, severed and maintained so under normal conditions of hading and transport there will be no accidental release of dangerous goods that would enderinger public over whether sitely. Conditions of hading and the sitely of conditions of hading and build not damaged, rusting, or leaking construction Standard unstaling, or leaking or deadly of the sitely of the sit	■ Use a pressure relief cap that meets manufacturers design speafincations ■ On on store small mobile tanks in riparian management areas or marine environments wherever productable ■ On ont senvironments wherever marine environments where fuel is stored or dispensed ■ As per manufacture is recommendations, tanks must be appropriately secured and kept level to prevent shriting, be appropriately secured and kept level to prevent shriting, the appropriately secured and the vehicle and accidental release of product. ■ The down straps must have safe greater than the secured load greater than the secured load	Use dispensing pumps designed If the productive briefly analded Use an appropriate hose and norzale (in accordance with U.C standards) for dispensing fuel Make sure there is suitable bonding (i.e. war lined hose) to prevent static charges when dispensing assoline. Maintain current MSDS in a location available to workers a Maintain current MSDS in a location available to workers a maintained and not leak. Do not dispense fuel in riparian management areas on marine environments wherever management areas on marine environments wherever the practicable. Operators must stay with the nozze at all times while dispensing the safe must be secured in drip containment after use or in an upridict position so that it's above the tark. Colose ravies when finished dispensing and leaks (i.e. colled on top of tank) to not fill tranks beyond their safe filling level (approximate safe fill level — 90%).	if multiple tanks of diesel andor gesoline a certained on the yeahine and and the combined on the following conditions apply: • A shipping document must be completed for the goods haude • The operation must have a TDG training and possess a valid certificate • The operation must be placed on all visible sides • The load must be placed on all visible sides • WHMIN labeling or appropriate product learning hardon is visible safety marks: • Label or placed • Un number and when storing hazardous producits with the storing paperwork is linked to the specific ensuring paperwo	■ Take reasonable measures to perfer reasonable measures to severable sever



Legend		RANSPORT (see column 2 for PREVENTION & RESPONSE securing details)	If multiple lanks of diesel and/or agesorier accurated in the gassorier accurated in the gassorier accuration the gassorier accuration the agesorier accuration the and the gample of a gassorier accuration that and a statistical or a fair and and selection and personal and a statistical or a fair and and selection and personal and a fair and and a fair and and a fair and a selection and a fair and a selection and personal and a fair and
		TRANSPORT (If multiple tanks of diese lan gasoline are carried on the vehicle and the <u>combined capacity</u> . A shipping vecedes 2000 liles recombined capacity we credes 2000 liles represented to the hauled be completed for the hauled. The operator must be placeded on all visible so that the placeded on all visibles. If find you mobile tanks are transported on a trailer, the must meet Motor Vehicle Requirements. (GW, brake lights and axels etc.). Safety, Labeling & Spec Plates occupantly and axels etc.). Safety, Labeling & Spec Plates occupantly and axels etc.). Safety, Labeling & Spec Plates occupantly and axels etc.). Shipping and axels etc.). Shipping ame TDG Placards must be visible occumentation. (en saxoal occumentation.) en saxoal occumentation. (en saxoal occumentation.) en surving pare occurrentation. (en saxoal occumentation.) en surving pare occurrentation is required to be appropriate Powelut Identification is require storing hazardous productical expensions expensions expensions and productical expensions are storing hazardous productical expensions.
	Legal Requirement Recourse of BCTS Requirement	DISPENSING	Uses an appropriate hose and nazzle (in accordance with ULC Standards) for dispensing fuel Les dispensing pumps designed for the products being handed. Make sure there is suitable bonding (i.e. wive lined hose) to prevent static charges when dispensing gas oline a Martian current MSDs in a location available to workers or the sea and nozzles must be maintained and not leak man management areas or marine management areas or marine environments wherever practicable. In progression with the nozzles area or marine environments wherever practicable. In prevents and production area of management areas or marine environments where were practicable. In prevention area of marine environment after use or in an environment after use or in an environment after use or in an expension so that it's above the tank. In land the position so that it's above the tank. In land the position so that it's above the tank. In land the position so that it's above the tank. In land the land equipment on level ground dispensing deal on the political position so that it's above the tank. In land the land of the politic or the lank is as fer manner to prevent damage and basks (i.e. cond on the lank). In land the lank beyond their safe lilling level (approximate safe lilling level (approximate safe).
	LARGE MOBILE TANKS (Volumes: >450L - ≤3000L)	STORING AND SECURING	■ Use a pressure relief cap that meets manufaturers design specifications ■ Do not leave vehicles carrying auxiliary fuel in riperation management areas or marine practicable. ■ Do not smoke where fuel is stored or dispensed Securing ■ As per manufacture's a foot of the proportially-secured and kept level to prevent shifting, swaying, damage, escape from the vehicle or fuel. ■ Tie down straps must have safe combined working load ratings greater than the secured oad the production of trailer and accidental release of product. ■ Tie down straps must have safe combined working load ratings greater than the secured load to ensure the tank is integrally mountled.
	#3	CONDITION, DESIGN, & MAINTENANCE	Must be designed, constructed filled, closed, secured and maintained as of under runnial conditions of handling and transport there will be no adolental renaise prother level when conditions of handling and renaise problem or worker safely. Construction Standard All Tanks: used to transport their (regardless of victum) must be in good condition—not deraigned, and constructed to a mobile family standard and rispland so tylowing—will be a favily and will be a favily and specified as a favily and will be a favily and a favily and will be a favily and will be a favily and will be a favily and a favily and will be a favily and will be a favily and a favily with the last 5 years must be read to a regular fassi; minediately replace containers that are leaking.
	TABLE	TYPE	(Volumes: >450L – 3000L)

April 1, 2018



TAB	TABLE #4 UICHWAY STODOSTABLE TANKS	TANKS		Pregend	
(Fuel	FORT THE REPORT OF THE PROPERTY (Fuel Trucks & Pup-Trailers with Volumes > 3000L)	> 3000L)	■ Legal Requirement ☑ BCTS Requirement		
TYPE	CONDITION, DESIGN & MAINTENANCE	STORING AND SECURING	DISPENSING	TRANSPORT (see column 2 for securing details)	PREVENTION & RESPONSE
HIGHWAY & TC PORTABLE TANKS (Volume > 3000L)	Must be designed, constructed, filled, closed, secured and manifalrade so under normal conditions of handing and travacy there will be no accidental release of drange rough of start would endanger public or worker safety. Construction Standard All Tankes, used to transport fuel and sometimes to store and dispense fuel. Tanks must be designed, constructed and/or tested to a design is brindlard before to that smarted. Use All parties of the control of the safe of the sage of the safe of the sage of the control of the safe of SSA BECS 13 Standard. Total Toucks must meet the following: Sales the will all fact 2003 may tan sport for TDG. Sales the what is fact 2003 may tan sport for TDG. Non-Spec Tanks may no longer be used. Any lank without a specifier is non-spec. Inspections: All Highway and Transport Canada (TC), Portable Tank must be tested and rispected by a TC Registered facility every the years. Proof that will kest and inspection were conducted by a TC Registered facility very the years. Include the safe of the safe in specifial is non-spec. I client seeds Contradors must seet in specit tanks on a regular besis, immediately replace containers that are leaking.	Lise a pressure relief hatch that meets manufacturers design specifications. Do not leave fuel truck or pup trailer in riperia management areas or manine environments where fuel is standing to the manufacturers or manufacturers. Explored or dispensed Securing Fuel truck tanks must be inlegally mounted to the unit inlegally mounted to the unit. Explored or dispensed and remains level to prevent acrodited to be source, stable and remains level to prevent accidental release of product. Labeling Product identification is an acceptable substitute for supplier or workplace labels and may be affixed to the sides of the tank compartments and piping.	■ Use an appropriate hose and mozzle (in accordance) with U.C. standards) for depending humps designed for the products being land ded for the products for the land for the products for the product for the products for the product fo	Fuel frucks and pup-trailers used to transport products on public roads must need Mortov Vehicle roads must need Mortov Vehicle roads must need Mortov Vehicle roads must need to Comment (Cardovance). When the total capacity of a fuel tank sexes as 2000 lines: the shipperformers required to Commelder as hipperformers required to Commelder as hipperformers required to When the goods hauled or residue last contained. • Maritam a vaid TDG training certificate • Valide spec plate • Pleaser the lead on all four sides • Morto-Spec tanks may no longer be used. • Non-Spec tanks may no longer be used. • Whon-Spec tanks may no longer be used. • Whon-Spec tanks may no longer and which an viable safety marks: • Label or pleaser d and. • Unamper and on. • Shipping name • TDG Pleaserd must be visible on all four sides • Shipping name • TDG Pleaserd must be visible on all four sides • Shipping name • Containers from Stand and documentation-cleasuring papeawork • Manuta the following: • Container Tope & Stand and • Manuta the following: • Reconfinitation Date and TCF Registered Facility	■ Take reasonable measures to prevent a Respond to all fuel spills ■ Respond to all fuel spills ■ Where dispensing and staming tell in higher risk areas consider utilizing the modeling at \$910 control and dedition at \$910 control and Res ponse ■ Mentalma and self-speed one sailable #6.) ■ Fire Control and Res ponse ■ In pervent its operation ■ shows no obvious physical damage. (in a consision, leadage, or deget no zole) by prevent its operation ■ shows no obvious physical damage. (in operable ange reading or indicator is in operable ange and the proportial bearing or indicator is no poserable ange evolute (id/WMMS) label in place ■ safety seal or pin in place ■ safety seal or pin in place ■ conduct (id/WMMS) label in place ■ conduct a safel in appropriate location, and ■ decounter a safel in appropriate location, and ■ Comment as safel in spropropriate location, and ■ Comment as safel in spropropriate location.



1	TABLE # # 1 100 CONTACT OF TABLE TABLE OF TABLE TABLE			Pregend	
than	than >3000L)	NID LANNS (Generally volumes	■ Legal Requirement ■ BCTS Requirement		
TYPE	CONDITION, DESIGN & MAINTENANCE	STORING AND SECURING	DISPENSING	TRANSPORT (see column 2 for securing details)	PREVENTION & RESPONSE
LARGE STATIONARY SKID TANKS (Volume >3000L)	■ Native segond, constructed filled colond. ■ Sepacial and conditions of the miscontiner will be no accelerated in flanding of the prepariors goods that would endinger public or valorier stells? ■ Sepacial main: used for believing special and will generally have one of the following markings: ■ ULC-6880 LMS hanks ■ ULC-6880 LMS Is Bell Tanks ■ ULC-6880 LMS I	All statement Options not all there ascondary containment Options not about the statement Options and selections of a statement options are statement of the statement of the statement of the statement of the statement and selections to statement danged and leaks (i.e. on a terach; hose is sele mainer to statement danged and leaks (i.e. on a terach; hose seel or cobed) C) not not pleas abstracts yeld this in inpart management areas or marrier environments, unless no other area is practicable. C) Do not standard where fuel is stared or statement of the sta	Lea dispensing pumps bengined for the products being handled. Use an appropriate hose with ULC attended in accordance with ULC attended in accordance with ULC attended in accordance with ULC attended in a series in stailbale bonding to prevent stailing the production and passible with the production and passible with the production and bengined and not beak to maintained and not beak of the prevent and and the prevent and prevents a prevent supprioring the maintained and not beak of the prevent and prevent and the prevent supprioring the dispensing the maintained and and the prevent supprioring the prevent supprioring the prevent supprioring the prevent supprioring the safe filling level (spopuration supprioring level (spopuration supprioring level (spopuration supprise level ground evel ground	without here moving a skid tank (with or without here) having a total capacity of desegreted than 2000 iters you must bloken TUG Regulariors — Complete a shipping of document for the goods hauded or remaining in the goods hauded or remaining in the good occurrence of the Equivalent Level of Safety Persure that all conditions of the Equivalent Level of Safety Persure that all conditions of the Equivalent Level of Safety Persure that all considered administrations are medicated being the Equivalent Level of Safety Persur (see Level only form point to point in accordance with the Equivalent Level of Safety Persur (see table #6 for Labeling Manthain visible safety marks: Labeling Manthain visible safety marks: Labeling Shipping name Dige Record or specification and Contra sides WHMINS labeling abening required when storing hazardous products designed and service of the storing hazardous products when storing hazardous products.	■ Take reasonable measures to prevent leaks \$5 spills ■ Respond b all tuel spills Call Where depands and storing fuel in higher risk areas consider utilizing additional Spill Control and Prevention higher risk areas sonsider utilizing additional Spill Control and Prevention higher risk areas consider utilizing additional Spill Control and Prevention or bills of the spill spill control and Response Call Maintain and self-rispect one suitable BC-rated fire earthquister energy it's: • not actuated or tampered with • shows no obvious playsacil demage. (i. e. corrorson, leakage, or dagged • not actuated or tampered with • shows no obvious playsacil demage. • not actuated or tampered with • shows no obvious playsacil demage. • not actuated or tampered with • shows no obvious blassacile or dagged • not actuated or or tampered with • corresponded angle angle or dagged • product id/WHMIS bear in place • product id/WHMIS bear in place • corrurent self-finspections Maintain a spill kit of suitable size (See Table #7)



Table #6 Definition of Terms

able #6 Definition of Terms	Spill Control • Re-assess the environmental risk and implement additional control measures	ntion Review the BCTS Fuel Handling Environmental Field Procedure 06 to ensure procedures address the risk factors	Review Spill Response awareness and preparedness, conduct a spill drill and increase monitoring of dispensing area locations	Enhance minimum Spill Kit requirements as outlined in Table #7	Move the fuel storage to a lower risk location	Add secondary containment or double-walled containers	Breakaway valves on hoses	Collision Protection e.g. guard logs	Tanks located more than 6 meters from a building	Tarps for containment	Materials to block culverts when needed	Sandbags and PVC pipe for underflow containment	Sandbags for diversions and upstream eddy containment	re Extinguisher The number represents the size of fire the extinguisher will put out under normal use (non-expert)		• A 40 rated fire extinguisher will cover 9.15 square meters. Therefore two 40 rated fire extinguishers will cover the same area as one 80 rated fire extinguisher	• The B.C represents the type of fires: "B" fire is for flammable liquids, while a "C" fire is for electrical	Pediation Any form of nutrients, bacteria or enzymes that when added and mixed with the soil, will enhance the biological breakdown of petroleum hydrocarbon contaminated soil. This product is intended for small leaks, drips and spills that are below the reportable quantities and not impacting surface water or groundwater.	way valve An in-line device containing a flutter valve that, upon accidental separation of the hose, will automatically close and prevent fuel from being discharged	n Protection A barrier sufficient to alert the operator and prevent accidental damage to the container and release of the product.	ed space Any structure enclosed by three sides	llent Spill in an attempt to provide some flexibility in the minimum requirements of a spill kit, the following equivalent standards are listed. The intention of this equivalent list is to	provide	0	○ 5 Absorbent pads (for antifreeze) = 2L of Sphag Sorb (peat moss)	 5 Absorbent pads (for solvents) = 2L of Sphag Sorb (peat moss) 	○ Plug-N-Dike = Bentonite clay or "drillers clay"	○ One large heavy duty plastic bag = One five (5) gallon pail
able #6 Definit	Additional Spill Control	Prevention												B:C Fire Extinguisher)			Bioremediation Product	Breakaway valve	Collision Protection	Enclosed space	Equivalent Spill	Response Equipment	-				



Table #6 Definition of Terms

page 8 of 10



Table #6 Definition of Terms

Material Safety Data	MSDS-are summary documents that provide information about the hazards of a product and advice about safety precautions under the Workplace Hazardous Materials
Sheets (MSDS)	Information System (WHMIS).
Plug-N-Dike	Commercial product name for bentonite day also known as "drillers day". It is not the intention for BCTS to endorse a single product name over other products of a similar and equal nature.
Small Means of	A means of containment with a capacity less than or equal to <230 litres. For example, a drum, jerry cans, or intermediate bulk container.
Containment	
Spec Tank	A "Spec Tank" or "Specification Tank" is a means of containment that complies with one of the specifications set out in one of the Safety Standards referred to in Part 5 of
	the TDG regulations. An example of a "spec tank" would be a TC406 highway tank meeting all of the TC406 specification requirements described in CSA Standard B620- 03 Highway Tanks and Portable Tanks for the Transportation of Dangerous Goods.
TC	Transport Canada: Federal Agency that oversees the transportation of dangerous goods on land, sea and air
TDG	Transportation of Dangerous Goods Regulation
ULC	Underwriters Laboratory of Canada (Engineering Standards) Mobile tanks built to ULC Standards (142.13) have been replaced by the Canadian General Standards Board (CGSB) Standard (43.146)
UN Number	United Nations Number: Used to identify a specific dangerous good. Diesel: UN 1202; Gasoline UN 1203
Workplace Hazardous	Hazardous products in the workplace must be identified through one of the following means:
Materials Information	Supplier label
System (WHMIS)	 Workplace Label (attached when no supplier label was provided or the supplier label is lost or removed)
Labelling & product	○ Name of the product
identification	o Safety precautions
	○ Reference to SDS
	Product Identifier (name of the product, color coding, etc.)

TRANSPORT CANADA CONTACT INFORMATION

Transport Canada welcomes your questions, comments and suggestions. You can contact them by e-mail, mail or telephone and they will address your concerns as quickly as possible. See website link below for details! http://www.tc.gc.ca/eng/contact-us.htm

Leak Test and Inspection Facilities for Highway and TC Portable Tanks, (Registered per Standard CSA B620) can be found at the Transport Canada http://wwwapps.tc.gc.ca/saf-sec-sur/3/fdr-rici/highway/tanks.aspx website link below!

page 9 of 10



ENVIRONMENTAL FIELD PROCEDURE Environmental Management System EFP 06 FUEL HANDLING BC Timber Sales

Table #7

(Minimum Requirements) SPILL KIT

and dispensing fuels n Equipment / Machinery (excavators,

Spill kits must be present on equipment, (appropriate for type and potential size of skidders)

- One large heavy duty plastic bag or Spill kits must include:
 - absorbent material), appropriate for Absorbent pads (or equivalent other suitable container the type of spill,

absorbent material) appropriate for the

10 - absorbent pads (or equivalent

container(s),

3 – 3"x 48" absorbent booms/ socks,

type of spill,

bioremediation product,

One shovel

0

3 - Heavy duty plastic bags or suitable

Spill kits must include a minimum of:

Personal protective safety gear as required for the type of spill

Stationary or Mobile Fuel Storage & dispensing (tanks or multiple-drum caches) Spill kits must be present in vehicles transporting truck box tanks or multiple small containers) Vehicles carrying auxiliary fuel (e.g. pick-up

Spill kits must be present at points where fuel is Spill kits must include a minimum of: dispensed.

- Five large heavy duty plastic bags, or one open topped containment drum (or 20 absorbent pads (or equivalent equivalent), 0
- Two 10' linkable marine booms (if near 6 – 3"x 48" absorbent booms/ socks, type of spill,

absorbent material) appropriate for the

- bioremediation product, marine operations),
- One container of emergency tank sealant (i.e. Plug-N-Dike or equivalent),

Personal protective safety gear as required

for the type of spill

A container of emergency tank sealant (i.e. Plug-N-Dike, Seal-it or equivalent)

Personal protective safety gear as required for the type of spill One shovel

STOP WORK

and contact your project supervisor and the BCTS representative if:

- You are uncertain of the project plan, your responsibilities, or the location of hazardous/sensitive areas.
 - A previously unidentified resource feature, resource value (e.g. cultural) or sensitive area is found. You experience unfavorable weather or site conditions that could cause environmental damage.
- You observe conditions that have the potential for immediate environmental damage.

page 10 of 10

Key Sections of EFP-06

Truck Box (Slip Tanks) and other large portable tanks--230 to 3000 liters (EFP-06 Table #2 and #3)


-non-specification tanks can only be used for diesel in the 230L to 450L volume range and;

must be specification containers and tested by a Transport Canada -tanks for diesel and gasoline in the >450L to 3000L volume range Registered Facility every 5 years;

Large (double walled) Stationary Skid Tanks EFP-06 Table #5

Spill Kits -EFP-06 Table #7







Kootenay Business Area Species of Management Concern Licencees, Permittees & Contractors (LPC) General Guidance Updated August 2016

Introduction

Species of Management Concern are identified as potential environmental impacts associated with various Kootenay Business Area activities under its Environmental Management System (EMS). In addition certification under the Sustainable Forestry Initiative standard requires a program to promote biological diversity such as species at risk.

Apart from the certification programs, BCTS and its Timber Sale Licensees, Permittees and Contractors are required to meet various federal and provincial legislative requirements, such as the Canadian Species at Risk Act, BC Wildlife Act and Forest and Range Practices Act, which relate to the management of wildlife and ecosystems. This document provides guidance to LPCs in managing the species of management concern.

Procedures

Pre-work (BCTS staff and LPC personnel)

- Review any operational requirements/constraints specific to the activity/location as identified in the Site Plan
- Review wildlife (bird, mammal & amphibian) species listed in the 2014 Species of Management Concern in the Kootenay Business Area field guide. (It was decided to focus identification and management on only wildlife species at the operational level as these are the species more likely to be observed by forest workers.)
- · Review notification requirements under the Notification section.

Inspections (BCTS Field Team staff)

- Were any Species of Management Concern identified during operations? If yes, follow procedures under Notification.
- Check client awareness/conformance to specific operational requirements/constraints.

Notification of sightings of wildlife species of concern (all staff and LPC personnel)

Where a Species of Management Concern is sighted in the field:

- Notify BCTS Project Supervisor ASAP.
- For observations, note (at the minimum):
 - o Location (gps coordinates or sufficient information to locate on a map) of observation
 - Date of observation
 - Species
 - Number of individuals seen or heard.
- Other information that is useful is:
 - o Name and contact (phone/email) information of observer
 - Habitat (plant or special features of observation location),
 - Land status of observation (e.g. crown, federal, private)
 - Adjacent landscape (e.g. disturbance, roads)
 - Condition of habitat (measure of the quality of habitat of observation)
 - Health of species (e.g. live, dead, injured/sick). If possible take a picture of the species and make field notes.
 - This information is then forwarded to BCTS Project Supervisor.
- BCTS Project supervisor and Field Team/Planning staff will recommend appropriate site level measures, which may involve engaging a Qualified Professional to assess and indicate a course of action.

BCTS Project Supervisor will submit the information collected to the BC Conservation Data Centre through the following website: www.env.gov.bc.ca/wildlife/wsi/incidental_obs.htm. Please print a copy of the report pages, scan to .pdf with the date (e.g. Western Toad_Aug8-2016.pdf) and file it into the following directory for our records: <a href="https://kxivisor.kxivis



BC Timber Sales Environmental Management System ENVIRONMENTAL FIELD PROCEDURE

Kootenay BA Invasive Plants EFP #09

Purpose and Scope

This EFP applies to BCTS Kootenay Business Area Staff, Licensee, Permittee and Contractor workers involved in forest practices within the scope of the BCTS EMS. It describes specific requirements to prevent the introduction or spread of invasive plants. This EFP does not replace the requirements of legislation, licences, permits and contracts.

Identification and Reporting:

Be familiar with the <u>INVASIVE PLANT INFORMATION PACKAGE</u> provided, this includes:

- ✓ Understanding how to use Kootenay BCTS Invasive Plant Field Book and the identification of what to report in your operating area
- ✓ Location of applicable known infestation areas and any specified measures that apply.

Reportable invasive plants are those listed in the *Kootenay BCTS Field Book*. Invasive plants in the Kootenay BCTS Field Book are to be reported <u>within 30 days</u> of discovery by any of the following options:

- ✓ Use a Smartphone Report-A-Weed BC applications (download either the <u>iPhone app</u> or the <u>Android app</u>), or
- ✓ Go to BC Government invasive plant online reporting website https://www.for.gov.bc.ca/HRA/invasive-species/reportInvasives.htm

Inspecting and Cleaning:

- ✓ In areas of infestation, inspect vehicles, mechanized equipment, culverts, bridges and cattle-guards for presence of soil or plant material prior to being transported to or from work sites and, if present, plant and soil materials are to be removed.
- ✓ Inspections are to be documented.

Grass Seeding:

- Application of grass seeding is required to exposed soils in areas that include; cut and fill slopes of newly constructed roads, constructed or used landings, deactivated roads and any rehabilitated areas. Rehabilitated areas maybe exempt if the rehabilitated areas are to be re-vegetated through the planting of trees.
- ✓ Grass seeding is to occur during the first available spring or fall and not more than 12 months following the time of mineral soil exposure.
- Seed used is to be Canada Common#1 Forage Mix or better or a mix recommended by MFLNRORD range specialist.
- ✓ If utilizing a dry grass seeding method, seed shall be applied at a rate of 30 to 50 kilograms per hectare.

February 18, 2019	EFP 09	1

Roadside Residue Handling



IN-WOODS CHIPPING





3 8
THE STATE OF THE S
All the state of t
and the
And March
andar(Anh

Long Butts

Tops	1 2	Windows Company	ROAD GRA	<10	10-1	>15
Tops		The second secon	PILING INSTRUCTIONS	Pile for in-woods chipping (above)	Pile with secondary harvest agreement only.	Pile for burning if 15% pitches are longer than 50 metres
		The section of the	ROAD GRADE	<10%	10-15%	>15%

Pile for unprocessed collection

Pile for burning if 15% pitches Pile with secondary harvest

agreement only.

are longer than 50 metres

	CUTSLOPE HEIGHT	CUTSLOPE HEIGHT PILING INSTRUCTIONS
ve)	<3 metres	Pile for in-woods chipping (above)
arvester	3 to 5 metres	Pile with secondary harve agreement only.
	>5 metres	Pile for burning

Pile for unprocessed collection (above)

<5 metres

Pile for burning

>5 metres











Page 37



Standard Operating Procedure Bird Nest Encounters

July 7, 2017

APPLICATION:

This SOP applies to all BCTS Licensees, Permittees and Contractors, including their employees, agents and subcontractors, involved in timber harvesting, road construction, road maintenance and silviculture projects.

BACKGROUND:

The Federal Migratory Birds Convention Act protects migratory birds and prohibits the disturbance or destruction of migratory bird nests and eggs. Section 34 of the BC Wildlife Act prohibits the injuring, molesting or destruction of a bird, its egg or a nest occupied or the nests (active or vacant) of an eagle, peregrine falcon, gyrfalcon, osprey, heron or burrowing owl. Large stick nests may be re-used by birds from year to year and are to be protected, even if they are not currently occupied. An active bird nest is one with eggs or live young in it. Signs you may be near an active nest include birds swooping at you or machinery, birds flying in to tree cavities, or cheeping coming from tree cavities, trees or shrubs.

PROCEDURE:

If you encounter an active bird nest or a large stick nest, STOP WORK in the vicinity and immediately report the nest to the Project Supervisor and BCTS. BCTS staff will provide additional guidance or direction consistent with applicable licence, permit or contract provisions.



Establish a NO WORK ZONE that will ensure no further disturbance to the nest. Recommended best practices are to cease disturbances in the nesting area until the young have permanently left the nest (which could range from a few days to a few weeks, depending on the species and stage of development). The nest should be protected with a buffer zone (NO WORK ZONE) appropriate to the species, the level of disturbance and the landscape context. Example buffer distances that may be considered range from:

- 10 50 meters or more for songbirds and other small bird nests, exception is when brushingleave a 5-m no-cut zone in the direction you have not cut yet, and if others need to work in the area, flag a 10m no-work zone around the nest
- 25-50 meters or more for swallow colonies
- 100 to 200 meters for a pileated woodpecker,

Additional information is available from Environment Canada or qualified professionals.

Operations can continue outside of the NO WORK ZONE

1











Kootenay Business Area Wildlife Habitat Features

On May 29, 2018 the Minister of Environment & Climate Change Strategy signed an Order identifying <u>fourteen</u> wildlife habitat features in the Kootenay Boundary region, as listed in the table below.

LIST OF WILDLIFE HABITAT FEATUR	ES – KOOTENAY BOUNDARY REGION
1. a nest of a Bald Eagle	8. an American Badger burrow
2. a nest of an Osprey	9. a Grizzly Bear den
3. a nest of a Flammulated Owl	10. a significant mineral lick
4. a nest of a Western Screech-Owl macfarlanei	11. a significant wallow
subspecies	
5. a nest of a Great Blue Heron	12. a bat hibernaculum
6. a nest of a Lewis's Woodpecker	13. a bat nursery roost
7. a nest of a Williamson's Sapsucker	14. a hot spring or thermal spring

The order defines a "wildlife habitat feature" as a feature used by one or more wildlife species to meet their life history requirements where special management is necessary to ensure that these features are protected and remain functional.

It is important that Licensees, Permittees, and Contractors (LPC) carrying out forest or range activities not damage or render ineffective a *wildlife habitat feature*.

- Where measures to protect a wildlife habitat feature have been specified within a project plan, the holder of an agreement or contract will conduct primary forest activities and other related activities in accordance with the measures specified in the project plan.
- Where an LPC encounters a wildlife habitat feature, not previously identified and accommodated for in an existing project plan, the LPC must...



AND CONTACT YOUR PROJECT SUPERVISOR & BCTS REPRESENTATIVE

Upon reporting of an unidentified wildlife habitat feature, an LPC shall discuss a course of action with a BCTS representative to prevent damaging or rendering the feature ineffective.

Clear definitions and descriptions, as well as suggested management strategies for consideration when carrying out primary forest or range activities can be found in the field guide, at the following link:

https://www2.gov.bc.ca/assets/gov/environment/natural-resource-policy-legislation/legislation-regulation/frpa-pac/wildlife-habitat-features/whf field guide kootenay boundary.pdf

Please note the list of wildlife features in the table above may be expanded from time to time to reflect new information that indicates potential threats from forest or range activities on localized features. Updates will be included in the link above and/or discussed at operational pre-works.

Nov 25, 2020

Kootenay Business Area Wildlife Habitat Features

On May 29, 2018 the Minister of Environment & Climate Change Strategy signed an Order identifying <u>fourteen</u> wildlife habitat features in the Kootenay Boundary region, as listed in the table below.

LIST OF WILDLIFE HABITAT FEATUR	RES – KOOTENAY BOUNDARY REGION
1. a nest of a Bald Eagle	8. an American Badger burrow
2. a nest of an Osprey	9. a Grizzly Bear den
3. a nest of a Flammulated Owl	10. a significant mineral lick
4. a nest of a Western Screech-Owl macfarlanei	11. a significant wallow
subspecies	
5. a nest of a Great Blue Heron	12. a bat hibernaculum
6. a nest of a Lewis's Woodpecker	13. a bat nursery roost
7. a nest of a Williamson's Sapsucker	14. a hot spring or thermal spring

The order defines a "wildlife habitat feature" as a feature used by one or more wildlife species to meet their life history requirements where special management is necessary to ensure that these features are protected and remain functional.

It is important that Licensees, Permittees, and Contractors (LPC) carrying out forest or range activities not damage or render ineffective a *wildlife habitat feature*.

- Where measures to protect a wildlife habitat feature have been specified within a project plan, the holder of an agreement or contract will conduct primary forest activities and other related activities in accordance with the measures specified in the project plan.
- Where an LPC encounters a wildlife habitat feature, not previously identified and accommodated for in an existing project plan, the LPC must...



AND CONTACT YOUR PROJECT SUPERVISOR & BCTS REPRESENTATIVE

Upon reporting of an unidentified wildlife habitat feature, an LPC shall discuss a course of action with a BCTS representative to prevent damaging or rendering the feature ineffective.

Clear definitions and descriptions, as well as suggested management strategies for consideration when carrying out primary forest or range activities can be found in the field guide, at the following link:

https://www2.gov.bc.ca/assets/gov/environment/natural-resource-policy-legislation/legislation/regulation/frpa-pac/wildlife-habitat-features/whf field guide kootenay boundary.pdf

Please note the list of wildlife features in the table above may be expanded from time to time to reflect new information that indicates potential threats from forest or range activities on localized features. Updates will be included in the link above and/or discussed at operational pre-works.

Nov 25, 2020

BC Timber Sales Kootenay Business Area Wet Weather Operating Guide April 2017





Purpose: This guide is intended to assist BCTS clients and staff in recognizing wet weather and ground conditions that may impact worker safety, operations, environment and damage to road systems. The guide also provides suggested best practices and recommends operational shut down

Environmental Management System (EMS). The EMS plays a significant role in maintaining water quality as it requires the licensees and contractors to The primary control mechanism to protect water quality is through the operational controls such as Environmental Field Procedures (EFPs) of the manage erosion and sediment delivery into water features appropriately.

The following are related operational requirements identified in BCTS's EFPs #04 & #05 that apply to BCTS harvesting and road management activities:

- Operate during favourable weather and site conditions
- Implement strategies to minimize impacts to soil productivity and water quality
- Avoid excessive soil disturbance
- Utilize sediment control measures i.e. (silt fences, hay bales, rock armouring, swales, water bars or sediment ponds as appropriate)
 - Clean introduced debris from ditches, streams and culverts on an on-going basis.



STOP WORK and contact your project supervisor and the BCTS representative if:

- You experience unfavourable weather or site conditions that could cause environmental damage.
 - You observe conditions that have the potential for immediate environmental damage.



- Sudden muddy water in creeks (especially in gullies)
 - Sudden lack of flow in creeks during wet weather Cracks appearing in the soil
 - Sloughs $\ge 1 \text{m} \times 1 \text{m}$ occurring in the soil
- -andslides occurring in the general area, or sounds of landslides occurring Anchor stumps pulling out of wet soil
 - Sloughs in road cuts, especially during road construction or deactivation



BCTS BC Timber Sales

BC Timber Sales Kootenay Business Area Wet Weather Operating Guide April 2017

Iso refer to related requirements outlined in BCTS EFP #04 Roads, Bridges and Major Culverts & EFP #05	
arvesting and Road Activities	
I	

Harvesting and	~	Harvesting and Road Activities Also refer to related requirements outlined in BCTS EFP #04 Roads, Bridges and Major Culverts & EFP #05	EFP #04 Roads, Bridges and Major Culverts & I	EFP #05
Harvesting				
Activity		Recommended Practices	Recommended Shut Down Conditions	S
Trail Construction	A	Locate skid and pilot trails in areas that minimize excavation where	. Ground based operations should cease if the following	following
(this includes pilot		possible (avoid steep cuts, seeps, and wet areas).	conditions develop:	
trails for during road	A	Maintain drainage concurrently with skid trail or pilot trail	 Water is transporting visible siltation or sediment 	diment
construction)		construction by utilizing cross-ditches/swale, skid culverts/log	towards streams,	
		bundles including wood puncheon at all seeps and water courses	 Excessive rutting of 15cm or greater depth is 	SI L
		(NCDs and classified water courses). Highly erodible materials	occurring.	
		may require temporary rock armouring. Water bars may be		
		necessary on steeper grades especially when rutting occurs.	2. Operations should be modified or suspended where	where
	A	Install cross-ditches/swales and water bars during periods of	there is abundant hill slope runoff i.e. during spring	pring
		inactivity.	freshet or periods of high runoff from prolonged heavy	d heavy
	A	Utilize sediment control measures where necessary at key control	precipitation.	
		points.		
	A	Locate pilot trails in areas that minimize excavation and optimizes	3. Suspend operations if wet weather causes excessive	cessive
		material use, where possible (avoid steep cuts, seeps, and wet	erosion and rutting particularly to the extent where	here
		areas). Where possible, do not deviate from pre-located road	sediment flow is noticeable or when construction	on
		locations.	material (soils/parent material) losses its ability to hold	y to hold
	A	In areas of significant wet ground, pre-construct this section with	its shape.	
		excavator (i.e. install geotextile, rock ballast etc.) may be	-	
		necessary.		
	A	Prior to any excavations on wet ground, consider utilizing	一 一 一 一 一 一 一 一 一 一 一 一 一 一 一 一 一 一 一	*
		techniques to minimize excessive disturbance such as using		
		geotextile matting, puncheon, or rock ballast etc.). Have a plan		1
		prior to starting.		
	A	Ensure that ruts are cross ditched to allow drainage;		
	A	Maintain natural drainage concurrent with trail construction		
	A	If surfaces become rutted to the extent that water begins to pool or	The second second	100
		road surfaces become saturated from a lack of drainage, install		
		drainage control such as cross-ditches, swales and/or water bars.		The same
	A	Back blade to remove ruts and hasten dry material when		
		conditions allow		

BC Timber Sales Kootenay Business Area Wet Weather Operating Guide April 2017



Activity	Recommended Practices	Recommended Shut Down Conditions
Ground Skidding	 Machine use should be limited to areas where excessive scour, rutting, or compaction is avoidable. This would generally restrict 	 Ground based operations should cease if the following conditions develop:
	machine use from areas of moderately steep slopes as well as any localized areas of well so for or very localized areas of well so for or very localized areas of well so for or very localized areas of well as any	Water is transporting visible siltation or sediment
	reduce the likelihood of concentrated or redirected drainage, as	 Excessive rutting of 15cm or greater depth is
	well as shallow subsurface water interception.	occurring.
	Waintain drainage features clean out introduce debris concurrent	
	with operations.	Operations should be modified or suspended where
	Utilize sediment control measures where necessary at key control	there is abundant hill slope runoff i.e. during spring
	points.	freshet or periods of high runoff from prolonged heavy
Cable Skidding	Fall, skid, and yard away from all streams and NCDs where	precipitation.
	practicable.	
	Avoid cross-stream yarding and keep all riparian features clear of	Suspend operations if wet weather causes excessive
	debris.	erosion and rutting particularly to the extent where
	Where possible, avoid excessive repetitive scouring.	sediment flow is noticeable or when construction
	Maintain drainage features clean out introduce debris concurrent	material (soils/parent material) losses its ability to hold
	with operations.	its shape.
	Utilize sediment control measures at key control points.	
Hauling and Road	Operate during favourable weather and site conditions	 Road use should be suspended if:
Use	If hauling during marginal conditions prolong haul window and	 Road surface runoff is transporting visible siltation
	minimize road damage by daily tending of the road surface.	or sediment into streams,
	Utilize sediment control measures at key control points	 Road surface becomes soupy
	Minimize accumulation of moisture to road surface, install	 Ruts become sloppy and deformed
	temporary waterbars (well skewed) and spot surfacing of short	Acceptable depth of ruts is subject to discretion depending
	sections	on site conditions. In general, pick-up truck access should
	Operate during favourable weather and site conditions	be un-impeded,
Road	Schedule road works required in fine textured soils during dry weather	Material does not hold intended shape or achieve desired
Maintenance,	condition i.e.: summer/fall dry.	compaction when handled
Deactivation		Proceed with grading only under dry or slightly damp
		conditions.

FPInnovations prepared this guide in order to provide forest workers with information on purpose built skid trails on steep slopes. FPInnovations worked in close cooperation with BC Timber Sales, Kootenay Business Area during the development of this guide. Reference material for this guide included The Construction and Rehabilitation of Purpose-Built Skid Trails on Steep Slopes: Discussion Paper; FPInnovations Technical Report No. 3 (March 2015) by C. Gillies.

Photo's courtesy of BCTS

For more information about the use or intent of this guide,

please contact:

Ken Scown, RPF British Columbia Timber Sales ken.scown@gov.bc.ca

For more information about the development of this guide,

please contact:

Clayton Gillies, RPF, RPBio FPInnovations clayton.gillies@fpinnovations.ca

This guide can be downloaded and printed from www.fpinnovations.ca







The construction and rehabilitation of purpose built skid trails on steep slopes

A PRACTICAL GUIDE FOR FOREST WORKERS

fpinnovations.ca

REDUCING SITE IMPACTS

Constructing purpose-built skid trails to extract timber from steep slope harvest areas needs to be done with careful construction practices and with rehabilitation in mind. This guide will help forest workers choose appropriate construction and rehabilitation methods which aim to address soil protection and water management in an environmentally sensitive manner.

Best Practices and Sustainablity

The goal is to minimize soil disturbance, rehabilitate disturbed areas, and maintain / restore subsurface and surface drainage.

Forest workers need to choose harvesting strategies that minimize soil disturbance and maintain the biological and physical function of forest soils. Long-term soil productivity, hydrologic function, sediment generation, and the stability of current and rehabilitated trails are all key aspects to focus efforts towards, in order to sustain a healthy and productive forest ecosystem / productive forest land base.

Plan your work

Purpose-built skid trails have historically been used to aid ground-based harvesting on steep side slopes, specifically to accommodate the extraction of timber. The following should be considered during construction:

- · Use appropriate type and size of equipment.
- · The amount of newly constructed trails should be minimized.
- · Use existing / historic trails when appropriate.
- Utilize professional reports when available (terrain stability assessment, hydrology, soil, etc.)
- Constructed trails should not result in any concentration or redirection of runoff. As well, avoid locating trails where there is a risk of damaging any existing drainage structures.
- Trails should be constructed with a plan for rehabilitation; trails should be fully rehabilitated upon completion of harvesting and prior to spring runoff (not left to overwinter).
- As a best management practice, plan to rehabilitate trails concurrent with harvesting such as when a logical unit / area is complete.

Trail Construction



Use small excavators

- · Narrow trails will minimize disturbance
- Sort and place woody materials using the excavator's bucket and live thumb; the placement of woody material along the toe of the fill slope helps to reduce disturbances and provides a visual cue of the disturbance limits during rehabilitation.
- Use of an excavator during construction allows for the exposure
 and sorting of the forest floor and soil horizons. The aim of
 trail construction should include the separation of nutrientrich productive surface soil and organic material from less
 productive subsoil, so that during trail rehabilitation, both layers
 can be retrieved and deposited in the original undisturbed order.
 This placement of soil back to the location it was removed from
 helps to maintain site productivity.
- · Light weight machines help to reduce compaction.

Construct with deactivation in mind

- Planning ahead for rehabilitation by minimizing soil disturbance will reduce the rehabilitation efforts required.
- Stumps along the low side of a skid trail can be used to support fill and reduce the quantity of cut and fill required by holding the material at a steeper angle.
- The use of snow during winter construction helps to reduce the amount of cutbank excavation required to build the trail to the desired width, resulting in less disturbance. Use of the trail during frozen conditions will reduce soil disturbance due to reduced compaction and the reduced depth of decompaction required.
- Use of log bundles placed in a temporary stream crossings or seepage during trail construction:
 - Will deactivate more easily than excavating through solid frozen ground.
 - Will result in less soil disturbance resulting in a reduced erosion of the crossing site.
 - Provide a high level of protection to the channel and banks.

TRAIL REHABILITATION

GOAL

The goal is to improve site nutrient and soil moisture holding capacity (which provides a good substrate for seedling establishment and growth), restore soil structure, improve aeration porosity, control erosion, restore drainage patterns, and leave hummocky surface with variable micro-relief which incorporates large woody material.

Timing: Rehabilitate trail before spring runoff

A summer-built trail, which will not be rehabilitated before operations end and winter begins, will require seasonal deactivation to manage water. Waterbars and / or swales need to be constructed to shed water from the trail and prevent erosion.

A winter-built trail, which has a snow layer as part of the fill, will require careful planning in order to have all rehabilitation completed before snow melts. If the snow fill melts, the stability of the trail will be compromised.

PHASES OF REHABILITATION

Site Preparation: Remove long branches and stems before decompaction. No long branches or stems should be left in place during decompaction or recontouring (do not mix branches in with the soil). The stems could intercept and direct subsurface seepage resulting in concentrated flows causing erosion or instability.

Decompaction: Rip with teeth of excavator bucket to loosen soil below compacted surface. Rip deeper in the middle of the trail than the inside (uphill) track. This will provide an outsloping profile for the loosened soil. The outer (downhill) track will be decompacted during sidecast retrieval as part of recontouring.

Recontouring: Placement of soil material in reverse order – manage nutrient rich top soil to promote soil productivity. Place soil material to top of the cut bank.



Water Management:

Construct waterbars to help ensure slope hydrology has been restored. Waterbars can be regularly spaced as well as positioned at obvious swale locations. Waterbars are constructed to collect flows and disperse water down slope. Waterbar spacing will prevent concentrated flows from forming.

Outsloped swales or rolling grades constructed along the rehabilitated trail will provide water management benefits similar to those of waterbars.

Planting: Tree seedlings provide the growing stock of timber for future forest management.

The phases of decompaction and the retrieval of soil during recontouring help with seedling establishment and growth. Large woody debris should not be spread too thick otherwise it would interfere with the planting areas for tree seedlings.

Surface Roughness: The placement of large woody debris over the recontoured surface will help provide microsites more suitable for tree seedling growth; woody debris provides both shade and associated moisture retention.

Keep the surface rough and irregular to prevent erosion. The use of large woody debris will aid in preventing rainfall from eroding bare soils.

TRAIL DECOMPACTION

Decompaction should be done by ripping the trail surface with the teeth of an excavator-mounted bucket. A ripping depth of 10 to 30 cm is easily achieved.

4

Further spreading of the ripped material can be done with the bucket of the excavator which also will loosen the newly ripped surface material




Reduced cutbank

The mid track position should be ripped deeper than the inner track (upslope) position. This will promote an outsloping profile for the loosened soil. The shallow rip along the inner track will also help to prevent ripping into the undisturbed subsoil which could result in intercepting any functioning subsurface drainage.

The outer track location will be decompacted during sidecast retrieval and the placement of this material during recontouring.

SEASONAL CONSIDERATIONS

- When full rehabilitation of a summer-built trail needs to be suspended due to the onset of winter and frozen conditions, partial deactivation is required to control the water and prevent erosion along the trail network. Waterbars must be constructed along the trail before abandoning the trail network for the winter. Full deactivation can start again once the weather permits, allowing decompaction and recontouring to be completed. Rehabilitating trails concurrent with the completion of a logical unit / area will help to reduce the need to suspend activities.
- Deactivation of a winter constructed trail needs to be completed during the winter and before the snow melts. The snow placed as fill is providing support to the trail. If the snow melts the width of the trail will be reduced and the sorted soil layers will be compromised. A reduced trail width would not provide the needed trail width or stability for an excavator to rehabilitate the trail.
- During winter recontouring, retrieved material placed along the trail will settle as the snow melts, therefore material should be placed higher to compensate for this settlement.




Kootenay Business Area Road Deactivation Guidance Document

The intent of deactivation is to place the road in a self-maintaining state that will indefinitely protect adjacent resources at risk.

The purpose of a cross-ditch is to intercept road surface and ditchline water and convey it across the road onto stable, non-erodible slopes below the road.

Diagram of cross-ditch installation across an intact road.



A well-compacted ditch block will be installed immediately downgrade of the cross-ditch inlet. The ditch block is usually higher than the road surface. The ditch block should be non-erodible, relatively impermeable, and large enough to divert all expected flows into the cross-ditch. Where ditchwater converges at low points in the road, no ditch block or berm is required, as the cross-ditch should be constructed as a broad gentle swale.


Armour the base of the cross-ditch if erosion or rutting of the subgrade is expected to
cause a problem for future road access. Armour the outlet of the cross-ditch, unless
noted in the prescriptions. Size and placement of the armour will depend on the
anticipated flows and downstream consequences.

August 2011

- Use angular rock large enough to protect exposed soil, but small enough so as not to
 divert or obstruct flows. Where coarse rock is unavailable, other methods of protecting
 the outlet area may include revegetation, erosion control mats, sandbags, soil
 bioengineering, or appropriately sized and placed woody debris.
- The resulting cross ditch or ford will allow for easy 4 wheel drive, pickup truck access.

A ford is a dip in a road constructed to cross a perennial or ephemeral stream. It is usually designed and built as a permanent feature during original road construction, or road deactivation

Example of a ford installed on a non-fish-bearing stream.



August 2011





Sustainable Forestry Initiative (SFI) Client General Awareness Document

The purpose of this document is to provide BC Timber Sale clients (supervisors/workers) with a general awareness to the principles of the SFI Forest Management Standard, including SFI basic training requirements in a tailgate training format. To learn more about the SFI organization and its standards go to www.forests.org The SFI principles are based on an array of objectives, performance measures and indicators.

SFI Forest Management Standard Principles

Sustainable Forestry

- Forest Management is a balance of social, economic, and environmental values now and in the future
- Balancing harvesting with the needs of other values like water, soil, plants, animals, aquatic habitats and ecological
 communities, recreation, and the capacity of the land to grow trees including consideration of climate change
 adaptation and mitigation.

Forest Productivity and Health

- Protect soils because productive soils support ecological values including growing trees
- Know the applicable soil disturbance limits and use appropriate methods to avoid excessive soil disturbance
- · Become familiar with applicable invasive plants in your area and prevent/minimize their introduction and spread
- Prevent forest fires

Protection of Water Resources

- To protect and maintain water quality and quantity of water bodies and riparian areas, Follow BCTS Environmental
 Field Procedures (EFPs) and any local Water Quality Best Management Practices (BMPs) applicable to your forest
 management activities
- Ensure that forest practices do not degrade water quality values through the introduction of soil/silt; petrochemical
 products like hydraulic fluid, oil, gas, and diesel; and other chemicals used in forest management activities, e.g.,
 herbicides
- Maintain the water's natural drainage patterns to the fullest extent possible and re-establish natural drainage patterns upon completion of forest management activities
- Follow wet weather shutdown procedures where they exist
- Do not disrupt the natural rate and timing of water flow through road construction or other forest management activities

Protection of Biological Diversity

- Know that BCTS's Species of Management Concern (SOMC) program is intended to protect threatened or endangered species and ecological communities (plants and animals).
- Know what SOMC exist, or could exist, in areas associated with your forest management activities
- Become familiar with Project Plans for forest operations to understand how to manage for SOMC
- Know about and protect biologically significant sites in or around areas of proposed forest management activities, e.g., parks, ecological reserves, old growth management areas, wildlife habitat areas, etc.
- · Maintain Wildlife Tree Retention Areas (WTRAs) and other stand-level retention requirements

Version Sept 19, 2022





Aesthetic Values and Recreation

- Implement Project Plans for forest operations to ensure that visual values on the landscape are maintained
- Prevent or mitigate potential negative impacts to recreational opportunities as a result your activities

Protection of Special Sites

Know about geologically (i.e. Karst) or culturally (i.e. historic, First Nations traditional use) significant sites in or around areas of proposed forest management activities in order to protect their unique qualities

Efficient Use of Fiber Resources

Ensure efficient utilization of harvested timber, minimize waste

Recognize and Respect Indigenous Peoples' Rights

- Understand and respect traditional forest-related knowledge, including non-timber forest products of value to indigenous peoples
- Identify and protect spiritually, historically or culturally important sites

Legal and Regulatory Compliance

- Know the laws applicable to your activities (See http://www.bclaws.ca/legallinks.html)
- Make sure your activities are consistent with Project Plans that guide your forestry management activities
- Follow applicable Safety/WorkSafeBC laws and regulations

Training and Education

- Ensure that supervisors have completed BCTS EMS/SFM Awareness training and show documentation to BCTS
- Train your crews and maintain training records
- Commit to continuous learning in the areas in which you are involved in forestry activities
- Understand what aspects of your job have the greatest environmental impacts and then learn how to implement new procedures, techniques, or technology to minimize potential impacts

Continuous Improvement

- ✓ STOP WORK if you believe the Project Plan will not work
- ✓ Monitor and inspect your work
- ✓ Follow-up on corrective and preventative actions
- ✓ Participate in internal and external audits
- ✓ Report project changes and inconsistent forest practices

If you suspect that forest practices are not meeting the SFI principles you are encouraged to submit a complaint as described on the Western Canadian SFI Implementation Committee (WCSIC) Inconsistent Practices website. To learn more about WCSIC, or how to file a complaint, please refer to the WCSIC 'Procedure for Addressing Allegations of SFI Non-

Conformance' at the following web address: http://www.wcsic.ca/Inconsistent/Practices.php

Version Sept 19, 2022



BC TIMBER SALES – Working with Indigenous Peoples

Last Updated: September 19, 2022

generating economic prosperity in British Columbia through safe and sustainable forest management and the auction of timber. As part of our BC Timber Sales (BCTS) manages the harvesting and reforestation of approximately 20 per cent of the allowable annual cut for public land, business planning, there are guiding principles for forest sector safety, sustainable forest management, and reconciliation with Indigenous

Reconciliation with Indigenous Peoples is integral to BCTS' mandate and its long-term success, and the program will continue to engage with indigenous Peoples on how to best collaborate and continue our collective journey towards reconciliation. Part of this journey is improving cultural awareness and the understanding of Indigenous Peoples' history, relationship with the land and legal framework. This includes opportunities to build effective and ongoing relationships with Indigenous Peoples.

experiences and culture. Each Indigenous Nation has unique cultures, community interests, and concerns regarding operations in their territories. relationships and informing operational decisions, it is important to understand Indigenous Peoples' connection to the land and how Indigenous indigenous Peoples would like the land to be treated with respect, and the impacts to the land and its values minimized. As part of building Working together with Indigenous Peoples takes willingness to building relationships by participating in open exchanges regarding wants, knowledge can inform such decisions.

Understanding our shared history and why it has led to intergenerational trauma for Indigenous Peoples is an important step towards reconciliation, righting some wrongs from the past, and improving relationships with Indigenous Peoples. The following information provides further insight into why we need to work with Indigenous Peoples but is only a fraction of available information. This document should be considered a starting point in educating all who work with BCTS. 0

for Indigenous Peoples. This includes educating ourselves connection to the land, and the importance of traditional colonialism has resulted in ongoing generational trauma Ongoing Learning is important to understand why on traditional governance, Indigenous Peoples' knowledge

discovery and awareness, and understanding why cultural humility and cultural safety are important to healing We need to build positive relationships through selfrelationships.

everyone's points of view and culture are important to Education, listening to each other, and understanding reduce potential conflict

The ability to work respectfully, knowledgeably, and effectively will result in positive relationships.

scoops; the missing and murdered Indigenous women and effects are still seen today. Some examples of this are: the continuing existence of the Indian Act; residential and day Peoples through racist and colonial policies, and the Colonialism has greatly impacted Indigenous schools; Indian hospitals; the sixties and millennium girls, and past and current provincial and federal government systems.

renew trust based relationships with Indigenous Peoples By working together, we can shift the status quo and based on respect Success will be when Indigenous Peoples believe they are self-governing, self-reliant and self-determining.

who work directly for BCTS, TSL holders and Peoples need to work together to build a better British Columbia. This includes all Indigenous and Non-Indigenous contractors.

To attempt to right wrongs from the past, we reconciliation and build positive relationships

must work together to move towards

with Indigenous Peoples.

Colonialism forced Indigenous Peoples to

disconnect from their lands, culture, and

community.

assimilation, systematic destruction of impacted Indigenous Peoples through 1700s (for BC) colonialism has greatly Since **European contact** in the late culture, and disease. The goal of the Province (including BCTS) is to reconcile with Indigenous Peoples. This Indigenous communities to participate in includes providing opportunities for BC's economy.

WHEN

Indigenous

Peoples

Relationships

with

₹ Q E

Building

This process is ongoing, and reconciliation will be achieved when everyone agrees. This may take time and will evolve over

outside of government and on government worksites, and industry (including As part of reconciliation, building respectful relationships, and forming positive partnerships with Indigenous Peoples will take place within and forestry) is also working to partner with Indigenous Peoples.

0

EMS INCIDENT REPORTING REQUIREMENTS

1. Emergency Response Incidents

- Fire: Any uncontrolled fire related to BCTS activities
- Spills: any spill exceeding BCTS reportable levels or any amount spilled into or immediately adjacent to a stream, lake or running water.
- Erosion/Landslide events: any emergency situations or potential emergency exists, abnormal movement has or is occurring, abnormal sedimentation, a volume of material greater than 250^{m3} has moved or is at imminent risk of movement, or a land area greater than 0.25 ha is disturbed through erosion processes

2. Potential Non-Compliance:

 In the opinion of the person reporting, legislation and regulation has been violated and there may be an agency investigation to determine fact and possible enforcement action.

3. Significant Non-conformance:

- An occurrence or event that has or will likely result in a negative impact to a significant environmental aspect and cannot be immediately rectified
- Where the EMS program has been severely compromised and or a "Notice to Comply" has been issued at the discretion of local management. This includes; repeated non-conformances that may become significant.

Report	Reportable Levels	
Substances	BCTS	d3d
Antifreeze	5 litres	2
		kilograms
Diesel fuel	25 litres	100 litres
Gasoline (auto &	25 litres	100 litres
saw)		
Greases	25 litres	100 litres
Hydraulic Oil	25 litres	100 litres
Lubricating Oils	25 litres	100 litres
Methyl Hydrate	5 litres	2
		kilograms
Paints & Paint	25 litres	100 litres
Thinners		
Solvents	25 litres	100 litres
Pesticides	1	1
	kilogra	kilogram
	m	
Explosives	Any	Any

NOTES

NOTES



BCTS Environmental Management System EMS Tailgate Training

Field Card for use by LPC supervisors to support worker EMS and SFM training BEFORE STARTING WORK KNOW ABOUT:

1. Environmental and Sustainable Forest Management Policies

- Complying with the law.
- Prevent & minimize impacts on the environment.
- Practice of sustainable forestry.
- Recognition and respect for indigenous rights
- Continuous Improvement

2. Emergency Response Plan

- Know your eERP roles and responsibilities.
- Be prepared for emergencies i.e. fire, spills and erosion events.
- Know location of applicable ER equipment (spill kit, hand tools, fire suppression).

3. Environmental Field Procedures

- EFP #1 "General" applies to all workers.
- EFP #2 "Supervisors" applies to project and/or onsite supervisors.
- EFP #3 "Developing & Planning" applies to planning & development activities.
- <u>EFP #4 "Roads Bridges and Major Culverts"</u> applies road construction, maintenance, inspections and deactivation activities.
- EFP #5 "Harvesting" applies to all phases of harvesting activities.
- EFP #6 "Fuel Handling" applies to fuel handling activities.
- EFP #7 "Dryland Sort" applies to dryland sort activities.
- <u>EFP #8 "Marine Log Handling Facilities"</u> applies to construction & operations of log dumps, helicopter water drop zones, and direct barge-loading facilities.

Ensure all workers are familiar with the EFPs that apply to their roles and responsibilities before starting work. Copies available from your supervisor or BCTS representative.

4. Stop Work Procedures (See EFPs)

If not sure, Stop Work and contact your project supervisor or BCTS representative.

5. What to report to Supervisor and BCTS

- Hazardous Material Spills, Uncontrolled Fires & Erosion / Landslide Events.
- Potential non-compliances and non-conformances.
- Unidentified resource features, values, or sensitive areas e.g. Karst, Bear dens, culturally modified trees
- · Species of Management Concern sightings.
- Changes to project plan.
- Safety hazards, close calls/near misses, or accidents.
- STOP Work situations

Revised Sept 19, 2022 1