

AB-FS_PC9-A2_H488

Project Cargo Corridor - Pre-Approved Permit Conditions

Notice: This is a travel condition document, not a permit. For information about obtaining permits for travel, see the **contact process and information attached**. By electing to use this permit approval rather than seeking a custom Extraordinary Load Approval, the user agrees that information about this permit application and any associated permits may be shared between the Ministry of Transportation and any municipalities who have jurisdiction over roads along the approved route.

Notice: The permitting authorities who have authorized use of this form for pre-approval of permits for compliant vehicles along the specified route acknowledge only that they have been notified of the movement of this load along the specific route. Such acknowledgment does not constitute the permitting authorities' assumption of risk or waiver of the applicant's or any third party's liability for any damage or loss incurred by the permitting authorities or any one of them as a result of the applicant's transportation of the vehicles, loads, or equipment on the routes of travel described in this document. The permitting authorities, including utility companies with infrastructure along the routes, reserve the right to pursue a claim or action for damages arising as a result of the movement of the load(s) as set out in this document. For travel on municipal portions of Project Cargo Corridors, separate approval will be needed from utility companies.

BC/AB Border on Hwy 16 to Fraser Surrey Docks – Overheight (4.30 m to 4.88 m)

The following pre-approved permit conditions are applicable only for the semi-trailer configuration listed in the table below, at the spacings and at or less than the weights shown.

Semi-trailer	Width	Length	Height
Non-steering	5 meters	23.5 KPLA*	over 4.30 meters
Rear-steering	5 meters 3.2 meters	45 meters 50 meters	over 4.30 meters

* KPLA – king pin to last axle

9 Axle Configuration A2 (PC 9-A2)

Axle No.	1	2	3	4	5	6	7	8	9	GCVW
Axle Description	Steer	Tandem Drive		Tandem Jeep		Tandem Trailer		Tandem Booster		
Max Axle Weight (kg)	7,700	23,000		23,000		23,000		23,000		99,700
No. of Tires	2	8		8		8		8		
Spacing (m)		4.39 - 5.51	1.37 - 1.52	4.27 - 4.59	1.37	9.9 - 14.0	1.37	4.27 - 4.57	1.37	

The overload configuration described above is approved to use bridges on the following portions of the route that are under the jurisdiction of the B.C. Ministry of Transportation and Infrastructure (MOTI), and in some cases as specified, those under the jurisdiction of municipalities along the route, subject to the listed bridge crossing restrictions below. Bridge crossing restrictions for NON MOTI jurisdiction bridges have been taken from separate bridge evaluation reports available from the relevant jurisdictions.

Bridge Crossing Restrictions

The Carrier must comply with all bridge crossing restrictions

A) General Bridge Crossing Restrictions

A.1) The carrier shall assign a person who is not driving to accompany the move and be responsible for:

- identifying the locations of bridges on the route and their required bridge crossing restrictions, and
- relaying these to the driver of the overweight vehicle.

This permit condition only applies to route segments which have bridges with bridge crossing restrictions.

A.2) No additional axles (including additional puller or pusher trucks) shall be added to the Vehicle Configuration that crosses any bridge.

Carriers at Extreme Width and Length Limits

Special measures may be required for certain maneuvers along the designated routes. **For special condition maneuvers, a minimum of 4 pilot cars are required.** Included in the route below are suggested maneuvers, general notes, and cautions for the carrier's consideration.

Route Summary – (MOTI Jurisdiction except as specified)

Hwy 16, Hwy 5, Hwy 1/5, Hwy 5, Hwy 3, Hwy 1, Hwy 11, [8 Avenue/Huntingdon Road/Vye Road \(City of Abbotsford & Township of Langley\)](#), Hwy 13, [Fraser Hwy, Langley Bypass \(Township of Langley & City of Langley\)](#), Hwy 10, Hwy 15, Hwy 17, Tannery Road, [Timberland Road, Robson Road, Elevator Road \(City of Surrey\)](#)

B) Specific Bridge Crossing Restrictions

LEG 1 – MOTI Jurisdiction

- Travel west from BC/AB Border on Highway 16 to Highway 5
- South on Highway 5 to Highway 1/5
- West on Highway 1/5 to Highway 5
- South on Highway 5 to Highway 3
- West on Highway 3 to Highway 1

Select the route option, A, B, or C, that is applicable to the vehicle OAH.

A) If OAH is greater than 4.3 m but less than or equal to 4.5 m

- West on Highway 1 to Highway 11

B) If OAH is greater than 4.5 m but less than or equal to 4.8 m

- West on Highway 1 to No. 3 Road
- Take exit ramp at No. 3 Road (Exit #104), cross No. 3 Road, take on ramp back onto Highway 1

- Continue west on Highway 1 to Highway 11

C) ***If OAH is greater than 4.8 m***

- West on Highway 1 to Lickman Road
- Take exit ramp at Lickman Road (Exit #116), cross Lickman Road, take on ramp back onto Highway 1
- Continue west on Highway 1 to No. 3 Road
- Take exit ramp at No. 3 Road (Exit #104), cross No. 3 Road, take on ramp back onto Highway 1
- Continue west on Highway 1 to Highway 11

- South on Highway 11 to Vye Road

The following **3** bridges:

Fraser River East, No. 1408 (on Highway 16 approximately 12.7 km from the BC/AB Border),

Ghita, No. 1444 (on Highway 16 approximately 15.8 km from the BC/AB Border),

Fraser River West, No. 1407 (on Highway 16 approximately 17.6 km from the BC/AB Border)

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload
- 3) At a speed less than 10 km/h

The following **2** bridges:

Moose River, No. 1405 (on Highway 16 approximately 28.3 km from the BC/AB Border),

Robson River, No. 2276 (on Highway 16 approximately 62.2 km from the BC/AB Border)

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload

The following **1** bridge:

Tete Jaune, No. 2315 (on Highway 5 approximately 0.2 km from the junction with Highway 16)

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload
- 3) At a speed less than 10 km/h

The following **3** bridges:

Cedarside O/P, No. 1655 (on Highway 5 approximately 24.4 km from the junction with Highway 16),

Canoe River, No. 2300 (on Highway 5 approximately 26.8 km from the junction with Highway 16),

Albreda River North, No. 2297 (on Highway 5 approximately 58.3 km from the junction with Highway 16),

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload

The following **3** bridges:

Gosnell, No. 2294 (on Highway 5 approximately 64.3 km from the junction with Highway 16)

Moonbeam, No. 2293 (on Highway 5 approximately 65.9 km from the junction with Highway 16),

Lempriere, No. 2292 (on Highway 5 approximately 68.9 km from the junction with Highway 16)

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload
- 3) At a speed less than 10 km/h

The following **2** bridges:

Whitewater, No. 1295 (on Highway 5 approximately 99.1 km from the junction with Highway 16),

Blue River, No. 2279 (on Highway 5 approximately 107.7 km from the junction with Highway 16)

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload

The following **2** bridges:

6 Mile, No. 2264 (on Highway 5 approximately 119.5 km from the junction with Highway 16),

Avola, No. 2245 (on Highway 5 approximately 147.6 km from the junction with Highway 16)

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload
- 3) At a speed less than 10 km/h

The following **2** bridges:

Avola O/H, No. 2250 (on Highway 5 approximately 147.7 km from the junction with Highway 16),

Mad River, No. 1328 (on Highway 5 approximately 175.8 km from the junction with Highway 16)

Must be crossed:

- 1) Down the centerline of the bridge roadway

- 2) With no other vehicles on the bridge at the same time as the overload

The following 1 bridge:

Clearwater River, No. 0866 (on Highway 5 approximately 218.1 km from the junction with Highway 16)

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload
- 3) At a speed less than 10 km/h

The following 3 bridges:

Barriere North Thompson, No. 0099 (on Highway 5 approximately 27.7 km from the junction with Highway 24 (Little Fort)),

Barriere River, No. 2210 (on Highway 5 approximately 29.4 km from the junction with Highway 24 (Little Fort)),

Louis Creek, No. 0263 (on Highway 5 approximately 34.6 km from the junction with Highway 24 (Little Fort))

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload

The following 1 bridge:

Station Road O/P, No. 2935 (on Highway 5 approximately 69.3 km from the junction with Highway 24 (Little Fort))

Must be crossed:

- 1) Down the centerline of the bridge roadway in the direction of travel
- 2) With no other vehicles in the direction of travel at the same time as the overload

The following 2 bridges:

Kamloops East, No. 0098 (on Highway 5 approximately 6.0 km from the junction with CN Road (North Kamloops)),

Kamloops East O/H, No. 2209 (on Highway 5 approximately 6.3 km from the junction with CN Road (North Kamloops))

Must be crossed:

- 1) Straddling two lanes in the direction of travel
- 2) With no other vehicles in the direction of travel at the same time as the overload
- 3) At a speed less than 10 km/h

The following 1 bridge:

Peterson Creek, No. 2319 (on Highway 5 approximately 2.0 km from the junction with Highway 1/97 (Kamloops))

Must be crossed:

- 1) With no other vehicles in the same lane at the same time as the overload

The following 1 bridge:

Springhill Drive O/P, No. 2220 (on Highway 1/5 approximately 3.1 km from the junction with Highway 1/97 (Kamloops))

Must be crossed:

- 1) Down the centerline of the bridge roadway in the direction of travel
- 2) With no other vehicles in the direction of travel at the same time as the overload
- 3) At a speed less than 10 km/h

The following 2 bridges:

Sagebrush O/P, No. 2344 (on Highway 1/5 approximately 3.7 km from the junction with Highway 1/97 (Kamloops)),

Afton O/P, No. 2876W (on Highway 5 approximately 0.5 km from the junction with Highway 1/97 (West of Kamloops))

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload
- 3) At a speed less than 10 km/h

The following 2 bridges:

Sugarloaf O/P, No. 2889W (on Highway 5 approximately 2.3 km from the junction with Highway 1/97 (West of Kamloops)),

Ajax O/P, No. 2888W (on Highway 5 approximately 6.0 km from the junction with Highway 1/97 (West of Kamloops))

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload

The following 1 bridge:

Nicola River, No. 2843W (on Highway 5 approximately 1.2 km from the junction with Highway 5A North Junction (Merritt))

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload
- 3) At a speed less than 10 km/h

The following 1 bridge:

Kingsvale O/P, No. 2845W (on Highway 5 approximately 29.5 km from the junction with Highway 5A South Junction (Merritt))

Must be crossed:

- 1) Down the centerline of the bridge roadway in the direction of travel
- 2) With no other vehicles in the direction of travel at the same time as the overload
- 3) At a speed less than 10 km/h

The following 1 bridge:

Henning, No. 2830W (on Highway 5 approximately 57.6 km from the junction with Highway 5A South Junction (Merritt))

Must be crossed:

- 1) Straddling two lanes in the direction of travel
- 2) With no other vehicles on the bridge at the same time as the overload
- 3) At a speed less than 10 km/h

The following **2** bridges:

Ladner Creek, No. 2853 (on Highway 5 approximately 88.5 km from the junction with Highway 5A South Junction (Merritt)),

Nicolium Creek, No. 2828 (on Highway 5 approximately 108.6 km from the junction with Highway 5A South Junction (Merritt))

Must be crossed:

- 1) Straddling two lanes in the direction of travel
- 2) With no other vehicles in the direction of travel at the same time as the overload
- 3) At a speed less than 10 km/h

The following **2** bridges:

Alexander No. 1, No. 2849 (on Highway 3 approximately 2.6 km from the junction with Highway 5),

Two Mile Creek, No. 1248 (on Highway 3 approximately 3.3 km from the junction with Highway 5)

Must be crossed:

- 1) Down the centerline of the bridge roadway in the direction of travel
- 2) With no other vehicles in the direction of travel at the same time as the overload
- 3) At a speed less than 10 km/h

The following **2** bridges:

Thacker Creek O/P, No. 2826W (on Highway 3 approximately 4.0 km from the junction with Highway 5),

Floods Hope O/P, No. 2645W (on Highway 3 approximately 6.4 km from the junction with Highway 5),

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload
- 3) At a speed less than 10 km/h

The following **3** bridges:

Hunter Creek, No. 2516W (on Highway 1 approximately 9.7 km from the junction with Highway 3)

Hunter Creek O/P, No. 2875W (on Highway 1 approximately 10.3 km from the junction with Highway 3),

Waleach Creek, No. 2496W (on Highway 1 approximately 15.5 km from the junction with Highway 3)

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload

The following 1 bridge:

Atchelitz Creek, No. 1530W (on Highway 1 approximately 18.2 km from the junction with Highway 9 (Bridal Falls))

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload
- 3) At a speed less than 10 km/h

The following 1 bridge:

Vedder Canal WB, No. 1658 (on Highway 1 approximately 25.8 km from the junction with Highway 9 (Bridal Falls))

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload

The following 1 bridge:

Marshall Creek, No. 6017 (on Highway 11 approximately 0.3 km from the junction with Highway 1)

Must be crossed:

- 1) Straddling two lanes in the direction of travel
- 2) With no other vehicles in the direction of travel at the same time as the overload
- 3) At a speed less than 10 km/h

LEG 2 – City of Abbotsford

- West on Vye Road until it turns into Huntingdon Road
- Continue west on Huntingdon Road until 276 Street where it turns into 8th Avenue

LEG 3 – Township of Langley

- Continue west on 8th Avenue to Highway 13

LEG 4 – MOTI Jurisdiction

- North on Highway 13 to Fraser Highway

LEG 5 – Township of Langley

- West on Fraser Highway until just East of Old Yale Road

LEG 6 – City of Langley

- Continue west on Fraser Highway to Langley Bypass
- North on Langley Bypass to the junction with Kwantlen Place

LEG 7 – MOTI Jurisdiction

- Continue north then west on Langley Bypass (Highway 10) to Highway 10
- West on Highway 10 to Highway 15
- North on Highway 15 to Highway 17 (Westbound)
- North then west on Highway 17 to Tannery Road
- Northwest then southwest on Tannery Road to Timberland Road

The following 1 bridge:

South Serpentine River, No. 2575N (on Highway 15 approximately 0.4 km from the junction with Fraser Highway)

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload

The following 1 bridge:

176th Street U/P, No. 1651 (on Highway 15 approximately 0.5 km from the junction with Golden Ears Way)

Must be crossed:

- 1) Straddling two lanes in the direction of travel
- 2) With no other vehicles in the direction of travel at the same time as the overload

The following 1 bridge:

Fraser Heights, No. 5929 (on Highway 17 approximately 2.1 km from the junction with Highway 1)

Must be crossed:

- 1) Down the centerline of the bridge roadway in the direction of travel
- 2) With no other vehicles in the direction of travel at the same time as the overload
- 3) At a speed less than 10 km/h

The following 1 bridge:

Tannery Rd O/H, No. 8290 (on Tannery Road approximately 0.4 km from the junction with Highway 17)

Must be crossed:

- 1) Straddling two lanes in the direction of travel
- 2) With no other vehicles in the direction of travel at the same time as the overload

LEG 8 – City of Surrey

- Southwest on Timberland Road until it turns into Robson Road
- Southwest on Robson Road to Elevator Road
- West on Elevator Road to site

General Permit Conditions – BC/Alberta Border on Hwy 16 to Lower Mainland

The following pre-approved permit conditions are organized by vehicle dimensions. Any vehicles that fall outside these dimensions or outside the weights and spacing from page 1 of this document must be sent to the Commercial Transport Advisors at the Provincial Permit Centre for evaluation following the normal procedures for Extraordinary Loads.

Condition A – OAW of 2.61 to 4.4 Meters Wide

- In order to accommodate bridge crossing and other conditions of travel, a minimum of 2 pilot cars are required (may be more; see special conditions along the route)

Route	Travel Time
Alberta to Blue River	Travel Time as per CVSE 1000
Blue River to Kamloops	8:00 pm to 6:00 am*
Kamloops to Hope	No Travel Time Restrictions
Hope to Lower Mainland	12:01 am to 5:00 am

*if the Bridge Crossing Restriction states “must cross bridge down centre line” or you are travelling between May 1st and Sept 30 then: *Travel Time* - 11:00 pm to 6:00 am

Condition B – OAW of 4.41 to 5.0 Meters Wide

- Travel from Monday to Friday only
- Minimum of 3 pilot cars required (see special conditions along the route)

Route	Travel Time
Alberta to Blue River	8:00 pm to 6:00 am*
Blue River to Kamloops	8:00 pm to 6:00 am*
Kamloops to Hope	No Travel Time Restrictions
Hope to Lower Mainland	12:01 am to 5:00 am

*if the Bridge Crossing Restriction states “must cross bridge down centre line” or you are travelling between May 1st and Sept 30 then: *Travel Time* - 11:00 pm to 6:00 am

Notice: This permit is valid only for travel on highways listed in section 7.01 (1) of the Commercial Transport Regulations. The applicant is responsible for obtaining any further approvals, permits, or authorizations which may be necessary for travel on other highways.

For your information, a list of some common municipal permit conditions and bylaw provisions can be found below. However, this list may not be exhaustive and it is the applicant's responsibility to ensure they are aware of the laws in all applicable jurisdictions.

- Noise: No use of engine retarder brakes or other excessive noise on municipal roads.
- Liability/Insurance: The permittee must be properly licensed and insured for British Columbia; and must possess a minimum \$10,000,000 third-party liability insurance.

Contact Process and Information

All jurisdictions on your route must give approval before permits can be issued. Please request your approval quoting vehicle configuration, permit condition document, by email to the following.

Jurisdictions	Permit Needed?	Approval Emails
<i>MOTI</i>	Yes	DAWCREEK@gov.bc.ca
<i>City of Surrey</i>	Yes	engineering@surrey.ca
<i>City of Langley</i>	Yes	engineering@langleycity.ca
<i>Township of Langley</i>	Yes	enginfo@tol.ca
<i>City of Abbotsford</i>	Yes	highwaypermits@abbotsford.ca
<i>Email String</i>	DAWCREEK@gov.bc.ca ; engineering@surrey.ca ; engineering@langleycity.ca ; enginfo@tol.ca ; highwaypermits@abbotsford.ca	

Expect a response within 2 business days from all jurisdictions contacted. Note that many municipal offices are closed from December 25th to January 2nd and approvals should not be expected back during this time. Once you have all approvals, please proceed to obtain your permits as directed below.

Jurisdictions	Contact Information
<i>MOTI</i>	<ul style="list-style-type: none"> • Apply by phone at 1 800 559-9688
<i>City of Surrey</i>	<ul style="list-style-type: none"> • Apply by phone at 1 604 591-4340
<i>City of Langley</i>	<ul style="list-style-type: none"> • Download application online, and email it to engineering@langleycity.ca or fax it to 604 514-2322 • Apply in person
<i>Township of Langley</i>	<ul style="list-style-type: none"> • Download application online, and email it to enginfo@tol.ca or fax it to 604 533-6098. • Apply in person
<i>City of Abbotsford</i>	<ul style="list-style-type: none"> • Download application online, and email it to highwaypermits@abbotsford.ca or fax it to 604 853-2219. • Apply by phone at 604 864-5514. • Apply in person