

AB-LT_PC8-A2_H488

Project Cargo Corridor - Pre-Approved Permit Conditions

Notice: This is a travel condition document, not a permit. For information about obtaining permits for travel, see the contact process and information attached. By electing to use this permit approval rather than seeking a custom Extraordinary Load Approval, the user agrees that information about this permit application and any associated permits may be shared between the Ministry of Transportation and any municipalities who have jurisdiction over roads along the approved route.

Notice: The permitting authorities who have authorized use of this form for pre-approval of permits for compliant vehicles along the specified route acknowledge only that they have been notified of the movement of this load along the specific route. Such acknowledgment does not constitute the permitting authorities' assumption of risk or waiver of the applicant's or any third party's liability for any damage or loss incurred by the permitting authorities or any one of them as a result of the applicant's transportation of the vehicles, loads, or equipment on the routes of travel described in this document. The permitting authorities, including utility companies with infrastructure along the routes, reserve the right to pursue a claim or action for damages arising as a result of the movement of the load(s) as set out in this document. For travel on municipal portions of Project Cargo Corridors, separate approval will be needed from utility companies.

BC/AB Border on Hwy 16 to Lynnterm – Overheight (4.57 m to 4.88 m)

The following pre-approved permit conditions are applicable only for the semi-trailer configuration listed in the table below, at the spacings and at or less than the weights shown.

Semi-trailer	Width	Length	Height
Non-steering	5 meters	23.5 KPLA*	4.57 – 4.88 meters
Rear-steering	5 meters 3.2 meters	45 meters 50 meters	4.57 – 4.88 meters

* KPLA – king pin to last axle

8 Axle Configuration A2 (PC 8-A2)

Axle No.	1	2	3	4	5	6	7	8	GCVW
Axle Description	Steer	Tandem Drive ¹		Single Jeep ²	Tridem Trailer			Single Booster	
Max Axle Weight (kg)	7,700	29,000			27,000			9,100	72,800
No. of Tires	2	8		4	12			4	
Spacing (m)		4.39 - 5.51	1.37 - 1.52	1.78 - 1.82	9.9 - 14.0	1.40 - 1.52	1.40 - 1.52	3.5 - 4.30	

1. Max. 23,000 kg 2. Max. 11,000 kg

The overload configuration described above is approved to use bridges on the following portions of the route that are under the jurisdiction of the B.C. Ministry of Transportation and Infrastructure (MOTI), and in some cases as specified, those under the jurisdiction of municipalities along the route, subject to the listed bridge crossing restrictions below. Bridge crossing restrictions for NON MOTI jurisdiction bridges have been taken from separate bridge evaluation reports available from the relevant jurisdictions.

Bridge Crossing Restrictions and Special Measures

The Carrier must comply with all bridge crossing restrictions

A) General Bridge Crossing Restrictions

A.1) The carrier shall assign a person who is not driving to accompany the move and be responsible for:

- identifying the locations of bridges on the route and their required bridge crossing restrictions, and
- relaying these to the driver of the overweight vehicle.

This permit condition only applies to route segments which have bridges with bridge crossing restrictions.

A.2) No additional axles (including additional puller or pusher trucks) shall be added to the Vehicle Configuration that crosses any bridge.

Carriers at Extreme Width and Length Limits

Special measures may be required for certain maneuvers along the designated routes. **For special condition maneuvers, a minimum of 4 pilot cars are required.** Included in the route below are suggested maneuvers, general notes, and cautions for the carrier's consideration.

Route Summary - (MOTI Jurisdiction except as specified)

Hwy 16, Hwy 5, Hwy 1/5, Hwy 5, Hwy 3, Hwy 1, Hwy 11, 8 Avenue/Huntingdon Road/Vye Road (City of Abbotsford & Township of Langley), Hwy 13, Fraser Highway, Langley Bypass (Township of Langley & City of Langley), Hwy 10, Hwy 15, Hwy 1, Willingdon Avenue, Loughheed Highway, Boundary Rd (City of Burnaby), E 1st Ave (City of Vancouver), Hwy 1, Main Street, Dollarton Hwy, Riverside Dr, Mt Seymour Pkwy (District of North Vancouver), Fern St, Keith Rd, Mountain Highway, Main Street, Harbour Avenue, Dominion Street, Mountain Highway (District of North Vancouver)

A) Specific Bridge Crossing Restrictions and Special Measures

LEG 1 – MOTI Jurisdiction

- Travel west from BC/AB Border on Highway 16 to Highway 5
- South on Highway 5 to Highway 1/5
- West on Highway 1/5 to Highway 5
- South on Highway 5 to Highway 3
- West on Highway 3 to Highway 1 (Hope)

Select the route option A or B that is applicable to the vehicle OAH.

A) ***If OAH is greater than 4.57 m but less than or equal to 4.76 m***

- West on Highway 1 to No. 3 Road
- Take exit ramp at No. 3 Road (Exit #104), cross No. 3 Road, take on ramp back onto Highway 1
- Continue west on Highway 1 to Highway 11

B) ***If OAH is greater than 4.76 m but less than or equal to 4.88 m***

- West on Highway 1 to Lickman Road
- Take exit ramp at Lickman Road (Exit #116), cross Lickman Road, take on ramp back onto Highway 1
- Continue west on Highway 1 to No. 3 Road
- Take exit ramp at No. 3 Road (Exit #104), cross No. 3 Road, take on ramp back onto Highway 1
- Continue west on Highway 1 to Highway 11

- South on Highway 11 to Vye Road

The following 1 bridge:

Gosnell, No. 2294 (on Highway 5 approximately 64.3 km from the junction with Highway 16)

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload
- 3) At a speed less than 10 km/h

The following 1 bridge:

Whitewater, No. 1295 (on Highway 5 approximately 99.1 km from the junction with Highway 16)

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload

The following 2 bridges:

6 Mile, No. 2264 (on Highway 5 approximately 119.5 km from the junction with Highway 16),

Avola, No. 2245 (on Highway 5 approximately 147.6 km from the junction with Highway 16)

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload
- 3) At a speed less than 10 km/h

The following 2 bridges:

Raft River, No. 1080 (on Highway 5 approximately 210.2 km from the junction with Highway 16),

Barriere North Thompson, No. 0099 (on Highway 5 approximately 27.7 km from the junction with Highway 24 (Little Fort))

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload

The following **1** bridge:

Kamloops East, No. 0098 (on Highway 5 approximately 6.0 km from the junction with CN Road (North Kamloops))

Must be crossed:

- 1) Straddling two lanes in the direction of travel
- 2) With no other vehicles in the direction of travel at the same time as the overload
- 3) At a speed less than 10 km/h

The following **1** bridge:

Sumas Canal, No. 2880 (on Highway 1 approximately 28.1 km from the junction with Highway 9 (Bridal Falls))

Must be crossed:

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload

LEG 2 – City of Abbotsford

- West on Vye Road until it turns into Huntingdon Road
- Continue west on Huntingdon Road until 276 Street where it turns into 8th Avenue

LEG 3 – Township of Langley

- Continue west on 8th Avenue to Highway 13

LEG 4 – MOTI Jurisdiction

- North on Highway 13 to Fraser Highway

LEG 5 – Township of Langley

- West on Fraser Highway until just East of Old Yale Road

LEG 6 – City of Langley

- Continue west on Fraser Highway to Langley Bypass
- North on Langley Bypass to the junction with Kwantlen Place

LEG 7 – MOTI Jurisdiction

- Continue north then west on Langley Bypass (Highway 10) to Highway 10
- West on Highway 10 to Highway 15
- North on Highway 15 to Highway 1 (Westbound)
- West on Highway 1 to Willingdon Avenue
- North on Willingdon Avenue to Still Creek Avenue

CAUTION**Hwy 15 on-ramp to Hwy 1**

- Approved to 5 m wide and 23.5 m KPLA only

The following Underpass:

Douglas Road U/P, No. 1671 (Highway 1 goes underneath the bridge, approximately 10.1 km from the junction with Brunette Avenue)

If OAH is between 4.66 m and 4.88 m, use Lane 2 and/or 3 from the right shoulder when travelling under the bridge

LEG 8 – City of Burnaby

- Continue north on Willingdon Avenue to Lougheed Highway
- West on Lougheed Highway to Boundary Road
- North on Boundary Road to E. 1st Avenue

The following 1 bridge (not under MOTI jurisdiction):

Willingdon Ave. O/H, No. 80083 (on Willingdon Avenue approximately 0.9 km from the junction with Highway 1)

Must be crossed:

- 1) Straddling two inner lanes in the direction of travel
- 2) With no other vehicles in the direction of travel at the same time as the overload

SPECIAL CONDITION**Lougheed Hwy onto Boundary Rd**

- Move into the eastbound Lougheed Hwy (counterflow) at the intersection of Lougheed Hwy and Gilmore Ave
- Turn right into northbound Boundary Rd

CAUTION

Boundary onto 1st Ave

- Long/Wide loads may mount the median island on 1st Ave

CAUTION

1st Ave on-ramp to Hwy 1

- Approach from far left lane

LEG 9 – City of Vancouver

- West on E. 1st Avenue to Highway 1 (Westbound)

LEG 10 – MOTI Jurisdiction

- North on Highway 1 to Main Street
- East on Main Street to Dollarton Highway

LEG 11 – District of North Vancouver

- Continue east on Dollarton Highway to Riverside Drive
- North on Riverside Drive to Mt. Seymour Parkway
- West on Mt. Seymour Parkway to Seymour Boulevard

SPECIAL CONDITION

Riverside Dr. onto Mt Seymour Parkway

- 3-point turn (Drive straight through, reverse into counterflow (south side of Mt Seymour Pkwy), then proceed west on Mt. Seymour
- Concrete sections of median barrier need to be removed

LEG 12 – MOTI Jurisdiction

- Continue west on Mt. Seymour Parkway to Fern Street
- South then west on Fern Street to Keith Road

The following 1 bridge:

Fern St. U/P, No. 1516 (on Fern Street approximately 0.2 km from the junction with Mt. Seymour Parkway)

Must be crossed:

- 1) Straddling two lanes in the direction of travel
- 2) With no other vehicles in the direction of travel at the same time as the overload

- Continue west on Keith Road to Mountain Highway
- South on Mountain Highway to Main Street
- West on Main Street to Harbour Avenue
- South on Harbour Avenue to railway tracks and transfer load across tracks
- South on Harbour Avenue from railway tracks to Dominion Street
- East on Dominion Street to Mountain Highway
- South on Mountain Highway to site

SPECIAL CONDITION

Mountain Hwy onto Main St

- 3-point turn: drive straight through intersection on Mountain Hwy, reverse onto Main St, proceed west on Main St

CAUTION

Main St onto Harbour Ave

- Long/Wide loads may mount the median island or sidewalk on Harbour Ave

SPECIAL CONDITION

Use of the Harbour Avenue Gates and Crossing of Rails to exit the Port

Vehicles greater than 4.43 m (or too long to travel safely through the rail overpass on Mountain Highway) entering or exiting Lynnterm must request approval from CN Rail by email to both of the following individuals, to obtain access and egress from the port at Harbour Avenue.

Gary Hanson
(604) 589-6522
Gary.Henson@cn.ca

Josh Aspenlind
(250) 877-3093
Joshuah.Aspenlind@cn.ca

Allow for at least 10 days for this approval. This is in addition to the Highway Use Permit from District of North Vancouver, which is for the staging area outside the port.

General Permit Conditions – BC/Alberta Border on Hwy 16 to Lower Mainland

The following pre-approved permit conditions are organized by vehicle dimensions. Any vehicles that fall outside these dimensions or outside the weights and spacing from page 1 of this document must be sent to the Commercial Transport Advisors at the Provincial Permit Centre for evaluation following the normal procedures for Extraordinary Loads.

Condition A – OAW of 2.61 to 4.4 Meters Wide

- In order to accommodate bridge crossing and other conditions of travel, a minimum of 2 pilot cars are required (may be more; see special conditions along the route)

Route	Travel Time
Alberta to Blue River	Travel Time as per CVSE 1000
Blue River to Kamloops	8:00 pm to 6:00 am*
Kamloops to Hope	No Travel Time Restrictions
Hope to Lower Mainland	12:01 am to 5:00 am

*if the Bridge Crossing Restriction states “must cross bridge down centre line” or you are travelling between May 1st and Sept 30 then: *Travel Time* - 11:00 pm to 6:00 am

Condition B – OAW of 4.41 to 5.0 Meters Wide

- Travel from Monday to Friday only
- Minimum of 3 pilot cars required (see special conditions along the route)

Route	Travel Time
Alberta to Blue River	8:00 pm to 6:00 am*
Blue River to Kamloops	8:00 pm to 6:00 am*
Kamloops to Hope	No Travel Time Restrictions
Hope to Lower Mainland	12:01 am to 5:00 am

*if the Bridge Crossing Restriction states “must cross bridge down centre line” or you are travelling between May 1st and Sept 30 then: *Travel Time* - 11:00 pm to 6:00 am

Notice: This permit is valid only for travel on highways listed in section 7.01 (1) of the Commercial Transport Regulations. The applicant is responsible for obtaining any further approvals, permits, or authorizations which may be necessary for travel on other highways.

For your information, a list of some common municipal permit conditions and bylaw provisions can be found below. However, this list may not be exhaustive and it is the applicant's responsibility to ensure they are aware of the laws in all applicable jurisdictions.

- Noise: No use of engine retarder brakes or other excessive noise on municipal roads.
- Liability/Insurance: The permittee must be properly licensed and insured for British Columbia; and must possess a minimum \$10,000,000 third-party liability insurance.

Contact Process and Information

All jurisdictions on your route must give approval before permits can be issued. Please request your approval quoting vehicle configuration, permit condition document, by email to the following.

Jurisdictions	Permit Needed?	Approval Emails
<i>MOTI</i>	Yes	DAWCREEK@gov.bc.ca
<i>District of North Vancouver</i>	Yes	hup@dnv.org
<i>City of Vancouver</i>	No	Engineering.ClientServices@vancouver.ca
<i>City of Burnaby</i>	No	engineering@burnaby.ca
<i>City of Langley</i>	Yes	engineering@langleycity.ca
<i>Township of Langley</i>	Yes	enginfo@tol.ca
<i>City of Abbotsford</i>	Yes	highwaypermits@abbotsford.ca
<i>Email String</i>	DAWCREEK@gov.bc.ca ; hup@dnv.org ; Engineering.ClientServices@vancouver.ca ; engineering@burnaby.ca ; engineering@langleycity.ca ; enginfo@tol.ca ; highwaypermits@abbotsford.ca	

Expect a response within 2 business days from all jurisdictions contacted. Note that many municipal offices are closed from December 25th to January 2nd and approvals should not be expected back during this time. Once you have all approvals, please proceed to obtain your permits as directed below.

Jurisdictions	Contact Information
<i>MOTI</i>	<ul style="list-style-type: none"> • Apply by phone at 1 800 559-9688
<i>District of North Vancouver</i>	<ul style="list-style-type: none"> • Download Highway Use Permit (HUP) application online, and submit online or e-mail it to hup@dnv.org
<i>City of Langley</i>	<ul style="list-style-type: none"> • Download application online, and email it to engineering@langleycity.ca or fax it to 604 514-2322 • Apply in person
<i>Township of Langley</i>	<ul style="list-style-type: none"> • Download application online, and email it to enginfo@tol.ca or fax it to 604 533-6098.

	<ul style="list-style-type: none">• Apply in person
<i>City of Abbotsford</i>	<ul style="list-style-type: none">• Download application online, and email it to highwaypermits@abbotsford.ca or fax it to 604 853-2219.• Apply by phone at 604 864-5514.• Apply in person