

## LT-AB\_PC8-B1\_H430

# Project Cargo Corridor - Pre-Approved Permit Conditions

**Notice:** This is a travel condition document, not a permit. For information about obtaining permits for travel, see the contact process and information attached. By electing to use this permit approval rather than seeking a custom Extraordinary Load Approval, the user agrees that information about this permit application and any associated permits may be shared between the Ministry of Transportation and any municipalities who have jurisdiction over roads along the approved route.

**Notice:** The permitting authorities who have authorized use of this form for pre-approval of permits for compliant vehicles along the specified route acknowledge only that they have been notified of the movement of this load along the specific route. Such acknowledgment does not constitute the permitting authorities' assumption of risk or waiver of the applicant's or any third party's liability for any damage or loss incurred by the permitting authorities or any one of them as a result of the applicant's transportation of the vehicles, loads, or equipment on the routes of travel described in this document. The permitting authorities, including utility companies with infrastructure along the routes, reserve the right to pursue a claim or action for damages arising as a result of the movement of the load(s) as set out in this document. For travel on municipal portions of Project Cargo Corridors, separate approval will be needed from utility companies.

### **Lynnterm to BC/AB Border on Hwy 16 – Standard Height (up to 4.3 m)**

The following pre-approved permit conditions are applicable only for the semi-trailer configuration listed in the table below, at the spacings and at or less than the weights shown.

Semi-trailer	Width	Length	Height
Non-steering	5 meters	23.5 KPLA*	up to 4.30 meters
Rear-steering	5 meters 3.2 meters	45 meters 50 meters	Up to 4.30 meters

\* KPLA – king pin to last axle

### **8 Axle Configuration B1 (PC 8-B1)**

Axle No.	1	2	3	4	5	6	7	8	GCVW
Axle Description	Steer	Tandem Drive		Single Jeep	Tridem Trailer			Single Booster	
Max Axle Weight (kg)	7,700	23,000		11,000	27,000			9,100	77,800
No. of Tires	2	8		4	12			4	
Spacing (m)		4.39 - 5.51	1.37 - 1.52	3.50 - 3.85	8.43 - 9.9	1.40 - 1.52	1.40 - 1.52	3.5 - 4.30	

The overload configuration described above is approved to use bridges on the following portions of the route that are under the jurisdiction of the B.C. Ministry of Transportation and Infrastructure (MOTI), and in some cases as specified, those under the jurisdiction of municipalities along the route, subject to the listed bridge crossing restrictions below. Bridge crossing restrictions for NON MOTI jurisdiction bridges have been taken from separate bridge evaluation reports available from the relevant jurisdictions.

## **Bridge Crossing Restrictions and Special Measures**

***The Carrier must comply with all bridge crossing restrictions***

### **A) General Bridge Crossing Restrictions**

A.1) The carrier shall assign a person who is not driving to accompany the move and be responsible for:

- identifying the locations of bridges on the route and their required bridge crossing restrictions, and
- relaying these to the driver of the overweight vehicle.

This permit condition only applies to route segments which have bridges with bridge crossing restrictions.

A.2) No additional axles (including additional puller or pusher trucks) shall be added to the Vehicle Configuration that crosses any bridge.

### **Route Summary** - (MOTI Jurisdiction except as specified)

Mountain Highway (District of North Vancouver), Main Street, Hwy 1, Hwy 3, Hwy 5, Hwy 1/5, Hwy 5, Hwy 16

### **B) Specific Bridge Crossing Restrictions and Special Measures**

---

#### **LEG 1 – District of North Vancouver**

---

- Travel north from site on Mountain Highway to Main Street

---

#### **LEG 2 – MOTI Jurisdiction**

---

- East on Main Street to Highway 1
- South then east on Highway 1 to Highway 3
- Continue east on Highway 3 to Highway 5
- North on Highway 5 to Highway 1/5
- East on Highway 1/5 to Highway 5
- North on Highway 5 to Highway 16
- East on Highway 16 to BC/AB Border

The following **1** bridge:

**Sumas Canal, No. 1662** (on Highway 1 approximately 14.6 km from the junction with Highway 11)

#### **Must be crossed:**

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload

The following 2 bridges:

**Kamloops East O/H, No. 2209** (on Highway 5 approximately 0.9 km from the junction with Highway 1 (Kamloops)),

**Kamloops East, No. 0098** (on Highway 5 approximately 1.0 km from the junction with Highway 1 (Kamloops))

**Must be crossed:**

- 1) Straddling two lanes in the direction of travel
- 2) With no other vehicles in the direction of travel at the same time as the overload

The following 2 bridges:

**Avola, No. 2245** (on Highway 5 approximately 97.5 km from the junction with Highway 24 (Little Fort)),

**6 Mile, No. 2264** (on Highway 5 approximately 125.7 km from the junction with Highway 24 (Little Fort))

**Must be crossed:**

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload
- 3) At a speed less than 10 km/h

The following 1 bridge:

**Whitewater, No. 1295** (on Highway 5 approximately 146.0 km from the junction with Highway 24 (Little Fort))

**Must be crossed:**

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload

The following 1 bridge:

**Gosnell, No. 2294** (on Highway 5 approximately 180.9 km from the junction with Highway 24 (Little Fort))

**Must be crossed:**

- 1) Down the centerline of the bridge roadway
- 2) With no other vehicles on the bridge at the same time as the overload
- 3) At a speed less than 10 km/h

## **General Permit Conditions – Lower Mainland to BC/Alberta Border on Hwy 16**

The following pre-approved permit conditions are organized by vehicle dimensions. Any vehicles that fall outside these dimensions or outside the weights and spacing from page 1 of this document must be sent to the Commercial Transport Advisors at the Provincial Permit Centre for evaluation following the normal procedures for Extraordinary Loads.

### **Condition A – OAW of 2.61 to 4.4 Meters Wide**

- In order to accommodate bridge crossing and other conditions of travel, a minimum of 2 pilot cars are required (may be more; see special conditions along the route)

<b>Route</b>	<b>Travel Time</b>
Lower Mainland to Hope	12:01 am to 5:00 am
Hope to Kamloops	No Travel Time Restrictions
Kamloops to Blue River	8:00 pm to 6:00 am*
Blue River to Alberta	Travel Time as per <a href="#">CVSE 1000</a>

\*if the Bridge Crossing Restriction states “must cross bridge down centre line” or you are travelling between May 1st and Sept 30 then: *Travel Time* - 11:00 pm to 6:00 am

### **Condition B – OAW of 4.41 to 5.0 Meters Wide**

- Travel from Monday to Friday only
- Minimum of 3 pilot cars required (see special conditions along the route)

<b>Route</b>	<b>Travel Time</b>
Lower Mainland to Hope	12:01 am to 5:00 am
Hope to Kamloops	No Travel Time Restrictions
Kamloops to Blue River	8:00 pm to 6:00 am*
Blue River to Alberta	8:00 pm to 6:00 am*

\*if the Bridge Crossing Restriction states “must cross bridge down centre line” or you are travelling between May 1st and Sept 30 then: *Travel Time* - 11:00 pm to 6:00 am

**Notice:** This permit is valid only for travel on highways listed in section 7.01 (1) of the Commercial Transport Regulations. The applicant is responsible for obtaining any further approvals, permits, or authorizations which may be necessary for travel on other highways.

For your information, a list of some common municipal permit conditions and bylaw provisions can be found below. However, this list may not be exhaustive and it is the applicant’s responsibility to ensure they are aware of the laws in all applicable jurisdictions.

- Noise: No use of engine retarder brakes or other excessive noise on municipal roads.
- Liability/Insurance: The permittee must be properly licensed and insured for British Columbia; and must possess a minimum \$10,000,000 third-party liability insurance.

**Contact Process and Information**

All jurisdictions on your route must give approval before permits can be issued. Please request your approval quoting vehicle configuration, permit condition document, by email to the following.

Jurisdictions	Permit Needed?	Approval Emails
<i>MOTI</i>	Yes	DAWCREEK@gov.bc.ca
<i>District of North Vancouver</i>	No	hup@dnv.org
<b><i>Email String</i></b>	<a href="mailto:DAWCREEK@gov.bc.ca">DAWCREEK@gov.bc.ca</a> ; <a href="mailto:hup@dnv.org">hup@dnv.org</a>	

Expect a response within 2 business days from all jurisdictions contacted. Note that many municipal offices are closed from December 25<sup>th</sup> to January 2<sup>nd</sup> and approvals should not be expected back during this time. Once you have all approvals, please proceed to obtain your permits as directed below.

Jurisdictions	Contact Information
<i>MOTI</i>	<ul style="list-style-type: none"> <li>• Apply by phone at 1 800 559-9688</li> </ul>