

Memo

PGL File #: 0346-65.01

DATE: July 28, 2023

TO: FrontCounter BC

FROM: Stewart Brown, R.P.Bio., P.Ag.

Re: Change Approval Application Number 100403050 for Kenyon Creek and

Flume Creek Culvert and Bank Stabilization Works

PGL Environmental Consultants (PGL) previously submitted a Change Approval application for Changes In and About a Stream (Tracking Number 100403050) on behalf of the Ministry of Transportation and Infrastructure (MOTI) for permanent culvert replacement and stream bank stabilization works at three roadway stream crossing sites (Table A) within the Sunshine Coast Regional District (SCRD) in response to widespread flooding from an atmospheric rain event in November 2021. The sites include:

- Where Kenyon Creek crosses under Redrooffs Road;
- Where Flume Creek crosses under Margaret Road; and
- Where Flume Creek crosses Beach Avenue.

Table A: Road Names (Site Names), Stream Names, Municipality within the SCRD, and Site Coordinates

Road Name (Site Name)	Stream Name	Location within SCRD	Site Coordinates			
Redrooffs Road	Kenyon Creek	Sechelt, BC	Lat: 49.4803320			
	Reliyon Creek	Secret, BC	Long: -123.8554920			
Margaret Road	Flume Creek	Robert's Creek, BC	Lat: 49.4314860			
	Fluille Creek	Robert's Creek, BC	Long: -123.6693050			
Beach Avenue	Flume Creek	Robert's Creek, BC	Lat: 49.4314860			
	Fluine Creek	Robert's Creek, BC	Long: -123.6693050			

Permanent instream works were initially scheduled for the 2023 least-risk window but have been postponed until 2024. Urban Systems Ltd. (Urban) conducted site inspections on June 5, 2023, for the MOTI to assess current instream and infrastructure conditions at each crossing location and determine whether additional works would be required to reduce the risk of additional damage to infrastructure or wash-out during the winter and spring of 2023/2024 prior to the completion of permanent repair works in the fall of 2024. If the inspection found there were vulnerabilities, Urban determined the nature of "Phase 1" works to be required. Urban's findings are summarized in the following memos and included in Appendix 1:

- Urban Systems Ltd. July 24, 2023. Memorandum: Project 14009 Sunshine Coast DFAA Kenyon Creek Phase 1 Work: and
- Urban Systems Ltd. July 24, 2023. Memorandum: Project 14005 Sunshine Coast DFAA Flume Creek -Phase 1 Work.

July 28, 2023 PGL File: 0346-65.01

Urban identified risks and vulnerabilities to roadway and drainage components of the sites which require interim measures to be completed in the 2023 least-risk window (Appendix 1).

Phase 1 works will occur within the project footprint of the previously submitted Change Approval application (Appendix 2) except for the proposed riprap spillway located on the eastern edge of the project area on Redrooffs Road. Both proposed spillways will be constructed above the high-water mark on the existing gravel shoulder and will not require any vegetation removal.

Works have been summarized in Phase 1 (2023) and Phase 2 (2024) for each crossing for your reference.

#### 1.1 Redrooffs Road Scope of Work

#### 1.1.1 Redrooffs Phase 1 (2023)

Phase 1 Redrooffs Road design includes the following scope of work:

Install 10kg riprap spillway underlain with geotextile in the location of the existing localized erosion. Exact
extents to be determined while in the field.

#### 1.1.2 Redrooffs Phase 2 (2024)

The permanent Redrooffs Road design includes the following scope of work:

- Removing the five temporary culverts installed under emergency works during the flooding event;
- Installing two, 35m-long, concrete, square box culverts side-by-side (two-barrel culvert crossing) one 2.4m width x 2.4m height, the other 2.1m width x 2.1m height complete with fish baffle design (refer to appended civil engineering drawings);
- Installing one, 13m-long, 0.90m-diameter HDPE culvert;
- Installing 50kg Class (550mm thickness) riprap aprons (armoring) at the culvert inlets and outlets (6m length riprap armoring at inlets, and 12m-long armoring at outlets) on top of 150mm-thickness, medium-weight, non-woven geotextile fabric (keyed into ground);
- Regrading embankments and repaving Redrooffs Road according to finalized civil engineering drawings;
- Removing trees determined likely to fail, as described in the Arborist Summary Report; and
- Seeding and/or planting any disturbed vegetated areas from construction works and restoration areas.

#### 1.2 Margaret Road Scope of Work

#### 1.2.1 Margaret Road Phase 1 (2023)

Interim Margaret Road design includes the following scope of work:

• Cleaning out the existing culvert at Margaret Road intersection, which is plugged with granular material.

#### 1.2.2 Margaret Road Phase 2 (2024)

The proposed permanent design scope of work at Margaret Road includes:

- Removing accumulated debris and gravel/sand substrate that may have accumulated at the culvert inlets/outlets during the atmospheric river event;
- Removing the three temporary CSP culverts at Margaret Road, which were installed under emergency works;
- Installing two side-by-side (double-barrel) concrete box culverts (both culverts 12.5m-long, one barrel 2.7m wide and 1.5m high, the other barrel 2.1m wide and 1.2m high), complete with a concrete headwall, and fish baffles (spacing of fish baffles is TBD);
- Clearing and grubbing (minor vegetation removal) at culvert inlets/outlets and along the road edges to accommodate the riprap armouring and road/driveway rebuilding;



July 28, 2023 PGL File: 0346-65.01

- Stripping surface material and installing non-woven geotextile fabric to be covered by 450mm-thick class 25kg riprap armouring at the inlet and outlet (67m<sup>2</sup> of riprap at the inlet, and 95m<sup>2</sup> at the outlet);
- Excavating, stripping, rebuilding, grading, and paving an approximately 90m-long section of Margaret Road;
- Minor regrading of a residential driveway off Margaret Road; and
- Seeding and/or planting any disturbed vegetated areas from construction works and restoration areas.

#### 1.3 Beach Avenue Scope of Work

#### 1.3.1 Beach Avenue Phase 1 (2023)

The proposed design scope of work at Beach Avenue includes:

- Cleaning out the existing culvert at Beach Avenue intersection;
- Removing the gravel bar and realigning thalweg of Flume Creek to align with the center of the culvert crossings.
   This includes retaining and reusing existing channel gravels to restore the creek bed upon removal of the gravel bar:
- Trimming the existing most westerly culvert back to match other culverts, approximately 1.0–1.5m. Riprap may need to be adjusted because of this;
- Installing a bentonite clay cut-off wall below Beach Avenue culvert crossings to minimize the waterflow that bypasses the culverts. This involves excavating below the culvert and up to halfway up the side of the culverts, and then placing a blended bentonite clay in sandbags below the culvert inlets to seal water flow; and
- Backfilling the excavation with bedding material that was removed. If clay and sandbags are exposed with the
  potential to be damaged by debris, placing riprap to protect the bags is recommended.

#### 1.3.2 Beach Avenue Phase 2 (2024)

The proposed permanent design scope of work at Beach Avenue includes:

- Removing accumulated debris and gravel/sand substrate that may have accumulated at the culvert inlets/outlets during the atmospheric river event;
- Removing the four temporary CSP culverts, which were installed under emergency works;
- Installing two side-by-side (double-barrel) concrete box culverts (both 13m-long, one barrel 2.1m wide and 1.2m wide, the second barrel with a width of 2.7m and height of 1.5m), complete with a concrete headwall and fish baffles (spacing of fish baffles is TBD);
- Clearing and grubbing (minor vegetation removal) at culvert inlets/outlets and along the road edges to accommodate the riprap armouring and road rebuilding;
- Stripping surface material and installing non-woven geotextile fabric to be covered by 450mm-thick class 25kg riprap armouring at the inlet and outlet;
- Excavating, stripping, rebuilding, grading, and paving an approximately 60m-long section of Beach Avenue;
- Seeding and/or planting any disturbed vegetated areas from construction works.

## 1.4 FISH AND FISH HABITAT PROTECTION MEASURES AND BEST MANAGEMENT PRACTICES FOR INSTREAM WORKS

Phase 1 works will be subject to the same environmental mitigation measures as already provided as part of the original application package to the Ministry of Forests detailed in PGL's March 17, 2023, Supplementary Information to Support Change Approval Application Number 100403050 for Kenyon Creek and Flume Creek Culvert and Bank Stabilization Works and summarized below for Phase 1 instream works to avoid contravention of the Fisheries Act.



July 28, 2023 PGL File: 0346-65.01

Environmental Mitigation Measure Required for Phase 1 Works	Document Section Reference (where the relevant mitigation has already been provided in previous application package)
Erosion and Sediment Control	<ul> <li>Appendix 5 of March 17, 2023, Supplementary Information document (MOTI's Sunshine Coast Construction Environmental Management Plan)</li> <li>Section 5 of March 17, 2023, Supplementary Information document</li> </ul>
Protection of Riparian Zone	Section 5 of March 17, 2023, Supplementary Information document
Instream Work Area Isolation	<ul> <li>DFO Code of practice for temp diversion channel</li> <li>Section 5 of March 17, 2023, Supplementary Information document</li> </ul>
Spill Response	<ul> <li>Emergency Spill Response Plan provided within the Construction Environmental Management Plan of March 17, 2023, Supplementary Information document (MOTI's Sunshine Coast Construction Environmental Management Plan)</li> <li>Section 5 of March 17, 2023, Supplementary Information document</li> </ul>

#### STATEMENT OF LIMITATIONS AND CONDITIONS FOR REPORT

#### **Complete Report**

All documents, records, data and files, whether electronic or otherwise, generated as part of this assignment are a part of the Report, which is of a summary nature and is not intended to stand alone without reference to the instructions given to PGL by the Client, communications between PGL and the Client, and any other reports, proposals or documents prepared by PGL for the Client relative to the specific site described herein, all of which together constitute the Report.

In order to properly understand the suggestions, recommendations and opinions expressed herein, reference must be made to the whole of the Report. **PGL** is not responsible for use by any part of portions of the Report without reference to the whole report.

#### **Basis of Report**

The Report has been prepared for the specific site and purposes that are set out in the contract between PGL and the Client. The findings, recommendations, suggestions, or opinions expressed in the Report are only applicable to the site and purposes in relation to which the Report is expressly provided, and then only to the extent that there has been no material alteration to or variation from the information provided or available to PGL.

#### **Use of the Report**

The information and opinions expressed in the Report, or any document forming part of the Report, are for the sole benefit of the Client. No other party may use or rely upon the Report or any portion thereof without PGL's written consent, and such use shall be on terms and conditions as PGL may expressly approve. Ownership in and copyright for the contents of the Report belong to PGL. Any use which a third party makes of the Report, is the sole responsibility of such third party. **PGL accepts no responsibility whatsoever for damages suffered by any third party resulting from use of the Report.** 

#### **CLOSING**

We trust that this meets your needs. If you have any questions or require clarification, please contact Stewart Brown or Bruce Nidle at 604-895-7612 and 604-895-7609, respectively.

Attachments: Appendix 1 – Phase 1 Work Memos (Urban Systems Ltd.)

Appendix 2 – Environmental Permit Submissions



Appendix 1

Phase 1 Work Memos (Urban Systems Ltd.)



# <u>MEMORANDUM</u>



DATE July 20, 2023 FROM Cody Bagg, P.Eng.
TO Stacie Crane FILE 1961.0480.15

CC Michael Braun SUBJECT Project 14009 - Sunshine Coast DFAA – Kenyon

Gundula Brigl Creek – Phase 1 Work

#### 1.0 BACKGROUND

On June 5<sup>th</sup>, 2023, Urban Systems Ltd. (Urban), conducted a site inspection for the BC Ministry of Transportation and Infrastructure (MOTI) on the Sunshine Coast DFAA – Kenyon Creek project which is located where Kenyon Creek crosses Redrooffs Road. The purpose of the site inspection was to assess the risks and vulnerabilities of roadway design as well as the drainage components of the site relating to postponement of the permanent replacement of the temporary culverts which had been installed in response to the atmospheric river events in November 2021. In addition to the site inspection, Urban was requested to provide recommendations to mitigate the risks and vulnerabilities that were identified on site. While there is overlap, the recommendations have been broken down into three categories: Roadway, Drainage, and Maintenance.

#### 2.0 SITE OBSERVATIONS

Attendance: Cody Bagg (Urban), Sam Roosma (Urban), Tim Barnes (MOTI), Eric Corrigan (Stantec)

#### Site Photos:



Figure 1: Kenyon Creek - Inlet



Figure 2: Kenyon Creek – Upstream

SUBJECT Project 14009 - Sunshine Coast DFAA - Kenyon Creek - Phase 1 Work

PAGE 2 of 5





Figure 3: Kenyon Creek - Outlet



Figure 4: Kenyon Creek - Downstream



Figure 5: Redrooffs Rd – Looking west from culvert crossing




Figure 6: - Redrooffs Rd – Looking east from culvert crossing



Figure 7: Redrooffs Rd – Looking west towards culvert crossing



Figure 8: Redrooffs Rd – Looking east towards culvert crossing



PAGE 3 of 5



#### Site Notes:

- Site appeared to be in similar condition as previous site visit.
- Temporary traffic pylons were in place on both sides of the roadway.
- Temporary paint markings were in place. Slight offset at the eastern tie in.
- Existing paint markings outside of project limits are worn out and faded.
- Small amounts of shoulder erosion due to pavement runoff.
- No visible changes to drainage conditions within Kenyon Creek.
- Small amount of small diameter woody debris blocking culvert inlet. Removed by hand.
- Vehicle traffic was witnessed to be consistently exceeding the posted speed limit within the project zone.

#### 3.0 RECOMMENDATIONS

Below are the recommendations to minimize risk and address vulnerabilities with the existing roadway, drainage, and maintenance practices.

#### 3.1 ROADWAY

- To assist in the delineation of the shoulder, install flexible delineator posts on both sides of Redrooffs Road. Delineator posts to have white reflectors to drivers' right side and yellow reflectors to the left side.
- Install additional signage to notify motorists of the reduced lane width and/or speed limit. As per direction from the MOTI Traffic Representative, a W-026 sign is to be temporarily installed in each direction as motorists approach the project site.

#### 3.2 DRAINAGE

• Install 10kg riprap spillway underlain with geotextile at location of existing localized erosion. Exact extents to be determined in field. Location identified on attached schematic design drawings.

#### 3.3 MAINTAINENCE

• Increase the frequency of routine site inspections. Determining a specific frequency is difficult so a practical approach should be taken to determine the appropriate frequency. After prolonged rainfalls or high intensity storms, site inspections should be completed. Visual inspection of the inlet and outlet of the culvert should be completed. Ensure no debris is blocking or has the potential to block the culverts.

#### 4.0 CONCLUSION

I trust that the content of this memorandum satisfies your expectations and requirements. Please notify the undersigned of plans to implement these recommendations and if any issues are experienced at these sites until the permanent replacement can occur.

SUBJECT Project 14009 - Sunshine Coast DFAA – Kenyon Creek – Phase 1 Work

PAGE 4 of 5



Sincerely,

**URBAN SYSTEMS LTD** 



PERMIT TO PRACTICE
URBAN SYSTEMS LTD.
Signature
Date 2023-07-25
PERMIT NUMBER: 1000527
Engineers and Geoscientists BC
(EGBC)

Cody Bagg, P.Eng. Transportation Design Engineer

/cb

Enclosure

Appendix A – Schematic Design Drawings


 $file://usl.urban-systems.com/projects/Projects\_SUR/1961/0480/15/R-Reports-Studies-Documents/R1-Reports/Phase%201%20works/2023-06-12%20Kenyon%20Creek%20-%20Phase%201%20Works%20-%20DRAFT.docx$ 



PAGE 5 of 5



## APPENDIX A - SCHEMATIC DESIGN DRAWINGS



# **MEMORANDUM**



Cody Bagg, P.Eng. DATE July 24, 2023 FROM TO Stacie Crane FILE 1961.0480.14

CC Michael Braun SUBJECT Project 14005 - Sunshine Coast DFAA - Flume Gundula Brigl

Creek - Phase 1 Work

#### **BACKGROUND** 1.0

On June 5th, 2023, Urban Systems Ltd. (Urban), conducted a site inspection for the BC Ministry of Transportation and Infrastructure (MOTI) on the Sunshine Coast DFAA - Flume Creek project located at the Flume Creek crossings of Margaret Road and Beach Avenue. The purpose of the site inspection was to assess the risks and vulnerabilities of roadway design as well as the drainage components of the site relating to postponement of the permanent replacement of the temporary culverts which had been installed in response to the atmospheric river events in November 2021. In addition to the site inspection, Urban was requested to provide recommendations to mitigate the risks and vulnerabilities that were identified on site. While there is overlap, the recommendations have been broken down into three categories: Roadway, Drainage, and Maintenance.

#### 2.0 SITE OBSERVATIONS

Attendance: Cody Bagg (Urban), Sam Roosma (Urban), Tim Barnes (MOTI), Eric Corrigan (Stantec)



Figure 1: Margaret Rd Crossing - Inlet



Figure 2: Margaret Rd – Flume Creek Upstream

SUBJECT Project 14005 - Sunshine Coast DFAA - Flume Creek - Phase 1 Work

PAGE 2 of 7





Figure 3: Margaret Rd Crossing – Outlet



Figure 4: Margaret Rd – Flume Creek Downstream



Figure 5: Margaret Rd – Looking north



Figure 6: - Margaret Rd – Looking south



Figure 7: Beach Ave Crossing - Inlet



Figure 8: Beach Ave – Flume Creek Upstream

SUBJECT Project 14005 - Sunshine Coast DFAA - Flume Creek - Phase 1 Work

PAGE 3 of 7





Figure 9: Beach Ave Crossing - Outlet



Figure 10: Beach Ave – Flume Creek Downstream



Figure 11: Beach Ave – Culvert crossing



Figure 12: Margaret Rd – Northern driveway Inlet




Figure 13: Margaret Rd – Southern driveway outlet



Figure 14: Beach Ave and Margaret Rd Intersection
– Plugged culvert inlet

#### Margaret Road Culvert Crossing:

- Appeared to be in similar condition as previous site visits.
- Minor potholes in gravel surface.
- No signs of erosion or instability in either road structure or drainage channel.



PAGE 4 of 7



- Riprap appeared stable and operating as intended.
- Ditch along Margaret Rd was slightly incised but appeared stable.

#### Beach Ave Culvert Crossing:

- Culvert at intersection of Beach Avenue and Margaret Road is still plugged with granular material.
- Shoulder erosion in locations where size and placement of riprap created large voids.
- Water was seen piping under and between the eastern two culverts. A visible void all the way through the length of the two culverts. NOTE: It is difficult to determine if this has been the case since the installation of the temporary culverts. The culverts are side by side and are touching for the majority of the length. This would have made bedding and compaction impossible during construction.

#### 3.0 RECOMMENDATIONS

Below are the recommendations to minimize risk and address vulnerabilities with the existing roadway, drainage, and maintenance practices.

#### 3.1 ROADWAY

Temporarily pave existing gravel section of Beach Avenue and Margaret Road. An
extensive number of complaints have been received by MOTI District staff regarding
the condition of the roadways. A temporary asphalt patch will essentially eliminate the
complaints that the MOTI District staff must respond too. This temporary asphalt patch
will be kept in place until the construction of the permanent works are initiated.
(COMPLETED)

#### 3.2 DRAINAGE

- Clean out existing culvert at Margaret Road and Beach Avenue intersection. Culvert is plugged with granular material and is required to be flushed out. See Figure 14.
- Remove gravel bar and realign thalweg of Flume Creek to align with the center of the culvert crossings. Retain and stockpile removed gravels to be reused to restore the creek bed upon removal of gravel bar.



PAGE 5 of 7






Trim existing most westerly culvert back to match other culverts, approximately 1.0 1.5m. Riprap may need to be adjusted because of this.



• Install bentonite clay cut off wall below Beach Avenue culvert crossings to minimize the waterflow that bypasses the culverts. Excavate below the culvert and up to halfway up the side of the culverts. Place a blended bentonite clay in sandbags below the culvert inlets to seal water flow. Careful and deliberate placement of the bags ensure a good seal with the culverts. Backfill excavation with bedding material that was removed. If clay and sandbags are exposed with the potential to be damaged by debris, placing riprap to protect the bags is recommended.



PAGE 6 of 7





#### 3.3 MAINTAINENCE

- Increase the frequency of routine site inspections. Determining a specific frequency is difficult so a practical approach should be taken to determine the appropriate frequency. After prolonged rainfalls or high intensity storms, site inspections should be completed. Visual inspection of the inlet and outlet of each culvert should be completed. Ensure no debris is blocking or has the potential to block the culverts.
- Periodically inspect the proposed clay plug/cut off wall for signs of erosion and/or piping. Ensure complete seal around culverts.
- Repair roadway shoulders if erosion occurs. Minor patching of the shoulders may be required to ensure the roadway width is maximized.

#### 4.0 CONCLUSION

I trust that the content of this memorandum satisfies your expectations and requirements. Please notify the undersigned of plans to implement these recommendations and if any issues are experienced at these sites until the permanent replacement can occur.

Sincerely,

**URBAN SYSTEMS LTD.** 



Cody Bagg, P.Eng.
Transportation Design Engineer

/cb Enclosure Appendix A: Schematic Design Drawings

PAGE


7 of 7




SUBJECT Project 14005 - Sunshine Coast DFAA - Flume Creek - Phase 1 Work



## APPENDIX A - SCHEMATIC DESIGN DRAWINGS





#### Appendix 2

**Environmental Permit Submissions** 









# Ministry of Transportation and Infrastructure

PROJECT NO. 14009

# KENYON CREEK DFAA FLOOD DAMAGE ENVIRONMENTAL PERMITS

STA. 101+35.000 - STA. 102+41.000

0.106 km


N: 481210.983, E: 438013.044

GRADING AND DRAINAGE CONTRACT

# DRAWING INDEX

R1-1028-001 KEY PLAN R1-1028-002 LEGEND R1-1028-101 PLAN

R1-1028-701 DRAINAGE AND DETAILS



**KEY PLAN** 

URBAN SYSTEMS

DRAWING NUMBER RE

# LEGEND

# SYMBOLS (EXISTING)

SECTION LINE / DISTRICT LOT

1/4 SECTION BOUNDARY

LOT BOUNDARY

**EASEMENTS** 

# LINE TYPES (EXISTING)

# SYMBOLS (PROPOSED)

UTILITY PEDESTAL

TRAFFIC SIGNAL

TRAFFIC SIGNAL CONTROLLER

UNDERGROUND ELECTRICAL TRANSFORMER

# LINE TYPES (PROPOSED)

**FEATURES** 

AERIAL UTILITIES		DRAINAGE & UTILITIES			MAN-MADE FEATURES
POWER POLE	-	CULVERT OUTLET	— co	RAILWAY TRACKS	
POWER POLE WITH TRANSFORMER	<del></del>	SANITARY MANHOLE	<b>⊘</b> MH San	RAILWAY BALLAST	
POWER / TELEPHONE POLE WITH TRANSFORMER	<del></del>	UTILITY MANHOLE	MH     Vault	ROAD MARKING - YELLOW	
POWER GUY POLE	•-	WATER MANHOLE		ROAD MARKING - WHITE	
POWER / TELEPHONE POLE	-	MANHOLE UNKNOWN	MH     Unk	ROAD MARKING - BROKEN	
POWER / TELEPHONE GUY POLE	<b>—</b>			CROSSWALK	
ANCHOR OR GUY WIRE	$\rightarrow$	ELECTRICAL		STOP LINE	
DEADMAN	○-∋	JUNCTION BOX	<sub>o</sub> JB	EDGE OF ROAD - PAVED	
TELEPHONE POLE	-0-	UTILITY VAULT	□ JB	EDGE OF ROAD GRAVEL	
TELEPHONE GUY POLE	0-	LAMP STANDARD	OLS	GRAVEL SHOULDER	
HIGH TENSION POLE	-0-	UTILITY KIOSK	K	DIRT ROAD	
HIGH TENSION TOWER	-HT)-	UTILITY PEDESTAL	_ PED	GRAVEL ROAD	
UTILITY POLE	OUP	TRAFFIC COUNTER	0	EDGE OF GRAVEL	
SURVEY		TRAFFIC SIGNAL	$\Diamond$	SIDEWALK	
		TRAFFIC SIGNAL CONTROLLER	$\overline{\mathbb{W}}$	CONCRETE PAD	
CONTROL MONUMENT	•			FENCE	X
CONTROL MONUMENT	♠ MON	METERS		TOP OF CURB	
LEGAL MONUMENT	OIP	VALVE	$\otimes^{V}$	CL OF GUTTER	
STANDARD IRON PIN FOUND	CIP OIP	WATER VALVE	$\otimes^{WV}$	CONCRETE ROAD BARRIER	
CAPPED IRON PIN	_	WATER METER	$\otimes^{WM}$	TOP OF FILL	
LEAD PLUG	<b>=</b>	FIRE HYDRANT	⊗FH	RIP RAP	
BENCHMARK	X	WELL	0	BUILDING	
SPOT ELEVATION	+	STANDPIPE / WATER BLOW OFF	⊗SD	TREE LINE	
GEOTECHNICAL		AIR VALVE	⊗AIR	LAWN LINE	
TESTPIT	M	GAS VALVE	⊗ <sup>GV</sup>		
TESTHOLE	$oldsymbol{eta}^{TH}$	SERVICE METER	⊗SV		HYDRAULIC
OBSERVATION WELL	◆ <sup>ow</sup>	UNDERGROUND		CULVERT	
DETAIL		VENT/BREATHER PIPE	○ BP	DITCH CENTER	
	• GP		OFC	DITCH EDGE	
GATE POST	□ MB	FILLER CAP	<sub>a</sub> FP	CENTER OF CREEK	
MAILBOX OLD POST	O Post	FUEL / GAS PUMP FUEL TANK	FT	HIGH WATER	——————————————————————————————————————
DELINEATOR POST	_ DP	SEPTIC TANK	_ST	EDGE OF WATER	EW EW
FLAGPOLE	o FP		⊚UM	HIGH WATER MARK (EXTREME)	
DECORATIVE TREE		UNDERGROUND MARKER (MISC) IRRIGATION JUNCTION BOX	_ IJ	SEEPAGE LINE	
TREE	$\bigvee$		OIS		TOPOGRAPHY
PILING	Piling	IRRIGATION SPRINKLER HEAD	0.5	BASE OF SLOPE	
CONCRETE PILLAR	0	ROAD SIGNS		MARSH	
WELL	0	STANDARD SIGN	þ	TOP OF ROCK	
	<u> </u>	COMMERCIAL SIGN	$\bigvee^{\wedge}$	SLIDE	
SWAMP DIRECTIONAL ARROW	<del></del>	SIGN BRIDGE STRUCTURE		TALUS	
DIRECTIONAL ARROW		CANTILEVER STRUCTURE		TRAIL	
DRAINAGE & UTILITIES		TWO POST SIGN	0 0	TOP OF SLOPE	
STORM MANHOLE	MH Storm	TWO POST SIGN (BREAKAWAY)			
STANDARD CATCH BASIN		STANDARD DAVIT POLE - TYPE 3			UTILITIES
ROUND CATCH BASIN		STANDARD COMBINATION POLE - TYPE 1		OVERHEAD UTILITY	
DRYWELL	MH/CB Drywell	HEAVY DUTY DAVIT POLE - TYPE 6		PIPELINE (GAS)	
CB MANHOLE		HEAVY DUTY COMBINATION POLE - TYPE 7		UG ELECTRIC	UE
CULVERT INLET	— CI	HEAVY POLE - TYPE H		UG COMMUNICATION	UT
		HEAVY COMBINATION POLE - TYPE H	<u></u>	STORM SEWER	s
				SANITARY SEWER	——————————————————————————————————————
— — ·	/DEC /E	VIOTINO)		WATER MAIN	w
LINE IY	YES (E	XISTING)		MISCELLANEOUS UNDERGROUND	UG
LO	T BOUNDA	RIES		ONDEIVOIVOUND	

AERIAL UTILITIES	30L0 (1 1 t	01 002
POWER POLE	-	VALVE
POWER POLE WITH TRANSFORMER	<del></del>	WATER VA
POWER / TELEPHONE POLE WITH	<del>-</del>	WATER ME
TRANSFORMER POWER GUY POLE	•	FIRE HYDF
POWER / TELEPHONE POLE	<del></del>	STANDPIP
POWER / TELEPHONE GUY POLE	<del>-</del>	AIR VALVE
ANCHOR OR GUY WIRE	$\rightarrow$	GAS VALV
DEADMAN	0-→	SERVICE N
TELEPHONE POLE	-0-	
TELEPHONE GUY POLE	0-	ι
HIGH TENSION POLE	-0-	VENT/BRE
HIGH TENSION TOWER	-HTT-	FILLER CA
DETAIL		FUEL / GAS
	0.0	FUEL TANI
GATE POST	• GP	SEPTIC TA
MAILBOX	□ MB	UNDERGR
POST	OPost	
POST MOUNTED DELINEATOR	<sub>o</sub> DP	STANDARI
FLAGPOLE	OFP	BARRIER I
DIRECTIONAL ARROW		RELOCATE
DRAINAGE & UTILITIES		TWO POST
MANHOLE		TWO POST
STORM MANHOLE	MH Storm	STANDARI
STANDARD CATCH BASIN		STANDARI POLE - TYF
VARIABLE DEPTH CATCH BASIN		HEAVY DU
SPILLWAY		HEAVY DU POLE - TYI
HEADWALL	$\smile$	HEAVY PO
DRYWELL	MH/CB Drywell	HEAVY CO POLE - TYF
TELEPHONE MANHOLE	MH Tel	CANTILEVI
POWER MANHOLE	MH Power	SIGN BRID
SANITARY MANHOLE	MH San	
UTILITY MANHOLE	MH Vault	
WATER MANHOLE	MH Water	PAVEMEN <sup>-</sup>
MANHOLE UNKNOWN	MH Unk	RIPRAP
ELECTRICAL		RIGID INSU
JUNCTION BOX	<sub>o</sub> JB	
UTILITY VAULT	<sub>o</sub> JB	REMO
LAMP STANDARD		POWER PC
UTILITY KIOSK	K	TELEPHON

METERS		
'ALVE	$\otimes^{V}$	HIGH
VATER VALVE	⊗WV	MINO
VATER METER	⊗WM	CLEA
IRE HYDRANT	⊗FH	PAVE
STANDPIPE / WATER BLOW (	OFF ⊗ <sup>SD</sup>	SHOU
IR VALVE	$\otimes^{AIR}$	CURB
SAS VALVE	⊗GV	RAISE
SERVICE METER	⊗SV	SAWC
UNDERGROUI	ND	RUMB
'ENT/BREATHER PIPE	OBP	RETA
ILLER CAP	OFC	FENC TOP C
UEL / GAS PUMP	□ FP	BOTT
UEL TANK	<b>S</b> FT	100mn PAINT
SEPTIC TANK	ST	100mn PAINT
JNDERGROUND MARKER (M	IISC) ⊚ <sup>UM</sup>	100mn PAINT
ROAD SIGNS	3	100mn PAINT
STANDARD SIGN	þ	CONC
SARRIER MOUNTED DELINE	ATOR •	DITCH ADDIT
RELOCATED OVERHEAD SIG	6N <u> </u>	DITCH
WO POST SIGN	0 0	
WO POST SIGN (BREAKAWA	AY)	
STANDARD DAVIT POLE - TY STANDARD COMBINATION POLE - TYPE 1	PE 3	RIGHT TEMP TO CO
IEAVY DUTY DAVIT POLE - T IEAVY DUTY COMBINATION POLE - TYPE 7		
IEAVY POLE - TYPE H	<del></del>	OVER
IEAVY COMBINATION OLE - TYPE H	<del></del>	PIPEL
ANTILEVER STRUCTURE		SERV
IGN BRIDGE STRUCTURE	⊠	UG EL
PATTERNS		UG CC
AVEMENT REMOVAL		STOR
	k p <del>a p</del> a <del>pa p</del> a i	SUB C
RIPRAP		CULVI
IGID INSULATION FOAM		WATE
REMOVALS / RELO	CATES	MISCE UNDE
OWER POLE		
ELEPHONE POLE	$\bigcirc$	

HIGHWAY CONTROL LINE	100+00
MINOR CONTROL LINE	100+00
CLEARING AND GRUBBING	CL. & GR.
PAVEMENT EDGE	
SHOULDER EDGE	
CURB AND GUTTER	
RAISED ISLAND	
SAWCUT	
RUMBLE STRIP	·//·
RETAINING WALL	
FENCE	xx
TOP OF CUT /	CF
BOTTOM OF FILL (TOES) 100mm - YELLOW	
PAINT LINE (SOLID) 100mm - WHITE	
PAINT LINE (SOLID)	
100mm - CONTINUITY PAINT LINE (BROKEN)	<u> </u>
100mm - LANE PAINT LINE (BROKEN)	8 8
CONCRETE BARRIER	
DITCH CENTER /	
ADDITIONAL DITCHING DITCH EDGE	
	BOUNDARIES
RIGHT OF WAY	
TEMPORARY LICENCE TO CONSTRUCT	
TO CONSTRUCT	
	UTILITIES
OVERHEAD UTILITY	
PIPELINE (GAS)	—
SERVICE LINE (GAS)	
UG ELECTRIC	
UG COMMUNICATION	
STORM SEWER	—sss
	SD
SUB DRAIN	
SUB DRAIN CULVERT	
	SAN SAN
CULVERT	SAN SAN

NOTE:

APPROXIMATE HYDROVAC UTILITY LOCATE

HIGHWAY SIGNS

 $\Box^{\mathsf{XF}}$ 

NOT ALL SYMBOLS AND LINE TYPES
ILLUSTRATED IN THIS LEGEND ARE
UTILIZED IN THE FOLLOWING DESIGN

FOR ENVIRONMENTAL PERMITTING

	SC.	ALE	CAD FILENAME _ PLOT DATE _	R1-1028-000-ENVIRO 2023-03-01	BRITISH COLUMBIA
	REV	DATE	REVISIONS	NAME	
<b>URBAN</b>					
OT CA					CODY BAGG, P.ENG.
6 V 6 T F M 6					SENIOR DESIGNER
SYSTEMS					DATE

MINISTRY OF TRANSPORTATION
AND INFRASTRUCTURE
SOUTH COAST REGION
HIGHWAY ENGINEERING AND GEOMATICS

DESIGNED S.CAVASINNI DATE 2023-02-10
QUALITY CONTROL C.BAGG DATE 2023-02-10

PLAN


KENYON CREEK


DFAA FLOOD DAMAGE

DESIGNED S.CAVASINNI DATE 2023-02-10
QUALITY CONTROL C.BAGG DATE 2023-02-10
QUALITY ASSURANCE J.BORCH DATE 2023-02-10
DRAWN S.CAVASINNI DATE 2023-02-10

872CS1714

PROJECT NUMBER
PROJECT NUMBER
REG DRAWING NUMBER REV
14009
1 R1-1028-002-ENVIRO









Ministry of Transportation and Infrastructure

PROJECT NO. 14005

## DRAWING INDEX

R1-1027-001 R1-1027-002 R1-1027-101 to 102

R1-1027-701 to 703

PLAN DRAINAGE AND DETAILS

KEY PLAN LEGEND


# FLUME CREEK

# DFAA FLOOD DAMAGE ENVIRONMENTAL PERMITS

MARGARET RD: STA. 101+36.000 - STA. 102+25.000 (0.89 km) BEACH AVE: STA. 201+11.539 - STA. 201+70.693 (0.59 km)

N: 475613.652, E: 451469.172

# GRADING AND DRAINAGE CONTRACT



URBAN SYSTEMS

DRAWING NUMBER RE

# LEGEND

# SYMBOLS (EXISTING)

LOT BOUNDARIES

SECTION LINE / DISTRICT LOT

1/4 SECTION BOUNDARY

LOT BOUNDARY

**EASEMENTS** 

## LINE TYPES (EXISTING)

# SYMBOLS (PROPOSED)

# LINE TYPES (PROPOSED)

**FEATURES** 

<b>AERIAL UTILITIES</b>		DRAINAGE & UTILITIES	3		MAN-MADE FEATU	RES	
POWER POLE	•	CULVERT OUTLET	— co	RAILWAY TRACKS			
POWER POLE WITH TRANSFORMER	<del></del>	SANITARY MANHOLE	<b>⊘</b> MH San	RAILWAY BALLAST			
POWER / TELEPHONE POLE WITH TRANSFORMER	<del>-</del>	UTILITY MANHOLE	MH Vault	ROAD MARKING - YELLOW			
POWER GUY POLE	•-	WATER MANHOLE	MH Water	ROAD MARKING - WHITE			
POWER / TELEPHONE POLE	<del></del>	MANHOLE UNKNOWN		ROAD MARKING - BROKEN			
POWER / TELEPHONE GUY POLE	⊕—			CROSSWALK			
ANCHOR OR GUY WIRE	$\rightarrow$	ELECTRICAL		STOP LINE			
DEADMAN	○-∋	JUNCTION BOX	_ JB	EDGE OF ROAD - PAVED			
TELEPHONE POLE	<b>-</b>	UTILITY VAULT	<sub>o</sub> JB	EDGE OF ROAD GRAVEL			
TELEPHONE GUY POLE	0-	LAMP STANDARD	OLS	GRAVEL SHOULDER			
HIGH TENSION POLE	-0-	UTILITY KIOSK	K	DIRT ROAD			
HIGH TENSION TOWER	-HTI-	UTILITY PEDESTAL	_ PED	GRAVEL ROAD		<b>-</b> — — .	
UTILITY POLE	OUP	TRAFFIC COUNTER	0	EDGE OF GRAVEL			
		TRAFFIC SIGNAL	ightharpoons	SIDEWALK			
SURVEY		TRAFFIC SIGNAL CONTROLLER	_	CONCRETE PAD			
CONTROL POINT	Δ			FENCE	x	x	
CONTROL MONUMENT		METERS		TOP OF CURB			
LEGAL MONUMENT	<b>●</b> MON	VALVE	$\otimes^{V}$	CL OF GUTTER			
STANDARD IRON PIN FOUND	OIP	WATER VALVE	⊗WV	CONCRETE ROAD BARRIER			
CAPPED IRON PIN	CIP OIP	WATER METER	⊗WM	TOP OF FILL			
LEAD PLUG		FIRE HYDRANT	⊗FH	RIP RAP		-	
BENCHMARK	×	WELL	0	BUILDING			
SPOT ELEVATION	+	STANDPIPE / WATER BLOW OFF	— ⊗SD	TREE LINE		······································	~~~~~
GEOTECHNICAL		AIR VALVE	⊗ AIR	LAWN LINE			
TESTPIT	M	GAS VALVE	⊗ <sup>GV</sup>	LATTA LINE			
TESTHOLE	<b>⊕</b> ™	SERVICE METER	⊗SV		HYDRAULIC		
OBSERVATION WELL	<b>→</b> ow		0	CULVERT			
	Ψ	UNDERGROUND		DITCH CENTER			
DETAIL		VENT/BREATHER PIPE	OBP	DITCH EDGE		_ — — — — -	
GATE POST	• GP	FILLER CAP	OFC	CENTER OF CREEK			
MAILBOX	□ MB	FUEL / GAS PUMP	<sub>в</sub> FP	HIGH WATER	——— нwм ————————————————————————————————	—— нwм —————————————————————————————————	
OLD POST	OPost	FUEL TANK	FT	EDGE OF WATER	EW	EW	
DELINEATOR POST	_ DP	SEPTIC TANK	ST	HIGH WATER MARK (EXTREME)			
FLAGPOLE	o FP	UNDERGROUND MARKER (MISC)	⊚ UM	SEEPAGE LINE			
DECORATIVE TREE		IRRIGATION JUNCTION BOX	□ IJ		TOPOGRAPHY		
TREE	$\star$	IRRIGATION SPRINKLER HEAD	OIS		TOPOGNAFIII		
PILING	OPiling	ROAD SIGNS		BASE OF SLOPE			
CONCRETE PILLAR	0	STANDARD SIGN	Ь	MARSH			
WELL	0	COMMERCIAL SIGN	Δ	TOP OF ROCK			
SWAMP	<u> </u>		7	SLIDE			
DIRECTIONAL ARROW				TALUS			
DRAINAGE & UTILITIES		CANTILEVER STRUCTURE   TWO POST SIGN		TRAIL			
STORM MANHOLE	<b>⊘</b> MH Storm			TOP OF SLOPE			
		TWO POST SIGN (BREAKAWAY)			UTILITIES		
STANDARD CATCH BASIN		STANDARD DAVIT POLE - TYPE 3 STANDARD COMBINATION		0	UTILITILU		
ROUND CATCH BASIN	MH/CB	POLE - TYPE 1		OVERHEAD UTILITY			
DRYWELL CR MANUALE	MH/CB Drywell	HEAVY DUTY DAVIT POLE - TYPE 6 HEAVY DUTY COMBINATION		PIPELINE (GAS)	G	G	
CB MANHOLE	. CI	POLE - TYPE 7		UG ELECTRIC	——— UE ———	—— UE ——— ——	
CULVERT INLET	— cı	HEAVY POLE - TYPE H HEAVY COMBINATION	<u></u>	UG COMMUNICATION	——— UT ————	UT	
		POLE - TYPE H	<del></del>	STORM SEWER		s	
				SANITARY SEWER	SAN	SAN	
I INIE TV	/PEQ /E	XISTING)		WATER MAIN			
LINE I I	1 L3 (E	AIOTING)		MISCELLANEOUS UNDERGROUND	UG	—— UG ——— —	

AERIAL UTILITIES		METERS	
POWER POLE	-	VALVE	⊗V
POWER POLE WITH TRANSFORMER	<del></del>	WATER VALVE	⊗WV
POWER / TELEPHONE POLE WITH TRANSFORMER	<del></del>	WATER METER	$\otimes^{WM}$
POWER GUY POLE	•-	FIRE HYDRANT	⊗FH
POWER / TELEPHONE POLE	<del></del>	STANDPIPE / WATER BLOW OFF	⊗SD
POWER / TELEPHONE GUY POLE	<b>-</b>	AIR VALVE	$\otimes^{AIR}$
ANCHOR OR GUY WIRE	$\rightarrow$	GAS VALVE	⊗GV
DEADMAN	0-→	SERVICE METER	⊗SV
TELEPHONE POLE	-0-	UNDERGROUND	
TELEPHONE GUY POLE	<b>O</b> —		ОВР
HIGH TENSION POLE	-0-	VENT/BREATHER PIPE	OFC
HIGH TENSION TOWER	-HTI-	FILLER CAP	<sub>a</sub> FP
DETAIL		FUEL / GAS PUMP	FT
	• GP	FUEL TANK	_ST
GATE POST	⊕ MB	SEPTIC TANK	
MAILBOX	OPost	UNDERGROUND MARKER (MISC)	) <u>@</u>
POST MOUNTED DELINEATOR	_ DP	ROAD SIGNS	
POST MOUNTED DELINEATOR FLAGPOLE	OFP	STANDARD SIGN	þ
DIRECTIONAL ARROW	<b>O</b>	BARRIER MOUNTED DELINEATO	R •
DIRECTIONAL ARROW	***	RELOCATED OVERHEAD SIGN	
DRAINAGE & UTILITIES	8	TWO POST SIGN	0 0
MANHOLE		TWO POST SIGN (BREAKAWAY)	
STORM MANHOLE	MH Storm	STANDARD DAVIT POLE - TYPE 3	
STANDARD CATCH BASIN		STANDARD COMBINATION POLE - TYPE 1	
VARIABLE DEPTH CATCH BASIN		HEAVY DUTY DAVIT POLE - TYPE	E 6 <u></u> —≪
SPILLWAY		HEAVY DUTY COMBINATION POLE - TYPE 7	
HEADWALL	$\smile$	HEAVY POLE - TYPE H	<del></del>
DRYWELL	MH/CB Drywell	HEAVY COMBINATION POLE - TYPE H	<b>─</b>
TELEPHONE MANHOLE	MH Tel	CANTILEVER STRUCTURE	<u></u> ⊠
POWER MANHOLE	MH Power	SIGN BRIDGE STRUCTURE	⊠
SANITARY MANHOLE	MH San	PATTERNS	
UTILITY MANHOLE	MH Vault	LEVELLING COURSE	
WATER MANHOLE	MH Water	LEVELLING GOORGE	
MANHOLE UNKNOWN	MH Unk	PAVEMENT REMOVAL	
ELECTRICAL		RIPRAP	
JUNCTION BOX	<sub>o</sub> JB	THE DEINFORGEMENT	
UTILITY VAULT	<sub>o</sub> JB	TURF REINFORCEMENT FOR MATTING	
LAMP STANDARD			TEQ
UTILITY KIOSK	K	REMOVALS / RELOCA	.TES
UTILITY PEDESTAL	ped	POWER POLE	

HIGHWAY CONTROL LINE 100+00 MINOR CONTROL LINE CL. & GR. CLEARING AND GRUBBING PAVEMENT EDGE SHOULDER EDGE **CURB AND GUTTER** RAISED ISLAND SAWCUT RUMBLE STRIP **^** RETAINING WALL **FENCE** TOP OF CUT / BOTTOM OF FILL (TOES) 100mm - YELLOW PAINT LINE (SOLID) 100mm - WHITE PAINT LINE (SOLID) 100mm - CONTINUITY PAINT LINE (BROKEN) 100mm - LANE PAINT LINE (BROKEN) CONCRETE BARRIER .\_\_\_\_\_. DITCH CENTER / ADDITIONAL DITCHING DITCH EDGE BOUNDARIES RIGHT OF WAY T.L.T.C. TEMPORARY LICENCE TO CONSTRUCT UTILITIES OVERHEAD UTILITY PIPELINE (GAS) SERVICE LINE (GAS) UG ELECTRIC UG COMMUNICATION STORM SEWER SUB DRAIN CULVERT SANITARY SEWER WATER MAIN MISCELLANEOUS UNDERGROUND

NOTE:

TELEPHONE POLE

HIGHWAY SIGNS

NOT ALL SYMBOLS AND LINE TYPES ILLUSTRATED IN THIS LEGEND ARE UTILIZED IN THE FOLLOWING DESIGN FOR ENVIRONMENTAL PERMITTING

SYSTEMS

	SC	ALE	CAD FILENAME _ PLOT DATE _	R1-1027-000-ENVIRO 2023-03-02	
	REV	DATE	REVISIONS	NAME	
JRBAN					
					CODY BAGG, P.ENG. SENIOR DESIGNER
	-				1

TRAFFIC SIGNAL

UNDERGROUND

TRAFFIC SIGNAL CONTROLLER

ELECTRICAL TRANSFORMER

MINISTRY OF TRANSPORTATION AND INFRASTRUCTURE COLUMBIA SOUTH COAST REGION HIGHWAY ENGINEERING AND GEOMATICS

DESIGNED S.CAVASINNI DATE 2023-03-02


QUALITY CONTROL C.BAGG DATE 2023-03-02


DRAWN E.PROULX DATE 2023-03-02


QUALITY ASSURANCE J.BORCH DATE 2023-03-02


PLAN FLUME CREEK DFAA FLOOD DAMAGE


FILE NUMBER DRAWING NUMBER 1 R1-1027-002-ENVIRQ 872CS1714 14005



























# FOR ENVIRONMENTAL PERMITTING

RECTANGULAR NOTCH IN BAFFLE




PEDESTRIAN FENCING. SEE SP741-07.01


PROPOSED SHOULDER

AT BACK OF HEADWALL

ORIGINAL GROUND

D25 CULVERT







PERMIT TO PRACTICE URBAN SYSTEMS LTD. Date 2023-03-03 PERMIT NUMBER: 1000527

DRAWING NUMBER 1 R1-1027-704-ENVIRQ

# FOR ENVIRONMENTAL PERMITTING

	SCALE 0 0.5 1:50 2.5m  REV DATE REVISIONS	CAD FILENAME <u>R1-1027-700-E</u> PLOT DATE <u>202:</u> NAME	1-03-02 COLUMBI	A AND IN	MINISTRY OF TRANSPORTATION AND INFRASTRUCTURE SOUTH COAST REGION HIGHWAY ENGINEERING AND GEOMATICS			MARGARET ROAD PLUNGE POOL  FLUME CREEK DFAA FLOOD DAMAGE					
URBAN					CODY BAGG, P.ENG. SENIOR DESIGNER			INNI DATE 2023-03-02 AGG DATE 2023-03-02 RCH DATE 2023-03-02	FII F NUMBER	PROJECT NUMBER	REG	DRAWING	3 NUMBE
SYSTEMS					DATE			ULX DATE2023-03-02	872CS1714	14005	1	R1-1027-70	)4-Е