



**GENERAL NOTES**

Precast concrete shall be exposure Class S and meet min compressive strength of 35MPa

Cement: Type GU  
 Air Category: 4.0% - 7.0%  
 Aggregate: CSA/CAN A23.4 Maximum Size: 20mm  
 Admixtures: CSA/CAN A23.4  
 Reinforcing: Grade 400W CSA G30.18-09  
 Inserts/Embeds: As noted in drawing details

Manufacture of precast concrete units shall be in accordance with specification CSA A23.4

**\*\* LEKO PRECAST LTD SHALL NOT BE RESPONSIBLE FOR ANY INSTALLATION PRACTICES FOLLOWED ON-SITE UNLESS PERFORMED BY LEKO PRECAST LTD \*\***

11,250Kg (24,800 LBS)



**I1226B - BOX CULVERT HEADWALL**

DRAWN BY: JA	CHECKED BY:	APPROVED BY:	DATE: SEPT 2021
ASSEMBLY DWG.	PREVIOUS DWG.	DRAWING NO. I1226B	REVISION 0
SCALE: 1:75 ISOMETRIC: N/A			
DO NOT SCALE THIS DRAWING			