



Ministry of Transportation

TEST PIT / HOLE SUMMARY SHEET

Pit: **Raven Pit** Contract Area: **North Island - 3** Equipment: **Sonic Drill** Date: **March 15, 2016**

Test Hole Number	Layer Thickness (m)	Layer Top Elevation (m)	Layer Bottom Elevation (m)	Soil Classification	Gradation of Materials							Soundness Indicator					Density	Absorption	Water Table Elevation (m)	Remarks	Bag #				
					Gravel	Sand	Fines	75-150 mm	150-300 mm	> 300 mm	Maximum Size (mm)	Fracture		Micro Duval		Sand Eq.						MgSO4			
												A (%)	B (%)	C (%)	F (%)							C (%)	F (%)	C (%)	F (%)
16-1	1.5		-1.5	GW	58	39	3	>1			75											5.5	UTM 349066E 5506918N; Clay coating on gravel; WSA	791	
	1.5	-1.5	-3.0	SM1	35	52	13	>1			75											2.74 on 14/04/16	WSA	792	
	1.0			GP	42	56	2	>1			50													Medium sand; WSA	793
	1.0			SP																					
	0.5			SM1	0	72	28																	Finer sand; WSA	794
	1.5			SM2																					
16-2	2.5			SP	44	54	2	>1			50											1.96 on 14/04/16	UTM 349095E 5506759N; As per TH16-07; WSA	795	
	0.7			GP	54	41	5	>1			50													WSA	796
	1.7			SM2	0	75	25																	blue silt/clay; Screen 12"-17" plug 11"; Hydrometer and Attiberg Limit tests done	plastic bag #1
	2.1			CL	0	2	98																		
16-3	4.0			GP	66	30	4	>1			50												2.55 on 14/04/16	UTM 348967E 5506841N; Pushed rock (short sample); WSA	797
	1.5			SM2	4	76	20																	silty sand; WSA	798
	1.5			ML	0	2	98																	blue clay/silt as per TH16-02	
	2.0			ML	0	2	98																		
	1.6			ML	5	2	93																	small gravel/cobble in clay; screen 13"-18" plug 12"	

BRX= Bedrock
 Layer Elevation = Possible Error

FVI= Field Visual Identification
 WSA= Washed Sieve Analysis
 LVI= Lab Visual Identification



Ministry of Transportation

TEST PIT / HOLE SUMMARY SHEET

Pit: Raven Pit Contract Area: North Island - 3 Equipment: Sonic Drill Date: March 15, 2016

Test Hole Number	Layer Thickness (m)	Layer Top Elevation (m)	Layer Bottom Elevation (m)	Soil Classification	Gradation of Materials							Soundness Indicator					Density	Absorption	Water Table Elevation (m)	Remarks	Bag #			
					Gravel	Sand	Fines	75-150 mm	150-300 mm	> 300 mm	Maximum Size (mm)	Fracture		Micro Duval		Sand Eq.						MgSO4		
												A (%)	B (%)	C (%)	F (%)							C (%)	F (%)	C (%)
16-4	3.2			SP	42	55	3	>1			75										0.2	UTM 348825E 5506794N; WSA	799	
	2.0			SP	37	60	3	>1			50										0m @ 14/04/16	WSA	780	
	1.3			SPSM	2	88	10															fine/med sand; WSA	781	
	2.0			SM1	1	84	15															Coarser sand; WSA	782	
	2.9			SPSM	46	48	6															screen 23"-28", plug 22"; WSA	783	
	0.2			ML	0	1	99															Blue clay/silt		
16-05	3.0			FILL																		UTM 348848E 5506883N; Fill, screened round, OB		
	4.1			SM3	2	66	32														1.2m @ 14/04/16	silty sand; WSA	784	
	1.0			GP	55	44	1			50												clean gravel; WSA	785	
	0.2			ML	0	2	98															silt and fine sand		
	0.5			SM2	5	75	20															silty sand, some gravel		
	0.2			ML	0	98	2															Blue clay sand		
	0.4			SM3	5	75	20															blue color; WSA	786	
	1.4			SM2																				
	1.7			ML	0	98	2															Blue clay/silt; screen 30"-35" plug 29"		
16-06	3.0			GP	56	40	4	>1			75											UTM 348954E 5506910N; WSA	787	
	3.0			SP-SM	5	86	9															1.92 @14/04/16	medium sand; WSA	788
	3.7			ML	0	2	98															Blue clay; Screen 13"-18" plug 12"		

BRX= Bedrock
 Layer Elevation = Possible Error

FVI= Field Visual Identification
 WSA= Washed Sieve Analysis
 LVI= Lab Visual Identification



Pit: Raven Pit Contract Area: North Island - 3 Equipment: Sonic Drill Date: March 15, 2016

Test Hole Number	Layer Thickness (m)	Layer Top Elevation (m)	Layer Bottom Elevation (m)	Soil Classification	Gradation of Materials						Soundness Indicator					Density	Absorption		Water Table Elevation (m)	Remarks	Bag #					
					Gravel	Sand	Fines	75-150 mm	150-300 mm	> 300 mm	Maximum Size (mm)	Fracture		Micro Duval								Sand Eq.	MgSO4			
												A (%)	B (%)	C (%)	F (%)								C (%)	F (%)	C (%)	F (%)
16-07	0.7			SP	23	69	8														UTM 348990E 5506775N; WSA; Medium sand	789				
	0.5			GPGM				>1		75															WSA	
	0.6			SP																					WSA	
	0.2			GPGM				>1		50															2.7	WSA
	1.5			SP																					2.35 @14/04/16	WSA
	3.0			ML/CL	0	1	99															Blue clay/silt; Screen 7"-12", plug 6"				
16-08	1.5			FILL																	4.2	UTM 349067E 5506860N; #3214 oversize reject				
	2.7			SM1	8	75	17															2.0 on 14/04/16	Medium sand with silt seam @ 3.2m; WSA	900		
	1.3			SM3	0	70	30																WSA	901		
	1.5			ML/CL	0	1	99																			
16-09	1.0			Crush																			UTM 348677E 5506798N			
	2.0			SP	46	50	4	>1			100												WSA	902		
	3.0			GP-GM	53	41	6	>1															WSA	903		
	0.2			SM1	20	65	15	>1																		
	0.8			GP	60	38	2	2			100															
	1.6			SP	30	65	5				100												9.4-7.5 silt seam			
	1.6			GP	90	9	1	2			50												washed out? no sand			
	1.6			SPSM	34	61	5	>1			50												WSA	904		
	2.9			SM4	0	55	45																brown silty sand			
	0.2			ML/CL	0	1	99																blue clay/silt			

BRX= Bedrock
Layer Elevation = Possible Error

FVI= Field Visual Identification
WSA= Washed Sieve Analysis
LVI= Lab Visual Identification

Pit: Raven Pit **Contract Area:** North Island - 3 **Equipment:** Sonic Drill **Date:** March 15, 2016

Test Hole Number	Layer Thickness (m)	Layer Top Elevation (m)	Layer Bottom Elevation (m)	Soil Classification	Gradation of Materials							Soundness Indicator					Density	Absorption		Water Table Elevation (m)	Remarks	Bag #					
					Gravel	Sand	Fines	75-150 mm	150-300 mm	> 300 mm	Maximum Size (mm)	Fracture		Micro Duval		Sand Eq.							MgSO4				
												A (%)	B (%)	C (%)	F (%)								C (%)	F (%)	C (%)	F (%)	
16-10	1.3			GP	60	36	4	>1				50												UTM 348560E 5506918N; Way point #328			
	1.7			SPSM	30	52	18	>1				50												silty sand and gravel; WSA	905		
	3.0			GPGM				>1			50															WSA	
	4.5			GP				1			75																medium sand-silt bedding; WSA
	2.0			SM2				6	73	21																WSA	906
	1.5			SPSM	15	77	8					25															
	1.5			ML/CL	0	1	99																	Blue clay/silt			
16-11	3.5			GP	39	56	5	1				75			8.2	10.7								5.5	UTM 348474E 5506912N; Pit floor;WSA	907	
	2.5			SP				>1			50																WSA
	2.0			SP							50																medium sand; WSA
	1.2			GP				1			75																coarse sand and gravel; WSA
		3.3			ML/CL	0	1	99																Blue clay silt			
16-12	5.0			GP-GM	53	39	8	1				100			9.6	10.3								UTM 348482E 5506966N; Pit floor;WSA	908		
	0.3			ML	0	1	99																	Clay seams			
	1.2			SP	15	80	5																				
	0.2			ML	10	10	80																	silty sand layer			
	2.1			SP	45	51	4	>1				100												WSA	909		
	1.2			SM4	0	55	45																				
	2.5			ML/CL	0	1	99																	Blue clay/silt			

BRX= Bedrock
Layer Elevation = Possible Error

FVI= Field Visual Identification
WSA= Washed Sieve Analysis
LVI= Lab Visual Identification



Ministry of Transportation

TEST PIT / HOLE SUMMARY SHEET

Pit: Raven #0152 Contract Area: North Island - 3 Equipment Type: Excavator

Test Pit/Hole Number	Layer Thickness (m)	Layer Top Elevation (m)	Layer Bottom Elevation (m)	Soil Classification	Gradation of Materials							Soundness Indicator					Density	Absorption		Water Table Elevation (m)	Remarks	Bag #					
					75/150 mm	150/225 mm	> 225 mm	Maximum Size (mm)	Gravel	Sand	Fines	Fracture		Micro Duval	Sand Eq.	MgSO4		C	F				C	F			
												A	B			C									F	C	F
												(%)	(%)	(%)	(%)	(%)		(%)	(%)				(%)	(%)	(%)	(%)	(%)
13-1	0.6	117.5	116.9	CR					50	46	4													FVI; CRUSH			
	0.4	116.9	116.5	GP	5	1		300	89	10	1														FVI		
	3.0	116.5	113.5	SP					15	83	2										114.0				FVI; 2L/MIN		
13-2	0.2	118.6	118.4	CR																					FVI; CRUSH		
	0.8	118.4	117.6	GP	3	1		300	54	44	2															FVI	
	2.0	117.6	115.6	SP	2			150	41	58	1															WSA	181
	0.2	115.6	115.4	CL																						FVI	
	0.8	115.4	114.6	GP	5	2	1	350	62	36	2										115.4					FVI; 2L/MIN	
13-3	1.0	121.6	120.6	GP	8	2		300	70	29	1											120.8				FVI; 2L/MIN	
13-4	0.2	123.2	123.0	CR																						FVI; CRUSH	
	1.0	123.0	122.0	SPSM	3	2	1	300	40	52	8															WSA	738
	2.0	122.0	120.0	SP	5	2	1	300	43	56	1															WSA	739
	0.3	120.0	119.7	SP					20	78	2										119.7					FVI; 2L/MIN	

BRX= Bedrock
 Layer Elevation = Possible Error

FVI= Field Visual Identification
 WSA= Washed Sieve Analysis
 LVI= Lab Visual Identification



Ministry of Transportation

TEST PIT / HOLE SUMMARY SHEET

Pit: Raven #0152 **Contract Area:** North Island - 3 **Equipment Type:** Excavator

Test Pit/Hole Number	Layer Thickness (m)	Layer Top Elevation (m)	Layer Bottom Elevation (m)	Soil Classification	Gradation of Materials							Soundness Indicator				Density	Absorption		Water Table Elevation (m)	Remarks	Bag #				
					75/150 mm	150/225 mm	> 225 mm	Maximum Size (mm)	Gravel	Sand	Fines	Fracture		Micro Duval	Sand Eq.		MgSO4					C	F	C	F
												A	B				C	F							
												(%)	(%)	(%)	(%)		(%)	(%)				(%)	(%)	(%)	(%)
13-5	0.3	131.5	131.2	GM1					48	38	14											FVI			
	1.5	131.2	129.7	GP	2			150	64	36	0												WSA	212	
	3.2	129.7	126.5	SP	2	1		180	44	54	2												WSA	213	
	1.0	126.5	125.5	GP	5	2		300	60	39	1												WSA	730	
13-6	0.3	133.2	132.9	GM1	1	1		200	48	38	14												FVI		
	4.2	132.9	128.7	GP	6	3	1	350	61	39	0	85	76	7	11								WSA; LOOSE MATERIAL	731	
13-7	6.0	131.7	125.7	SP	4	2	1	300	40	58	2												WSA	740	
13-8	1.0	130.7	129.7	GP	4	2	1	300	64	35	1	EXCAVATED OUT													
	5.0	129.7	124.7	GP	3	1		150	53	44	3														
13-9	2.5	142.3	139.8	GP	5	2	1	350	54	42	4	86	81	15	13								WSA	742	
	3.5	139.8	136.3	SP	2			150	39	59	2												WSA	743	
13-10	0.2	144.3	144.1	TS																			FVI; ORGANICS		
	1.5	144.1	142.6	SP	2	1		250	43	56	1	84	75	12	11								WSA; SOME CRUMBLY ROCK	744	
	1.8	142.6	140.8	GP	3	2	1	300	63	35	2												WSA	745	
	2.5	140.8	138.3	GP	1			150	54	44	2	81	74	12	13								WSA; FINER THAN SA-2	746	

BRX= Bedrock
 Layer Elevation = Possible Error

FVI= Field Visual Identification
 WSA= Washed Sieve Analysis
 LVI= Lab Visual Identification



Ministry of Transportation

TEST PIT / HOLE SUMMARY SHEET

Pit: Raven #0152 **Contract Area:** North Island - 3 **Equipment Type:** Excavator

Test Pit/Hole Number	Layer Thickness (m)	Layer Top Elevation (m)	Layer Bottom Elevation (m)	Soil Classification	Gradation of Materials							Soundness Indicator				Density	Absorption		Water Table Elevation (m)	Remarks	Bag #				
					75/150 mm	150/225 mm	> 225 mm	Maximum Size (mm)	Gravel	Sand	Fines	Fracture		Micro Duval	Sand Eq.		MgSO4					C	F	C	F
												A	B				C	F							
												(%)	(%)	(%)	(%)		(%)	(%)				(%)	(%)	(%)	(%)
13-11	0.2	145.8	145.6	TS																FVI; ORGANICS					
	2.8	145.6	142.8	GP	8	5	1	400	62	35	3										WSA	747			
	2.5	142.8	140.3	SP	4	2	1	350	46	51	3										WSA	748			
	0.5	140.3	139.8	SP	1			150	20	79	1										FVI				
13-12	0.2	151.5	151.3	TS																FVI; ORGANICS					
	1.5	151.3	149.8	GP	6	2	1	350	50	47	3										FVI				
	3.3	149.8	146.5	GP					63	35	2	83	73	13	13						WSA	749			
	1.0	146.5	145.5	SP	1			150	30	69	1										FVI				
13-13	0.2	152.1	151.9	TS																FVI; ORGANICS					
	2.3	151.9	149.6	GP	4	2		300	50	47	3					61	4	14	2.8	2.7	1.9	3.5	WSA	732	
	2.5	149.6	147.1	GP	4	2		300	62	35	3												WSA; CRUMBLY ROCK	733	
	1.0	147.1	146.1	SP	1			150	35	63	2												FVI		
13-14	0.2	142.9	142.7	TS																	FVI; ORGANICS				
	3.8	142.7	138.9	GP	6	3	1	450	71	28	1												WSA; FINES DOWNWARD	734	
	2.0	138.9	136.9	SP	2	1		250	42	51	2												WSA	735	

BRX= Bedrock
 Layer Elevation = Possible Error

FVI= Field Visual Identification
 WSA= Washed Sieve Analysis
 LVI= Lab Visual Identification



Ministry of Transportation

TEST PIT / HOLE SUMMARY SHEET

Pit: Raven #0152 Contract Area: North Island - 3 Equipment Type: Excavator

Test Pit/Hole Number	Layer Thickness (m)	Layer Top Elevation (m)	Layer Bottom Elevation (m)	Soil Classification	Gradation of Materials							Soundness Indicator				Density	Absorption		Water Table Elevation (m)	Remarks	Bag #				
					75/150 mm	150/225 mm	> 225 mm	Maximum Size (mm)	Gravel	Sand	Fines	Fracture		Micro Duval	Sand Eq.		MgSO4					C	F	C	F
												A	B				C	F							
												(%)	(%)	(%)	(%)		(%)	(%)				(%)	(%)	(%)	(%)
13-15	0.2	145.7	145.5	TS																	FVI; ORGANICS				
	4.3	145.5	141.2	GP	10	5	2	450	61	36	3	84	78	12	13								WSA	736	
	1.5	141.2	139.7	GPGM	2	1		250	52	42	6												FVI; FINES DOWNWARD		
13-16	0.2	135.5	135.3	TS																		FVI; ORGANICS			
	1.3	135.3	134.0	GP	5	3	1	450	62	34	4												FVI		
	3.0	134.0	131.0	GPGM	5	3	1	450	58	37	5					47	5.9	12	2.9	2.7	1.6	3.1	WSA	737	
	1.5	131.0	129.5	SP	1			150	35	64	1												FVI		
13-17	0.2	141.0	140.8	TS																			FVI; ORGANICS		
	2.3	140.8	138.5	GPGM	10	5	2	750	64	30	6													FVI	
	3.5	138.5	135.0	SP	2	1		300	48	49	3													WSA	180
13-18	0.2	147.2	147.0	TS																			FVI; ORGANICS		
	3.3	147.0	143.7	GP	10	5	1	600	59	40	1													WSA	178
	2.5	143.7	141.2	SP	1	1		200	25	74	1													FVI	
13-19	0.4	150.0	149.6	TS																			FVI; ORGANICS		
	3.6	149.6	146.0	GP	10	5	2	450	65	33	2	87	83	11	9.9									WSA	174
	2.0	146.0	144.0	GPGM	2	1		200	48	47	5													WSA	175

BRX= Bedrock
 Layer Elevation = Possible Error

FVI= Field Visual Identification
 WSA= Washed Sieve Analysis
 LVI= Lab Visual Identification



Ministry of Transportation

TEST PIT / HOLE SUMMARY SHEET

Pit: Raven #0152 Contract Area: North Island - 3 Equipment Type: Excavator

Test Pit/Hole Number	Layer Thickness (m)	Layer Top Elevation (m)	Layer Bottom Elevation (m)	Soil Classification	Gradation of Materials								Soundness Indicator				Density	Absorption		Water Table Elevation (m)	Remarks	Bag #			
					75/150 mm	150/225 mm	> 225 mm	Maximum Size (mm)	Gravel	Sand	Fines	Fracture		Micro Duval	Sand Eq.	MgSO4		C	F				C	F	
												A	B			C									F
												(%)	(%)	(%)	(%)	(%)		(%)	(%)				(%)	(%)	(%)
13-20	0.4	153.6	153.2	TS																	FVI; ORGANICS				
	4.1	153.2	149.1	SP	5	2	1	450	48	49	3										WSA: COMPACTED/CEMENTED	173			
	1.5	149.1	147.6	SP	1			150	46	53	1									147.6	FVI; 4L/MIN				
13-21	0.4	154.4	154.0	TS																		FVI; ORGANICS			
	3.1	154.0	150.9	SP	4	2			44	54	2	81	76	12	12							WSA: COMPACTED/CEMENTED	171		
	2.0	150.9	148.9	GP	6	3	1		49	48	3											WSA	172		
	0.5	148.9	148.4	SP	1			150	24	75	1											FVI			
13-22	0.4	127.0	126.6	TS																			FVI; ORGANICS		
	2.6	126.6	124.0	SP	4	2		300	43	56	1												WSA; LUMPS OF COMPACTED S+G	176	
	2.0	124.0	122.0	SP	2			150	33	66	1												FVI		
	1.0	122.0	121.0	GP	4	1		250	63	35	2												WSA	177	
13-23	0.4	130.0	129.6	TS																				FVI; ORGANICS	
	3.6	129.6	126.0	GP	4	2	1	450	52	47	1	81	73	9.4	10								WSA	179	
	1.5	126.0	124.5	GP	3	2		250	79	17	4												WSA	710	
	0.5	124.5	124.0	SP	1			150	34	65	1												FVI		

BRX= Bedrock
 Layer Elevation = Possible Error

FVI= Field Visual Identification
 WSA= Washed Sieve Analysis
 LVI= Lab Visual Identification



Ministry of Transportation

TEST PIT / HOLE SUMMARY SHEET

Pit: Raven #0152

Contract Area: North Island - 3

Equipment Type: Excavator

Test Pit/Hole Number	Layer Thickness (m)	Layer Top Elevation (m)	Layer Bottom Elevation (m)	Soil Classification	Gradation of Materials							Soundness Indicator				Density	Absorption		Water Table Elevation (m)	Remarks	Bag #											
					75/150 mm	150/225 mm	> 225 mm	Maximum Size (mm)	Gravel	Sand	Fines	Fracture		Micro Duval	Sand Eq.		MgSO4					C (%)	F (%)	C (%)	F (%)							
												A (%)	B (%)				C (%)	F (%)								C (%)	F (%)					
13-24	1.0	132.2	131.2	GP	5	2		300	68	32	2	EXCAVATED OUT																711				
	5.0	131.2	126.2	SP	3	2		300	48	50	2																					
13-25	0.5	133.1	132.6	TS								FVI; ORGANICS																				
	0.5	132.6	132.1	SP					14	84	2	FVI																				
	4.0	132.1	128.1	GP	6	3		300	62	37	1	WSA																712				
	1.0	128.1	127.1	SP					40	58	2	FVI																				
13-26	0.4	148.4	148.0	TS								FVI; ORGANICS																				
	5.6	148.0	142.4	GP	4	2	1	300	53	46	1	84	78	12	11	WSA																713
13-27	0.4	146.0	145.6	TS								FVI; ORGANICS																				
	0.6	145.6	145.0	GP	6	4	1	400	56	42	2	FVI																				
	0.5	145.0	144.5	SM2	3	2	1	400	18	60	22	FVI																				
	0.5	144.5	144.0	SP					32	66	2	FVI																				
	0.3	144.0	143.7	GP	5	2		200	80	19	1	FVI																				
	2.7	143.7	141.0	SP	3	2		200	34	63	3	WSA																714				
	1.0	141.0	140.0	GP	3	2		200	60	39	1	FVI																				

BRX= Bedrock
 Layer Elevation = Possible Error

FVI= Field Visual Identification
 WSA= Washed Sieve Analysis
 LVI= Lab Visual Identification



Ministry of Transportation

TEST PIT / HOLE SUMMARY SHEET

Pit: Raven #0152 Contract Area: North Island - 3 Equipment Type: Excavator

Test Pit/Hole Number	Layer Thickness (m)	Layer Top Elevation (m)	Layer Bottom Elevation (m)	Soil Classification	Gradation of Materials							Soundness Indicator					Density	Absorption		Water Table Elevation (m)	Remarks	Bag #			
					75/150 mm	150/225 mm	> 225 mm	Maximum Size (mm)	Gravel	Sand	Fines	Fracture		Micro Duval	Sand Eq.	MgSO4		C	F				C	F	
												A	B			C									F
												(%)	(%)	(%)	(%)	(%)		(%)	(%)				(%)	(%)	(%)
13-28	0.4	150.8	150.4	TS																		FVI; ORGANICS			
	2.0	150.4	148.4	GP	10	5	2	500	60	36	4											FVI			
	3.6	148.4	144.8	SP	4	2		250	47	50	3											WSA	715		
13-29	0.4	146.1	145.7	TS																		FVI; ORGANICS			
	4.1	145.7	141.6	GP	10	5	1	500	68	31	1											WSA	716		
	1.5	141.6	140.1	SP	4	2	1	300	44	54	2											FVI			
13-30	0.4	144.4	144.0	TS																		FVI; ORGANICS			
	3.1	144.0	140.9	GP	5	3	1	400	57	42	1				86	5	13	2.8	2.7	1.9	3.2		WSA	718	
	1.0	140.9	139.9	SP	2	1		200	17	82	1											FVI			
	1.5	139.9	138.4	SP	2	1		200	45	54	1											WSA	717		

BRX= Bedrock
 Layer Elevation = Possible Error

FVI= Field Visual Identification
 WSA= Washed Sieve Analysis
 LVI= Lab Visual Identification