



GENERAL NOTES

Concrete shall be exposure Class HSe and meet min compressive strength of 30MPa @ 28d

Air Category: 4.0% - 7.0%

Aggregate: CSA/CAN A23.4 Maximum Size: 20mm

Admixtures: CSA/CAN A23.4

Reinforcing: Grade 400W CSA G30.18-09

Inserts/Embeds: As noted in drawing details

Manufacture of precast concrete units shall be in accordance with specification CSA A23.4

**** LEKO PRECAST LTD SHALL NOT BE RESPONSIBLE FOR ANY INSTALLATION PRACTICES FOLLOWED ON-SITE UNLESS PERFORMED BY LEKO PRECAST LTD ****



WOODY TOILET BUILDING, vestibule w/vault			
DRAWN BY: JA	CHECKED BY:	APPROVED BY:	DATE: June 2016
ASSEMBLY DWG.	PREVIOUS DWG.	DRAWING NO. W2003	REVISION
SCALE: 3/8"=1'-0" ISOMETRIC:			
DO NOT SCALE THIS DRAWING			