

Highway No. 4 Kennedy Hill Safety Improvements

Project No. 16527-2018

Earthworks Summary Table

<u>Material</u>	<u>Excavation</u>	<u>Used For</u>	<u>Embankment</u>	<u>Surplus</u>
Type A	217,222m ³	Highway Embankment (20% swell)	229,011m ³	
		Surplus to Crush for Road Gravels (Optional) (20% swell)		15,630m ³
		Surplus to Riprap Stockpile (20% swell)		16,025m ³
Type D (Suitable)	56,352m ³	Highway Embankment	50,529m ³	
		Surplus to Stockpile		5,823m ³
Type D (Unsuitable)	32,865m ³	Surplus – Spread on Embankment Slope or Stockpile		32,865m ³
Total	306,439m³		262,340m³	70,343m³