

16.1 Scope 2
 16.1.5 Uses requiring consent 2
16.4 Durability 2
 16.4.7 Allowance for wear in deck slabs 2
16.7 Externally restrained deck slabs 2
 16.7.1 General 2
 16.7.3 Cast-in-place deck slabs on stay-in-place formwork 2
16.8 Concrete beams, slabs and columns 2
 16.8.1 General 2
 16.8.10 Cast-in-place deck slabs with FRP stay-in-place structure forms 3

16.1 Scope

Add the following:

16.1.5 Uses requiring consent

Fibre-reinforced polymer (FRP) products shall not be used unless Consented to by the Ministry.

16.4 Durability

16.4.7 Allowance for wear in deck slabs

Delete and replace with:

No allowance for wear is required.

16.7 Externally restrained deck slabs

16.7.1 General

Delete item (c) and replace with:

- (c) The total thickness of the deck slab, t , is at least 175 mm and at least $s/15$.

Delete item (e) and replace with:

- (e) The deck slab is confined transversely by straps in accordance with the applicable provisions of Clause 16.7.2, 16.7.3 or 16.7.4.

Commentary: *The Ministry does not permit stay-in-place formwork. Partial depth concrete panels are not considered stay-in-place formwork.*

16.7.3 Cast-in-place deck slabs on stay-in-place formwork

Delete and replace with:

Stay-in-place formwork is not permitted.

Commentary: *The Ministry does not permit stay-in-place formwork.*

16.8 Concrete beams, slabs and columns

16.8.1 General

Delete the last paragraph and replace with the following:

FRP stay-in-place structural forms are not permitted for cast-in-place deck slabs. FRP stay-in-place structural forms for other components shall only be used when Consented to by the Ministry.

16.8.10 Cast-in-place deck slabs with FRP stay-in-place structure forms

Delete and replace with the following:

FRP stay-in-place structural forms are not permitted for cast-in-place deck slabs.