

PARTS LIST FOR 30A – 120/240V SERVICE PANEL (SN1765A)			
ITEM	QUANTITY	PART	DRAWING No.
1	1	S.S. PANEL ENCLOSURE	MS400.3 & 14
1A	1	S.S. PANEL TOP	MS400.8 & 15
1B	1	S.S. PANEL BOTTOM	MS400.8 & 15
1C	1	SMALL S.S. REINFORCING PLATE	MS400.4 & 16
1D	1	LARGE S.S. REINFORCING PLATE	MS400.4 & 16
1E	1	S.S. LOWER LEFT VERTICAL SUPPORT	MS400.6 & 16
1F	1	S.S. LOWER RIGHT VERTICAL SUPPORT	MS400.6 & 16
1G	1	S.S. UPPER LEFT VERTICAL SUPPORT	MS400.6 & 16
1H	1	S.S. UPPER RIGHT VERTICAL SUPPORT	MS400.6 & 16
1I	1	S.S. LOAD CENTRE MOUNTING PLATE	MS400.5 & 17
1J	1	BYPASS SWITCH MOUNTING PLATE	MS400.7 & 18
1K	1	MAIN BREAKER BARRIER	MS400.10 & 19
2	1	COVER PLATE	MS400.11 & 22
2A	1	LOAD CENTER DOOR AND COVER (SQUARE 'D' No. 00C12UC) DISCARD DOOR, USE COVER AND SPRING LOADED SCREWS ONLY	MS400.11
3	1	S.S. DOOR	MS400.12 & 21
4	1	LOAD CENTER (SQUARE 'D' 008MB-1) INCLUDING 30A MAIN BREAKER (SQUARE 'D' 00M30L)	MS400.9
4A	1	GROUND BAR (SUPPLIED WITH SQUARE 'D' LOAD CENTRE)	MS400.9
5	10	8-32 x 3/8" LONG S.S. ROBERTSON PAN HEAD SCREW	-
6	2	10-24 x 3/4" LONG S.S. ROBERTSON PAN HEAD SCREW INCLUDING S.S. NYLOCK NUT & 2 S.S. FLAT WASHERS	MS400.12
*	4	3/8" x 1" LONG (UNC) S.S. HEX HEAD BOLT INCLUDING S.S. FLAT WASHER & S.S. STAR LOCK WASHER	-
*	1	1" BULLET HUB (T & B No. 372) WITH GROUNDING AND BONDING LOCK NUT (T & B No. 3872)	-
*	1	1" INSULATED CHASE NIPPLE (T & B No. 1944)	-
*	1	RUBBER GASKET FOR 1" CHASE NIPPLE	-
*	1	SPEC GRADE 120-277 VAC 15A TOGGLE SWITCH INCLUDING MOUNTING SCREWS	-

NOTES

1. SEE STANDARD SPECIFICATIONS SECTION 401 – SERVICE DISTRIBUTION AND DISCONNECT PANELS FOR ADDITIONAL INFORMATION.
2. ALL DIMENSIONS ARE IN MILLIMETRES.
3. 'S.S.' INDICATES STAINLESS STEEL.
4. ITEMS INDICATED WITH AN * SHALL BE PACKAGED IN A PLASTIC BAG INSIDE THE PANEL.

30A--120/240V SERVICE PANEL
PARTS LIST

Xref ..\msbase1

PANEL DEPTH INCREASED

MAY97

MS400.1