



PARTS LIST FOR TELEPHONE DEMARCATION PANEL (SN1725)			
ITEM	QUANTITY	PART	DRAWING No.
1	1	S.S. PANEL ENCLOSURE	MS420.2, 3 & 10
1A	1	S.S. PANEL TOP	MS420.2, 6 & 11
1B	1	S.S. PANEL BOTTOM	MS420.2, 4 & 11
1C	1	S.S. PANEL MOUNTING BRACKET	MS420.2, 5 & 12
2	1	3/4" PLYWOOD EQUIPMENT MOUNTING BLOCK (ALL EDGES SANDED SMOOTH)	MS420.2, 7 & 12
2A	4	10-32 x 1" LONG S.S. BOLT, S.S. NUT AND S.S. WASHER	MS420.7
3	1	S.S. DOOR	MS420.2, 8 & 13
3A	1	LAMICOID NAME PLATE	MS420.2, 8 & 13
4	2	10-24 x 3/4" LONG S.S. ROBERTSON PAN HEAD SCREW INCLUDING S.S. NYLOCK NUT AND 2 S.S. FLAT WASHERS	MS420.2 & 8
*	4	3/8"ø x 1" LONG S.S. HEX HEAD BOLT INCLUDING S.S. FLAT WASHER AND SPRING LOCK WASHER.	-
*	1	1" BULLET HUB (T & B No. 372)	-
*	1	1" THREADLESS CONNECTOR (T & B No. 8323)	-
*	1	THREADED PLUG (CROUSE HINDS No. PLG35)	-

### NOTES

1. SEE STANDARD SPECIFICATIONS SECTION 403  
- TELEPHONE DEMARCATION PANELS FOR ADDITIONAL  
INFORMATION.
2. ALL DIMENSIONS ARE IN MILLIMETRES.
3. 'S.S.' INDICATES STAINLESS STEEL.
4. ITEMS INDICATED WITH AN \* SHALL BE PACKAGED IN A  
PLASTIC BAG INSIDE THE PANEL.

### TELEPHONE DEMARCATION PANEL PARTS LIST