

STANDARD GRASS SEED MIXES FOR REVEGETATION OF BRITISH COLUMBIA HIGHWAY ROADSIDES

REGION	GENERAL MIX	FORESTLAND MIX	DRYLAND MIX	OTHER MIXES	FERTILIZER
1 South Coast	(See Vancouver Island Mix)	(as for Region 2 below)	(as for Region 2 below)	(See Special Provisions)	18-18-18
2 Thompson Okanagan	(Use Specific Condition Mixes Shown)	Slender Wheatgrass 30% Perennial Ryegrass 23% Creeping Red Fescue 20% Canada Bluegrass 15% Alfalfa ("Rambler") 10% Redtop 2%	Crested Wheatgrass 40% Tall Wheatgrass 25% Slender Wheatgrass 20% Hard Fescue 15%	<u>Alkaline Tolerant Blend:</u> Crested Wheatgrass 35% Sherman Big Bluegrass 20% Hard Fescue 20% Canada Bluegrass 15%	22-11-11
3 Kootenays	(Use Specific Condition Mixes Shown)	(as for Region 2 above)	Tall Wheatgrass 38% Crested Wheatgrass 25% Hard Fescue 15% Alfalfa ("Rambler") 10% Canada Bluegrass 10% Redtop 2%	<u>Less Palatable Wildlife Mix:</u> Creeping Red Fescue 20% Canada Bluegrass 20% Tall Fescue 20% Crested Wheatgrass 15% Brome grass 10% Hard Fescue 5% Single Cut Red Clover 5% White Clover 5%	22-11-11
4 Central North East	Smooth Brome grass 40% Creeping Red Fescue 20% Timothy 15% Alfalfa 15% Alsike Clover 10%	(See Special Provisions)	Crested Wheatgrass 35% Intermediate Wheatgrass 25% Alfalfa 15% Smooth Brome 10% Creeping Red Fescue 10% Alsike Clover 5%	(See Special Provisions)	26-16-8
5 North West	Smooth Brome grass 40% Timothy 15% Alfalfa 15% Kentucky Bluegrass 10% Creeping Red Fescue 10% Alsike Clover 10%	<u>Northern Mix:</u> Crested Wheatgrass 20% Creeping Red Fescue 20% Alfalfa 16% Kentucky Bluegrass 15% Orchardgrass 15% Birdsfoot Trefoil 7% Hairy Vetch 7%	Orchardgrass 25% Intermediate Wheatgrass 20% Alfalfa 16% Crested Wheatgrass 15% Kentucky Bluegrass 10% Hard Fescue 7% White Clover 7%	<u>Coastal Mix:</u> Timothy 20% Sheep Fescue 20% Kentucky Bluegrass 15% Intermediate Wheatgrass 15% Smooth Brome grass 15% Alfalfa 10% Birdsfoot Trefoil 5%	22-11-11

6 Vancouver Island	Perennial Ryegrass	26%	(See Special Provisions)	18-18-18
	Creeping Red Fescue	24%		
	Alsike Clover	14%		
	Hard Fescue	13%		
	Timothy	8%		
	White Clover	9%		
	Canada Bluegrass	4%		
Redtop	2%			