

ELECTRICAL MAINTENANCE SPECIFICATION E-120

ILLUMINATED PEDESTRIAN CROSSING SIGN AND SPECIAL CROSSWALK SIGN MAINTENANCE

1. OBJECTIVE

To ensure that illuminated pedestrian crossing signs and special crosswalk signs are operational, and function in accordance with their design and Ministry standards.

2. DETAILED PERFORMANCE SPECIFICATIONS

2.1 Routine Maintenance Services

The Contractor must:

- a) repair or replace illuminated pedestrian crossing signs and special crosswalk signs and their components that constitute or have the potential to constitute an immediate Safety Hazard to the highway user or cause a Traffic Disruption, and Respond within 1 hour;
- b) repair or replace illuminated pedestrian crossing signs and special crosswalk signs and their components that do not operate as per their original design intent but are not immediate Safety Hazards, and Respond on the next Work Day;
- c) repair or replace illuminated pedestrian crossing signs and special crosswalk signs and/or their components that operate as per the original design intent, do not create a Safety Hazard, and are structurally sound but have identified deficiencies, and Respond within 30 days;
- d) perform Preventative Maintenance as required;
- e) replace non-LED lamps once every 12 months;
- f) replace failed LED light sources as required;
- g) replace all high intensity discharge lamps every 48 months;
- h) notify the RTMC of any malfunctioning illuminated pedestrian crossing sign and special crosswalk sign causing a Traffic Disruption within 5 minutes from the time the malfunction was detected by or reported to the Contractor and inform the RTMC when repaired;
- i) remove or cover graffiti in accordance with the performance time frames listed in the *Highway Maintenance Specification – Litter Collection and Graffiti Removal*; and
- j) document all activities related to electrical maintenance of illuminated pedestrian crossing signs and special crosswalk signs including but not limited to field inspections, Patrols, testing, complaints received/responses made and all changes made to the equipment and

operations as per section 600 of the *Traffic Controller Design Manual* in a timely manner to the Province's satisfaction.

2.2 Materials

Refer to Article 3 of the Introduction to the Specifications.