



BOREHOLE LOG 06-MW-26

Borehole Number: 06-MW-26

Client: ICL Holdings Ltd.

Levelton Project ID: 806-0131

Project: Detailed Site Investigation Site Location: 10091, 10111, 10131, 10151 River Dr. Richmond, BC

Depth (m)	Description	Symbol	Depth/Elev. (m)	Well and Backfill Details	SAMPLE		HEADSPACE VAPOUR CONC. ppmV (0-300) 50 150 250	COMMENTS
					Number	Type		
0	Ground Surface		0.0					
0-1	Asphalt							
1-1.2	Sand medium, damp-moist, brown, no odour				06-MW-26@0.6m	0		Not analyzed
1.2-1.7	-fine, some silt, moist - wet, grey, trace woodchips, no odour below 1.35m		1.2		06-MW-26@1.35m	10		Analyzed for styrene
1.7-2.25			1.7		06-MW-26@1.5m	5		Not analyzed
2.25-3.35	Clay silty, damp-moist, brown, slight decomposing odour -some wood fragments between 2.25-2.4m							Not analyzed
3.35-4.6	-slight fruity odour below 3.35m				06-MW-26@2.7m			Not analyzed
4.6-5.1			4.6		06-MW-26@3.6m	6		Analyzed for alcohols, dimethyl phthalate
5.1-6.1	Sand fine, silty, trace clay, wet, no odour				06-MW-26@5.1m			Shallow well backfill: concrete (0-0.3m) bentonite (0.3 - 0.6m) filter sand (0.6 -1.8m) with screen from 0.75-1.5m
6.1-6.1	End of Drill Hole		6.1					Deep well backfill: concrete (0-0.3m) bentonite (0.3-0.6m, 1.8-4.6m) filter sand (0.6-1.8m, 4.6-6.1m) with screen from 4.8-6.1m

Logged By: Jay Rao

Drilled by: Uniwide Drilling

Datum: Local

Date Drilled: May 4, 2006

Water Level Recorded on:

Sheet No: 1 of 1