



NEXT
Environmental Inc.

Borehole Log: BH103

Project No.: CAN210901.01

Logged By: NS

Project: DSI

Client: Canada Line Rapid Transit Inc.

Location
of Borehole: 2500 No. 3 Road: AEC3

Site Address: 2500 No. 3 Road, et al., Richmond, BC

| SUBSURFACE PROFILE | | | | SAMPLE | | | | |
|--------------------|--------|---|-------------|--------|------|------------------|--|---------------------|
| Depth | Symbol | Description | Depth/Elev. | Number | Type | Lab | ● ppmv ● 0 100 300 500 ▲ % LEL ▲ 0 50 100 | Borehole Completion |
| ft m | | Ground Surface | | | | | | |
| 0 | | SAND Fill Brown and grey medium to coarse SAND, trace gravel, trace concrete (Fill), wet, no odour. | 0.00 | 103-01 | ☛ | | 5 | |
| 1 | | Faint hydrocarbon odour from 1.5 m to 2.4 m. | | 103-02 | ☛ | B, V, E | 5 | |
| 2 | | Saturated at 1.5 m. | | 103-03 | ☛ | | 15 | |
| 3 | | SANDY SILT Grey SANDY SILT, saturated, strong hydrocarbon odour from 2.4 m to 3.4 m. | 2.44 | 103-04 | ☛ | B, V, L, H, P, M | 4 ▲ | |
| 4 | | | | 153-04 | ☛ | Dup of 103-04 | | |
| 5 | | SILTY SAND Grey SILTY SAND, saturated, moderate hydrocarbon odour from 3.4 m to 4.6 m. | 3.35 | 103-05 | ☛ | B, V, L, H, P | 325 | |
| 6 | | | | 103-06 | ☛ | | 110 | |
| 7 | | | | 103-07 | ☛ | | 300 | |
| 8 | | End of Borehole | 4.57 | | | | | |

Drilled By: Beck Drilling and Environmental Services

Drill (Sample) Method: Solid Stem Auger

Drill Date: February 28, 2008

Depth to Water 2.28
(below top) (m):

Top of Pipe (top)
Well Elevation (m): 2.30

Surface Grade Elevation (m): 1.70

Groundwater
Analysis: L, H, P, B, V, Si

Sheet: 1 of 1