



NEXT  
Environmental Inc.

# Borehole Log: BH302

Project No.: CAN211501.02

Logged By: TL

Project: DSI

Client: TransLink

Location  
of Borehole: 1m east of BH205

Site Address: 2931-2991 No. 3 Road, Richmond

SUBSURFACE PROFILE				SAMPLE				
Depth	Symbol	Description	Depth/Elev.	Number	Type	Lab		Borehole Completion
0		Ground Surface						
0		<b>Sand and Gravel</b> Grey/brown SAND and GRAVEL (fill), trace brick, trace glass.	0.00					
0.46		<b>SILT</b> Grey SILT with orange mottling.	0.46					
1.22		<b>Silt</b> Grey Sandy SILT.  Moist at 1.4m.  Wet at 1.7m.	1.22					
3.05		<b>Sand</b> Grey SAND, trace silt, wet.	3.05					
4.57		End of Borehole	4.57					
No Samples Taken								

Drilled By: Beck Drilling and Environmental Services Ltd.

Top of Pipe (top)  
Well Elevation (m): 1.64 (geodetic)

Drill (Sample) Method: Solid Stem Auger / Hollow Stem Install

Surface Grade Elevation (m): 1.69 (geodetic)

Drill Date: June 19, 2009

Groundwater  
Analysis: M

Depth to Water  
(below top) (m): 1.12 (Jan 7, 2010)

Sheet: 1 of 1