



# PGL

## LOG OF BORING BH1M

(Page 1 of 1)

Client: E. Mathers Holding Co.  
 Site Address: 12351 No. 2 Road  
 Richmond, BC

Installation Date : June 11, 2009  
 Contractor : Mud Bay  
 Drill Type : Solid Stem Auger; install with hollow stem  
 Logged By : Cory Cavazzi  
 Well Installed : Yes

Well Type : PVC (2" diameter)  
 Vapour Analyzer : GasTech

Project No. 2997-01.02

Depth in Meters	USCS	GRAPHIC	DESCRIPTION	SAMPLES	SAMPLE NAME	Vapour ppm	REMARKS
0	AS		Asphalt surface				
0.5	SP		Brown, medium grained SAND, trace subangular gravel, moist		BH1M-1	50	
1.0			Grey SILT, stiff, moist, faint hydrocarbon odour from 0.9m to 1.5m		BH1M-2	400	
1.5			some clay from 1.5m to 2.4m				
2.0	ML		wet at 1.8m		BH1M-3/BH1M-GR1	75	
2.5	SM		Silty-SAND		BH1M-4	75	
3.0			End of hole at 3.1m				
3.5							

Well: BH1M

