

Augerhole no. : AH-18

Equipment : TRACK MOUNTED SOLID STEM AUGER RIG

Location : (See Test Hole Location Plan)

Method of Sampling: GRAB SAMPLE

Ground Water Elevation : 5.5m depth (at time of investigation)

depth, ft.	depth, m	Geodetic elevation	symbol	Description	sample no.	water content %	Remarks
0	0	0.05		Loose to compact, moist, brown, SAND and GRAVEL, trace of silt (FILL)			
1	1			Soft to firm / loose to compact, damp, greyish brown, SILT and SAND, some gravel, trace to some debris (FILL)	Sa1 18-1	12	GEOTECH SAMPLE 18-1 AT 3'
5	5	1.7		Compact, moist, grey, silty, fine SAND (FILL)			
2	2			Soft to firm / loose to compact, damp, greyish brown, SILT and SAND, some gravel, trace to some debris (FILL)	Sa2 18-2	12	GEOTECH SAMPLE 18-2 AT 9'
10	10	3.4		Firm, moist, grey, sandy SILT, some gravel, trace to some wood debris (FILL)	Sa3 18-3	21	GEOTECH SAMPLE 18-3 AT 14'
4	4	4.6		Firm, moist, grey, brown and black, SILT, organic SILT and fibrous PEAT, trace of sand, interlayered (FILL) -becomes wet with some roots	Sa4 18-4	44	GEOTECH SAMPLE 18-4 AT 19'
20	20	6.1		Compact, damp to moist, grey, fine SAND, trace to some gravel from 7.2m	Sa5 18-5		GEOTECH SAMPLE 18-5 AT 24'
7	7			End of test hole at 7.6m			
25	25						
8	8						
30	30						
9	9						
10	10						

R.F. Binnie and Associates Ltd.



TROW ASSOCIATES INC.

Campbell Heights Development  
Phase 2  
Surrey, BC

Augerhole No.  
AH-18

Logged by: RK  
Sheet: 1 of 1

Date of Drilling: 2007-Nov-6  
Ref No. 071-03419-02