

Borehole No.: 3082-BH4
 Location: See Location Plan
 Date Drilled: July 11, 2007
 Supervision: S. Buck

Drilling Method: Track-mounted Drill Rig
 Sampling Method: Grab Sample

depth (m)	Description	sample no.	Headspace	monitoring well details	Remarks
0	Concrete floor slab				
	Brown, blue and grey, moist, firm, silt and clay FILL	1	10		
	Black, moist, soft SILT; some organics; sour odour	2	10		Bentonite
1	Blue/grey, mottled, moist, firm CLAY/SILT	3	15		Blank PVC
2	Blue/grey, mottled, moist, firm CLAY/SILT; trace sand	4	15		PVC Screen GWL (07/07/23) Filter Sand
3					
4	Blue/grey, mottled, wet, firm CLAY/SILT; some sand	5	45		
5	End of Borehole @ 4.6 metres				
6					
7					
8					
9					

Project No.: 071-03082
 Project Location: 575 Pembroke Street, Victoria, BC
 Project: Supplemental Phase II ESA

Logged by: SB

