

WELL RECORD

WELL NO:

CLIENT: IKEA Properties LTD.

PGL PROJECT NO: 1889-05.02

BH27M

PROJECT: IKEA Richmond

SURFACE ELEVATION: n/a

DEPTH (m)	SOIL TYPE	SOIL DESCRIPTION	SAMPLE TYPE	LABORATORY ANALYSES	VAPOUR READING (ppmv)	GROUNDWATER OBSERVATIONS	WATER LEVEL	WELL COMPLETION	COMPLETION NOTES	ELEVATION (m)
0.0 - 0.2	ASPHALT							Roadbox, J-Plug, Concrete		
0.2 - 0.4	SAND	compact, trace gravel, grey, moist	Hand	BH27-1				Bentonite		
0.4 - 0.6	Sandy SILT	loose, trace clay, grey, moist						Filter Pack		
0.6 - 1.0		Wet at 1.0m		BH27-2	50					
1.0 - 1.6										
1.6 - 2.0	Silty SAND	loose, grey, wet		BH27-3	10					
2.0 - 2.4										
2.4 - 3.0	SAND	loose, some silt, grey, wet		BH27-4	10					
3.0 - 3.2		Black at 3.0m - organic odour								
3.2 - 3.4				BH27-5	10					
3.4 - 3.6										



GW 1.47 m (7/30/2010)

End of borehole at 3.60 m.

Screened interval from 0.6 m to 2.1 m below surface.

PGL BOREHOLE LOG DECEMBER 2010 1889-05.02 BH LOGS.GPJ PGL CANADA.GDT 1/10/11

INVESTIG. METHOD: Solid Stem Auger

Sample Notes  Grab Sample  Auger Cuttings

INVESTIG. DATE: July 28, 2010

LOGGED BY: ZM

Page 1 of 1