

# MONITORING WELL ID: TYPICAL



Well Type: Groundwater and soil vapour monitoring wells

Project Location: 988 West Broadway, Vancouver

Drilling Contractor: Uniwide Drilling Co. Ltd.

Drilling Equipment/Method: Solid Stem Auger

Well Location:

Project Name/No.:

Client:

Engineer/Geologist:

Drill Date: August 8, 2011

Page: 1 of 1

Depth (ft/m)	Symbol	Soil / Sediment Description	Sample Type	% Recovery	Sample Analyzed (Y,N)	Sample ID	Headspace (GasTech) (x100) ppm				Headspace (GasTech) LEL (%)				Well Construction	Remarks
							1	2	3	4	20	40	60	80		
0		Ground Surface														
0		<b>ASPHALT</b>														
1		<b>Silty SAND</b> Brown fine Silty SAND, minor subrounded gravel, dry, odours and/or staining not observed.			N	MW11-2 (0.3)	0.0									
2																
3																
4					N	MW11-2 (1.2)	0.0									
5																
6																
7					N	MW11-2 (2.1)	0.0									
8																
9																
10		Grey at 3.1 mbg, damp to moist			N	MW11-2 (3.0)	0.0									
11																
12					N	MW11-2 (3.5)	0.0									
13																
14																
15					N	MW11-2 (4.3)	0.0									
16		Moist at 5.0 mbg														
17					Y	MW11-2 (5.1)	0.0									
18																
19																
20					N	MW11-2 (6.0)	0.0									
21																
22																
23					N	MW11-2 (6.7)	0.0									
24																
25					N	MW11-2 (7.5)	0.0									
		End of Hole														

Any use which a third party makes of this document, or any reliance on or decision to be made based on it, are the responsibility of such third parties. CSAP / MOE / Keystone Environmental Ltd. are not responsible for any use or modification of this document. CSAP / MOE / Keystone Environmental Ltd. accepts no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions taken based on this document.

Date of Water Level: August 9, 2011	Well-Borehole Diameter: 25 cm	Depth of Well (TOC): 7.10 m
Water Level (from TOC): 4.884 m	Well Casing Diameter: 5 cm	
	Well Casing Material: PVC	
	Well Screen Slot Size: 10 slot	