



REPRESENTATIVE BOREHOLE LOG

BOREHOLE NAME	BH15-1/MW15-1	WATER LEVEL BELOW TOC (M)	3.84
BOREHOLE ADDRESS	4255 Arbutus Street	WATER LEVEL BELOW SURFACE (M)	3.91
BOREHOLE MUNICIPALITY	Vancouver	TOTAL BOREHOLE DEPTH (M)	6.10
BOREHOLE SITE ID	12194	BOREHOLE TOC ELEVATION (M ASL)	33.93
LATITUDE	49.2493° N	BOREHOLE SURFACE ELEVATION (M ASL)	34.00
LONGITUDE	123.1541° W	TOP OF SCREEN (M BGS)	4.60
BOREHOLE LOCATION	12 m west of the east Site boundary, 5 m south of the north Site boundary.	BOTTOM OF SCREEN (M MGS)	6.10
FILE NAME	L09.231_Representative_BH_Log		
DATE DRILLED	23 January 2015		
DRILL METHOD	Trackmount Auger Rig		
BOREHOLE DIAMETER	150 mm	HYDRAULIC CONDUCTIVITY	Not Applicable

		DESCRIPTION	WELL DETAILS
Graphical Symbol USCS Symbol 0.0 1.0 2.0 3.0 4.0 5.0 6.0		ASPHALT (0.05m)	
	SM	SILTY SAND Grey fine to medium grained sand with some silt and gravel (<pebble), dry, loose	
	OL	SANDY SILT Brown-grey silt with some fine to medium grained sand and organics, and trace gravel (<pebble), iron-streaks, dry	
	SM	SILTY SAND Grey fine to medium grained sand with some silt and trace gravel (<pebble), dry, loose	Silica Sand Slotted PVC 1.5 m Screen
		Wet at 5.3 m bsg	

End of Borehole at 6.1 m bsg

Any use which a third party makes of this document, or any reliance on or decisions to be made based on it, are the responsibility of such third parties. CSAP/MOE are not responsible for any use or modification of this document. CSAP/MOE accept no responsibility for damages, if any, suffered by any third party as a result of decisions made or actions taken based on this document.