



Levelton Consultants Ltd.
301-19292 60th Ave
Surrey, BC, V3S 3M2

Chilliwack Bingo Association c/o 438569 BC Ltd.
46125 Olds Drive, Chilliwack, BC

10-BH5/MW5

Pg 1 of 1

Project No: FV10-1580-00

Depth (ft) (m)	Description	Symbol	Depth (m)	Sample		Well and Backfill Details	Headspace Vapour Concentration			Laboratory Analysis /Comments
				Number/ ID	Type		▲ (ppm.) ▲ 10 100 1000			
0.1	ASPHALT		0.1							
0.8	Brown SAND and GRAVEL (FILL), moist, no odour.		0.8							
2.8	Brown SILT to silty, fine-grained SAND, trace gravel, moist, no odour.		2.8	SA1@1.2m	●					
3.6	Grey SAND, some silt, trace gravel, wet at 3.6m, no odour.		3.6	SA2@2.7m	●					
5.2	- silt lense with black organic staining at 5.2m, no odour.		5.2	SA3@3.9m	●		5			Analyzed for VH, VPH, BTEX, and metals.
6.0			6.0	SA4@5.2m	●		5			
6.0	Bottom of hole at 6.00 meters									

HAZMAT FV10-1580-00 BOREHOLE LOGS.GPJ LEVELTON DATA TEMPLATE.GDT 1/19/11

Sample Symbols	Backfill Symbols	Soil Symbols	Notes	Logged By	GNS
Grab Sample	Filter Sand	Asphalt			
	Bentonite	Sand and Gravel		Drilled/ Excavated By	Downrite Drilling
	Solid Pipe	Silty Sand/Sandy Silt		Date Drilled or Excavated	11/10/2010
	Slotted Pipe	SAND		Elevation (grade)	
	Slough/Cuttings			Water Level Recorded On	11/10/2010
	Concrete			Drill Method	Solid Stem Auger
<small>This log is for environmental purposes only. This log is the sole property of Levelton Consultants Ltd and cannot be used or duplicated in anyway without express written permission.</small>					