



Pottinger Caherty
Environmental Consultants Ltd.

LOG OF BORING BH4M

(Page 1 of 1)

Client: Canada Line Company
Site Address: 6300 No 3 Road, Richmond, BC
Scotia Bank

Installation Date : September 29, 2007
Contractor : Beck Drilling
Drill Type : Vac truck / Solid, Hollow Stem
Logged By : Andrew Schmidt
Well Installed : Yes

Elevation (Surface) :
Elevation (TOC) :
Depth to water : 1.442 m
Elevation of water :
Well Type : PVC (2" diameter)

Project No.: 2069-02.02

DEPTH (m)	USCS	GRAPHIC	Water Level		SAMPLES	SAMPLE NAME	Headspace	Well: BH4M
			▽	▽				
			DESCRIPTION					
0	FL		Asphalt					
0 - 1.2	FL		Brown silty SAND (FILL), compact, moist					
1.2 - 2.7	ML		Grey SILT, some sand, trace rootlets, compact, wet					
2.7 - 4.5	SM		Grey silty SAND, loose, wet					
4.5					⊗	BH4M-1	0ppm Tetrachloroethylene	
6.0					⊗	BH4M-2	0ppm Tetrachloroethylene	
			End of hole @ 6.0m					
6.5								

11-16-2007 1:2000-21992069 - RAV02 02Borehole Logs: BH4M.bor