



NEXT
Environmental Inc.

Borehole Log: BH404

Project No.: MON030104.01 **Logged By:** NC

Project: Detailed Site Investigation **Client:** Mondiale Development Ltd.

Location of Borehole: North of Boatways

Site Address: 109 & 116 East Esplanade, North Vancouver

SUBSURFACE PROFILE				SAMPLE				
Depth	Symbol	Description	Depth/Elev.	Well Completion Details	Number	Type	Vapour (ppmv)	Lab Analysis
0		Ground Surface	0.0					
1		SAND Brown, SAND, some gravel, trace woodwaste, moist.			404-1	Grab	30	
2			0.8					
3		SAND and GRAVEL Grey, SAND and GRAVEL, trace wood debris, moist.			404-2	Grab	5	L/H/P
4								
5								
6								
7		- wet			404-3	Grab	40	
8			2.4					
9		SAND Dark grey/black, SAND, some gravel, trace silt, wet.			404-4/5	Grab	20	L/H/P
10		- trace shell fragments, trace wood debris						
11		WOODWASTE		404-6	Spoon	50	L/H/P	
12			3.3					
13		SAND Grey, coarse SAND, some gravel, some shell fragments, wet.		404-7	Spoon	10	PAH	
14			4.3					
15		SAND Grey, fine SAND, some silt, some gravel, wet.		404-8	Spoon	-	L/H/P	
16		- coarse sand		404-9	Spoon	<5		
17			5.2					
18		SILT and SAND Grey, fine SILT and SAND, trace gravel, moist.		404-10	Spoon	-		
19								
20								

Drilled By: Mud Bay Drilling Co. Ltd.

Drill Method: Solid & Hollow Stem

Drill Date: June 5, 2002

Depth to Water (below top) & Date: 1.987 m June 13/02

Top of Pipe (top) Well Elevation:

Surface Grade Elevation: 98.565 m

Groundwater BTEXS/VPHs/LEPHs/HEPHs Analysis: PAHs/Metals

Sheet: 1 of 2



NEXT
Environmental Inc.

Borehole Log: BH404

Project No.: MON030104.01

Logged By: NC

Project: Detailed Site Investigation

Client: Mondiale Development Ltd.

Location
of Borehole: North of Boatways

Site Address: 109 & 116 East Esplanade, North Vancouver

SUBSURFACE PROFILE				SAMPLE				
Depth	Symbol	Description	Depth/Elev.	Well Completion Details	Number	Type	Vapour (ppmv)	Lab Analysis
21	[Symbol: Dotted pattern]		7.3	[Diagram: Well completion details showing casing and screen]	404-11	Spoon	-	
22								
23	7							
24								
25								
26	8	L = LEPHs H = HEPHs P = PAHs						
27								
28								
29								
30	9							
31								
32								
33	10							
34								
35								
36	11							
37								
38								
39	12							
40								

Drilled By: Mud Bay Drilling Co. Ltd.

Drill Method: Solid & Hollow Stem

Drill Date: June 5, 2002

Depth to Water
(below top) & Date: 1.987 m June 13/02

Top of Pipe (top)
Well Elevation:

Surface Grade Elevation: 98.565 m

Groundwater BTEXS/PHs/LEPHs/HEPHs
Analysis: PAHs/Metals

Sheet: 2 of 2