

BOREHOLE LOG

LOGGED BY: Claudia Wu
DRILLER: Beck Drilling

RIG: Mobile B61
OD & TYPE: 130 mm OD SS Augers

HOLE NO.: BH-5
WELL PIPE TOP EL. (m): 100.068

Depth (m)	DESCRIPTION	Symbol	Number	Type	Well & Vapour Probe	COV Concentration		Comments
						ppmv	%LEL	
						●	■	
						100	10	
						200	30	
						300	50	
							70	
							90	
0	Ground Surface							
0 - 0.15	Concrete	vvvvvv			x			"Corkscrewed" augers - 0 to 1.5 m Drilled to 4.7 m. Refusal - apparent bedrock or boulder.
0.15 - 1.5	Sand/Gravel (Fill) Dark brown, dry to moist	x/x/x/x	1	●	x			
1.5 - 2.2	Silty clay Brown to grey, trace sand and gravel, firm to stiff, moist to wet	/ / / /	2	●	x			
2.2 - 2.5		/ / / /	3	●	x			
2.5 - 3.2		/ / / /	4	●	x			
3.2 - 4.7	Silty Sand Brown, trace fine gravel, wet	5	●	x			
4.7 - 5.0	Bedrock	— — — —		●	x			
5.0	End of Borehole							No chemical staining/odours observed throughout.



PROJECT Stage 2 PSI
LOCATION: 1001 Blanshard Street, Victoria, BC
CLIENT: Vancouver City Savings Credit Union

PROJECT NO: 7953
DRILLING DATE(S): 12 January, 2010
SHEET NO: 1 of 1