



NEXT
Environmental Inc.

Borehole Log: BH307

Project No.: MOR070101.03

Client: Moretti Bros Holdings Ltd.

Project: DSI

Logged By: RM

BH Location: North of northern tank nest.

Site Address: 1175 Venables Street & 1152 Union Street, Vancouver, BC

SUBSURFACE PROFILE				SAMPLE / BOREHOLE COMPLETION					
Depth	Symbol	Description	Depth/Elev.	Sample ID	Type	Lab	• ppmv •	Borehole Completion	Depth
							▲ % LEL ▲		
0		Ground Surface	0.00						0
1		SAND AND GRAVEL (fill) Light Brown, SAND AND GRAVEL, some cobbles, some brick, loose, dry-moist.		BH307-1		-	0		1
2									2
3									3
4			1.37						4
5		Clayey SOIL Dark Brown, Clayey SOIL, some organics, soft, moist.	1.68	BH307-2		Y	0		5
6				BH307-3		Y	80		6
7		SAND Grey, SAND, loose, wet.	1.98						7
8		Silty CLAY Light Grey/Blue, Silty CLAY, rusty mottling, stiff, moist-wet...		BH307-4		-	0		8
9									9
10									10
11		increase in Sand at end of interval.		BH307-5		-	0		11
12			3.66						12
13		End of Borehole							13
14									14
15									15
16									16
17									17
18									18
19									19
20									20

Drilled By: Omega Environmental Drilling Ltd.

Drill (Sample) Method: Solid Stem Auger

Drill Date: July 27, 2015

Depth to Water (below TOP) (m): 2.32

Date of Measurement: July 29, 2015

Top of Pipe (TOP)

Well Elevation (m): Not Surveyed

Surface Grade Elevation (m): Not Surveyed

Groundwater

Analysis: Y

Sheet: 1 of 1