

WELL RECORD

WELL NO:

CLIENT: Chard Development Ltd.
PROJECT: 848 Yates Street, Victoria, BC

PGL PROJECT NO: **4531-07.01**
TOP OF PIPE (TOP) ELEVATION: **19.949 m**
SURFACE ELEVATION: **20.03 m**

BH01M-S

DEPTH (m)	SOIL TYPE	SOIL DESCRIPTION	SAMPLE TYPE	LABORATORY ANALYSES	VAPOUR READING (ppmv)	WATER LEVEL	WELL COMPLETION	COMPLETION NOTES	ELEVATION (m)
0.0	ASPHALT							Roadbox, J-plug	20.0
0.2	SAND AND GRAVEL (FILL)	coarse grained, loose, brown, dry to moist						Concrete	19.8
0.4	Silty SAND (FILL)	fine grained, soft, trace gravel, topsoil, crushed bricks, black, moist						Silica Sand	19.6
0.6	Silty CLAY	stiff, some sand, grey, moist						Bentonite	19.4
0.8		trace sand below 0.8m							19.2
1.0									19.0
1.2									18.8
1.4			BH06M-02	ND					18.6
1.6		brown below 1.5m							18.4
1.8									18.2
2.0								50mm 010 Slot PVC	18.0
2.2									17.8
2.4									17.6
2.6									17.4
2.8								Slough	17.2
3.0									

End of borehole at 3.00 m

Screened interval from 1.1 m to 2.6 m below surface.
GW 1.54 mbgs
(5/12/2017)

INVESTIG. METHOD: Solid Stem Auger
INVESTIG. DATE: May 1, 2017
LOGGED BY: AER HOLE DIAM (mm): 150

Sample Notes  Auger