

PROJECT No.: 11-1436-0082 / 5000 / 5350

**RECORD OF MONITORING WELL: MW-ON14-05**

SHEET 1 OF 1

CLIENT: 8360 Wiggins Holdings Inc.  
 PROJECT: Oxford Riverbend  
 LOCATION: 5279 Riverbend Dr., Burnaby, B.C.  
 N: 5448420.87 E: 501937.26

DRILLING DATE: September 5, 2014  
 DRILLING CONTRACTOR: Downrite Drilling Ltd.

DATUM: Geodetic

DEPTH SCALE METRES	DRILLING RIG DRILLING METHOD	SOIL PROFILE		SAMPLES				PID ppm		DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m				ADDITIONAL LAB. TESTING	PIEZOMETER, STANDPIPE OR THERMISTOR INSTALLATION					
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	CORE No.	CORE RECOVERY %	5	10	15	20			20	40	60	80	
0	Track Mounted Auger Drill Rig Solid Stem Auger (152mm)	Ground Surface		1.58														Stickup		
		(SP) SAND, medium; grey, non-cohesive, dry, loose.		0.00	1	AS														
1		(PT) Amorphous PEAT; brown, contains wood fibers, cohesive, w-PL, soft.		0.48	2	AS														Bentonite Chips
2		- w>PL at 2.25m depth.		1.10																
3		(ML) SILT; grey, cohesive, w-PL, firm.		-1.32	3	AS														
4			2.90	4	AS															
5		End of Monitoring Well.		-3.02	5	AS												Slotted PVC Pipe		
			4.60																	
6																				
7																				
8																				
9																				
10																				

National IM Server\GINT\_CAL\INTERNATIONAL\Unique Project ID Output Form\BC\_BOREHOLE (ENVIRO) files 10/6/14

DEPTH SCALE

1 : 50



SOIL CLASSIFICATION SYSTEM: GACS

LOGGED: VP

CHECKED: EB

Disclaimer: For Environmental Purposes Only