

DRILL LOG

CLIENT: NEWCORP  
 JOB NO: 5-134-01.02  
 SITE LOCATION: 1185 Quayside Drive, New Westminster, B.C.

WELL NO: OW1  
 DATE: 06/13/91  
 DATUM: ground surface

NORECOL SUPERVISOR: B. Rodgers  
 CONTRACTOR: Mud Bay Drilling Co. Ltd.  
 DRILLING TYPE: Auger

INSTALLATION DETAILS  
 Casing Type - 51mm I.D. PVC, flush joint  
 Screen Type - 51mm PVC with 0.20mm slot  
 Sand Type - No.8 silica

DEPTH metres	SOIL DESCRIPTION		SAMPLE		BLOWS	OTHER
			INT	NAME		
0.0	Brown gravelly fill. Cement					
1.0	Fill Brown-grey silty sand with gravel (1"), no odour					
2.0	Bentonite Grey moist silt. Drilling characteristics indicated silt starts at approximately 1.8m depth.					
3.0						
4.0	Frac. Sand Grey silt with fine sand, no odour.					
5.0	End of Hole 4.5 m. Screened Interval 3.0 - 4.6 m					
6.0	Well was dry.					