

RECORD OF MONITORING WELL: MW11-01

LOCATION: CNV - 720 West 2nd Street, North Vancouver
 N: 5462960.29 E: 493226.17

DRILLING DATE: January 11, 2011

DATUM: N/A

DRILLING CONTRACTOR: Beck Drilling and Environmental Services Ltd.

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES		PID ppm				HYDRAULIC CONDUCTIVITY, k, cm/s				ADDITIONAL LAB. TESTING	PIEZOMETER, STANDPIPE OR THERMISTOR INSTALLATION	
		DESCRIPTION	STRATA PLOT	ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	5	10	15	20	10 ⁻⁶	10 ⁻⁵			10 ⁻⁴
0	B61 Truck Mounted Auger Drill Hollow Stem Auger	Ground Surface		6.90											Flush Mount Road Box	
		Asphalt.		6.80												Concrete
		Compact, moist, grey, silty SAND, some gravel, contains cobbles. (FILL) - no odour or staining.		0.10	1	AS	⊕									Bentonite Seal
1		Compact, moist, brown, sandy SILT, contains organics (wood fibre fragments), some gravel. - no odour or staining.		5.99	2	AS	⊕									Filter Sand
		Compact, moist to wet, grey SILT, trace sand. - no odour or staining.		5.38	3	AS	⊕									Slotted PVC Pipe
2		Compact, wet, grey SAND, trace silt. - no odour or staining.		4.77	4	AS	⊕									1/11/2011
		Compact, wet, brown SILT, contains organics (wood fibres and fragments), trace to some sand. - no odour or staining.		4.46	5	AS	⊕									
3	Compact, wet, grey-brown, coarse SAND, trace silt, trace gravel. - no odour or staining.		3.85	6	AS	⊕									Slough	
			3.05													
4			2.33													
5		End of Monitoring Well.		4.57												

File N:\BURJ-Graphics\PROJECTS\2010\1436\10-1436-0062\5000\10-1436-0062 (5000).GPJ Output Form BIC BOREHOLE (AUTO). Template: BIC REGION TEMPLATE BETA 1.GDT Library: BC REGION LIBRARY.GLB sreddy, 10/17/11