

"For Environmental Purposes Only"

PROJECT No.: 07-1412-0081 (6000)

**RECORD OF MONITORING WELL: MW10-09**

SHEET 1 OF 1  
DATUM: Local

LOCATION: Translink False Creek - 95 East 1st Avenue (South Lot)

DRILLING DATE: September 22, 2010

DRILLING CONTRACTOR: BECK Drilling and Environment Services Ltd.

DEPTH SCALE METRES	BORING METHOD	SOIL PROFILE		SAMPLES				DYNAMIC PENETRATION RESISTANCE, BLOWS/0.3m				ADDITIONAL LAB. TESTING	PIEZOMETER, STANDPIPE OR THERMISTOR INSTALLATION	
		DESCRIPTION	STRATA PLOT ELEV. DEPTH (m)	NUMBER	TYPE	BLOWS/0.3m	CORE No.	CORE RECOVERY %	PID ppm	WATER CONTENT PERCENT	Wp			W
0		Ground Surface												Stickup = 0.88m
		Compact, damp, grey, sandy GRAVEL (Road Base FILL) - no odour or staining.	0.00 0.15											Concrete
1														
2	Truck Mounted Sonic Drill Sonic	Compact, damp to very moist, silty SAND. (FILL) - no odour or staining. - moist at 1.98m depth. - very moist at 3.35m depth.												Bentonite Seal
3														Filter Sand 9/24/2010
4		Very dense, dry, grey SILTSTONE/SANDSTONE. (Native) - no odour or staining.	3.76											Slotted 51mm dia. PVC Pipe
5		End of Monitoring Well.	4.50											

FILE NUMBER: GBA-PHCS-PROJECT: 132007N141200-1412-0081 (6000).CPJ Output Form: BOREHOLE (ENVRD) Template: BC REGION TEMPLATE BETA 1.GDT Library: BC REGION LIBRARY.GLB created: 21/12/10

DEPTH SCALE

1 : 25



LOGGED: L.W.

CHECKED: **DRAFT**