

BOREHOLE LOG

CLIENT: Davis & Company  
 JOB NO: 5-069-03.03  
 SITE LOCATION: 32700 Mission Way, Mission, B.C.

WELL NO: OW11  
 DATE: 92 03 05  
 DATUM: Surface

NORECOL SUPERVISOR: Della Berwanger  
 CONTRACTOR: Sonic Drilling  
 DRILLING TYPE: Sonic

INSTALLATION DETAILS  
 Screen Type - 5 cm diameter PVC, 0.25 mm slot  
 Sand Type - Silica 16B  
 Stick up well protector Bentonite - Chips

DEPTH metres	SOIL DESCRIPTION	Diagram	SAMPLE		BLOWS	OTHER
			INT	NAME		
	Surface Conditions: Grass					
0.0	Top soil and grass roots					
	Moist, brown, med grained SAND			31101		
1.0	Stiff, moist SILT with brown & grey layers 5 - 8 cm thick with orange mottling grades into grey fine SAND with orange mottling			31102		
2.0	grading into medium grained SAND with distinct rust stained layers			31103		
3.0				31104		water
4.0				31105		
5.0	Wet, grey, medium grained SAND musty odour			31006		
5.0	E.O.H.					
6.0	Screen Interval 1.5 - 4.6m					