

## Borehole Log Record

**Project:** 14041  
**Client:** Senior Living  
**Location:** 996-8 Gorge Road West  
 Victoria, BC  
**Borehole ID:** BH18

**Section:** 1  
**Date:** 11-Sep-14  
**Logged by:** Colleen Delaney  
**Drilled by:** Blue Max  
**Temp:** 15°C  
**Elevation:** 4 m asl



**\*For Environmental Purposes Only\***

**Sample Type:** Excavated Auger  
 Split Spoon Core

Depth (m)	Depth (ft)	Sample No.	Soil Description	Comments	Groundwater Well		Vapour Well	
Steel Road Box Cap								
0.00	0.00		Asphalt					
0.20	0.66	BH18-0.3 & Dup	Fill - sand and gravel, damp	Odour				
0.40	1.31							
0.60	1.97	BH18-0.6	Fill - Silty clay with sand & shells, woody debris at 1.55 m	Odour & Staining	GW	Solid 2" PVC pipe surrounded by Bentonite Clay	No Vapour Well as Water Table too High	
0.80	2.62							
1.00	3.28							
1.20	3.94	BH18-1.2		Odour				
1.40	4.59	BH18-1.55		Odour				
1.60	5.25							
1.80	5.90	BH18-1.85	Native - Silty clay, stiff, mottled grey/blue, trace stones & shells - damp	Odour & Staining				
2.00	6.56							
2.20	7.22							
2.40	7.87							
2.60	8.53	BH18-2.65	Native - Silty clay, stiff, mottled, grey/brown, trace shell, no stones, damp to moist	Odour		5' or 1.53m Screened 2" PVC pipe surrounded by silica filter sand		
2.80	9.18							
3.00	9.84	BH18-3.00		Slight Odour				
3.20	10.50	BH18-3.35						
3.40	11.15							
3.60	11.81							
3.80	12.46							
4.00	13.12							
4.20	13.78	BH18-4.2		Slight Odour				
4.40	14.43	BH18-4.5		Slight Odour				
4.60	15.09							
4.80	15.74							
5.00	16.40	BH18-5.05	Native - Silty clay, soft, grey, wet	Slight Odour				
5.20	17.06							
5.40	17.71							
5.60	18.37							
5.80	19.02	BH18-5.8		No Odour				
6.00	19.68							
6.20	20.34		Maximum Advancement - 6.1m					
6.40	20.99							
6.60	21.65							
6.80	22.30							
7.00	22.96							
7.20	23.62							
7.40	24.27							
7.60	24.93							
7.80	25.58							
8.00	26.24							
8.20	26.90							
8.40	27.55							
8.60	28.21							
8.80	28.86							
9.00	29.52							
9.20	30.18							
9.40	30.83							
9.60	31.49							
9.80	32.14							
10.00	32.80							